


NOTES:
1.) OWNER: ST. MICHAELS CHURCH P.O. BOX 1623

- 2.) TAX MAP 121, LOT 139
- 3.) LOT AREA: 14,877 SQ. FT, 0.34 Ac.
- 4.) S.C.R.D. BOOK 3924, PAGE 58
- 5.) ZONING: R2 TOTAL LOT AREA ~ 6,000SQFT. FRONTAGE ~ 60' FRONT YARD ~15' SIDE YARD ~ 8' REAR YARD ~ 25
- 6.) I HEREBY CERTIFY THAT, TO THE BEST OF MY KNOWLEDGE AND BELIEF, THIS PARCEL DOES NOT FALL WITHIN THE FLOOD PLAIN FLOOD HAZARD REF.: FEMA, MAP NO.: 33017C0216D DATED: MAY 17, 2005
- 7.) FOR MORE INFORMATION ABOUT THIS SUBDIVISION, CONTACT THE CITY OF ROCHESTER PLANNING DEPARTMENT, 31 WAKEFIELD STREET, ROCHESTER, NH 03867, (603) 335-1338.
- 8.) VERTICAL DATUM BASED ON ARBITRARY ELEVATIONS. HORIZONTAL DATUM BASED ON MAGNETIC BEARINGS TAKEN JUNE, 2011.

AUG 9 2011 Planding Dept. GRAPHIC SCALE ( IN PREET )




LAND OF
ST. MICHAELS CHURCH
TAX MAP 121, LOT 139
PINE STREET ROCHESTER, NH



BERRY SURVEYING & ENGINEERING 335 SECOND CROWN POINT RD. BARRINGTON, N.H. 332-2863 SCALE : 1 IN. EQUALS 20 FT.

JUNE 13, 201 DATE : FILE NO. : DB 2011-078

PAGE 1 OF



NOTES

1.) OWNER: ST. MICHAELS CHURCH P.O. BOX 1623 ROCHESTER, NH 03867

2.) TAX MAP 121, LOT 139

3.) LOT AREA: 14,877 SQ. FT, 0.34 Ac.

4.) S.C.R.D. BOOK 3924, PAGE 58

5.) ZONING: R2 TOTAL LOT AREA ~ 6,000SQFT. FRONTAGE ~ 60' FRONT YARD ~16' SIDE YARD ~ 8' REAR YARD ~ 25

7.) PROPOSED OPEN SPACE ~ 12,577 Sq.Ft, 0.29 AC 84.54% PROPOSED IMPERVIOUS COVER ~ 2,300 Sq.Ft., 0.05 AC, 48.50%

8.) I HEREBY CERTIFY THAT, TO THE BEST OF MY KNOWLEDGE & BELIEF, THIS PARCEL DOES NOT FALL WITHIN THE FLOOD PLAIN FLOOD HAZARD REF: FEMA COMMUNITY# — 330150, MAP# ~33017C0211D DATED: MAY 17, 2005 (ZONE X, OUTSIDE THE 0.2% ANNUAL CHANCE FLOOD PLAIN)

9.) PROPERTY LINE INFORMATION HAS BEEN OBTAINED FROM A SURVEY PERFORMED BY BERRY SURVEYING & ENGINEERING JUNE 2011 WITH AN ERROR OF CLOSURE GREATER THENF 1 IN 10,000.

10.) STREET ADDRESSES FOR THE BUILDING WILL BE INSTALLED PRIOR TO THE CERTIFICATE OF OCCUPANCY

11.) THE PROPOSED USE IS A CHURCH

12.) THIS SITE IS SERVICED BY MUNICIPAL SEWER AND WATER

13.) THERE ARE NO REVISIONS PROPOSED TO THE ON-SITE UTILITIES.

14.) ALL MATERIALS AND CONSTRUCTION SHALL CONFORM WITH APPLICABLE TOWN AND STATE CODES.

15.) ALL EROSION CONTROL NOTES SHALL INCLUDE PROVISIONS FOR CONSTRUCTION SEQUENCING, TEMPORARY EROSION CONTROL MEASURES, AND PERMANENT STANDARDS SUCH AS LOAM SPREAD RATE FOR DISTURBED AREAS, RATES OF LIME, TYPE AND RATES FOR FERTILIZER, AND SEED AND MULCH MIXTURE WITH RATES OF APPLICATION.

16.) ALL CONSTRUCTION SHALL CONFORM WITH THE STATE OF NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION".

17.) SWALE LINE IS TO BE LINED WITH SOD. ALL OTHERS TO BE LOAM AND SEED.

18.) ALL TEMPORARY LOAM STOCKPILES SHALL RECEIVE TEMPORARY EROSION CONTROL MEASURES.

19.) WRITTEN DIMENSIONS ON THIS PLAN TAKE PRECEDENCE OVER SCALED DIMENSIONS. THE CONTRACTOR SHALL USE CAUTION WHEN SCALING REPRODUCED PLANS. IN THE EVENT OF A CONFLICT BETWEEN THIS PLAN SET AND ANY OTHER DRAWINGS AND/OR SPECIFICATIONS, THE ENGINEER SHALL BE NOTIFIED BY THE CONTRACTOR.

20.) THE CONTRACTOR SHALL CALL AND COORDINATE WITH DIGSAFE 1-888-344-7233 PRIOR TO ANY EXCAVATION.

21.) A SIGN PERMIT IS TO BE OBTAINED PRIOR TO ITS CONSTRUCTION.

22.) SEE SNOW STORAGE AREAS. EXCESS SNOW IS TO BE TRUCKED OFF-SITE AND DISPOSED OF PROPERLY.

23.) HOURS OF OPERATION 8AM-9PM M-F, 6AM-9PM S&S. THERE WILL BE OCCASION OVERNIGHT STAYS. (LIMITED TO 4 PER MONTH) ASSOCIATED MUSIC WILL NOT EXTEND BEYOND 7AM-8PM

24.) CONSTRUCTION ACTIVITY RELATED TO THIS SITE IS LIMITED TO 7:00 A.M. TO 6:00 P.M. MONDAY THROUGH FRIDAY AND 8:00 A.M. TO 6:00 P.M. SATURDAY,

25.) ALL OFF-SITE IMPROVEMENTS REQUIRED FOR THIS PROPOSAL WILL BE COMPLETED PRIOR TO THE ISSUANCE OF A CERTIFICATE OF OCCUPANCY. (NONE REQUIRED)

26.) THIS PLAN PROPOSES 8,000 Sq.Ft., OF DISTURBANCE

27.) THIS PLAN IS DESIGNED TO ACCOMMODATE A SU SIZED VEHICLES

28.) A FIRE SUPPRESSION SYSTEM IS NOT INCORPORATED AS PART OF THESE PLANS.

29.) THERE IS OVER 400' FEET OF SIGHT DISTANCE IN BOTH THE NORTH AND SOUTH DIRECTIONS.

30.) FIND "STORMWATER SYSTEM OPERATION AND MAINTENANCE PLAN AND INSPECTION AND MAINTENANCE MANUAL" MAINTENANCE AND INSPECTION REQUIRED IN THIS REPORT IS REQUIRED PER THIS SITE PLAN.

31.) REFUSE WILL BE PLACED CURB SIDE IN THE PROVIDED TOAT

32.) PARKING ON PINE STREET IS DISCOURAGED DURING SUMMER MONTHS AND PROHIBITED DURING WINTER MONTHS.

33.) COMPACTION OF PARKING AREA WILL BE DONE WITH A VIBRATORY ROLLER ON A "LOW" SETTING SO AS NOT TO HARM SURROUNDING RESIDENTIAL STRUCTURES.

34.) If during construction dbris is deposited in Pine street the applicant is required to sweep and clean. Inspections should be done every afternoon.


35.) IT IS THE APPLICANTS RESPONSABILITY TO ENSURE NO DUST IS CREATED FROM THE USE OF THIS PARKING LOT. WATERING METHODS AND THE USE OF ADDITIVES IS REQUIRED IF AIR BORN DUST OCCURS.


REVISION DATE DESCRIPTION

PROPOSED SITE PLAN
LAND OF
ST. MICHAELS CHURCH
TAX MAP 121, LOT 139
PINE SITRET
ROCHESITER: NH



PAGE 2 OF





- 4" AGED PINERARK MULCH AND A WEED BARRIER (TY-PAR FABRIC OR APPROVED EQUAL) SHALL BE APPLIED TO ALL SHRUB AND GROUND COVER BEDS. INSTALL WEED

NOTES:

- 5.) ALL PLANT MATERIALS SHALL BE FREE FROM INSECTS AND DISEASE.
- 6.) ALL PLANTINGS SHALL BE DONE IN ACCORDANCE WITH ACCEPTABLE HORTICULTURAL PRACTICES. THIS IS TO INCLUDE PROPER PLANTING MIX, PLANT BED AND TREE PIT PREPARATION, PRUNING STAKING OR GUYING, WRAPPING, SPRAYING, FERTILIZATION, PLANTING AND ADEQUATE MAINTENANCE UNTIL ACCEPTANCE FROM OWNER.
- 7.) ALL GRASS, OTHER VEGETATION AND DEBRIS SHALL BE REMOVED FROM ALL PLANTING AREAS PRIOR TO PLANTING.
- 8.) THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE 8.) THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF EXISTING AND NEWLY PLANTED TREES AND SHRUBS DURING THE CONSTRUCTION PROCESS. WHERE REQUIRED, THE CONTRACTOR SHALL INSTALL TEMPORARY FENCING (SNOW OR EQUAL) AROUND EXISTING TREES AND SHRUBS THAT COULD BE IMPACTED BY THE CONSTRUCTION PROCESS. STORAGE OF CONSTRUCTION EQUIPMENT, CONSTRUCTION MATERIALS, SNOW STORAGE AND OR VEHICLE PARKING SHALL NOT BE PERMITTED WITHIN THE DRIP LINE OF TREES OR TWENTY FEET WHICH EVER IS GREATER.
- 9.) NEW PLANTINGS SHALL BE INSTALLED PER PROJECT DRAWINGS AND SPECIFICATION THAT INCLUDE FERTILIZATION AND MULCHING AS
- 10.) ALL SHRUB BEDS AND TREE PITS SHALL BE MULCHED WITH  $3^{\prime\prime}$  CLEAN SHREDDED BLACK MULCH
- 11.) WHERE INDICATED ON PLAN, PLANTING SOIL MIXTURE FOR GROUND COVER AND PERENNIAL BED AREAS SHALL CONSIST OF FOUR PARTS TOPSOIL, TWO PARTS SPHAGNUM PEAT MOSS, AND ONE PART HORTICULTURAL PERUTE BY YOLUME. PEAT MOSS MAY BE SUBSTITUTED WITH WELL-ROTTED OR DEHYDRATED MANURE OR COMPOST. ROTOTILL BEDS TO A DEPTH OF 8 INCHES.
- 12.) MAINTENANCE OF NEW PLANTINGS AND LAWNS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR AND OR LANDSCAPE SUBCONTRACTOR UNTIL ACCEPTANCE BY THE OWNER. RESPONSIBILITIES SHALL INCLUDE WATERING WEEDING AND MOWING AS NECESSARY. ALL PLANT MATERIAL, SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR FROM THE DATE OF ACCEPTANCE, REPLACEMENT MATERIAL SHALL BE GUARANTEED FOR AND ADDITIONAL YEAR FROM TIME OF INSTALLATION.
- 13.) THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL TEMPORARY EROSION CONTROL MEASURES DURING THE CONSTRUCTION PHASE AND UNTIL ALL AREAS HAVE BEEN STABILIZED AND ACCEPTED BY THE OWNER. THE GENERAL CONTRACTOR SHALL PROVIDE WEEKLY INSPECTIONS OF EROSION MEASURE AND IMMEDIATELY AFTER STORM EVENTS AND REPAIR AS NECESSARY.
- 14.) THE GENERAL CONTRACTOR AND THE OR THE LANDSCAPE SUBCONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL TREE GUYING MATERIAL ONCE PLANT MATERIAL HAS BEEN ESTABLISHED. (MINIMUM of one growing season). All temporary erosion control measure shall be removed once stabilization of disturbance has been accepted by owner.
- 15.) THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR A MINIMUM OF TWO MOWING FOR ALL TURF AREAS OR UNTIL ACCEPTANCE BY THE OWNER. A MINIMUM UNIFORM 75% CATCH OF TURF IS REQUIRED FOR ACCEPTANCE.
- 16.) ALL PLANTINGS SHALL BE WATERED REGULARLY DURING THEIR FIRST YEAR AND MAINTAINED PERMANENTLY IN GOOD GROWING CONDITION AS AN EFFECTIVE VISUAL SCREEN.
- 17.) SHRUBS OR TREES WHICH DIE SHALL BE REPLACED WITHIN ONE GROWING SEASON WITH NEW SHRUBS OR TREES TO ENSURE CONTINUED COMPLIANCE WITH APPLICABLE LANDSCAPING REQUIREMENTS.

MAINTENANCE PLAN:

LAWNS MOWN 39 TIMES A YEAR.

LAWNS FERTILIZED 3 TIMES A YEAR

GARDEN WEEDED MONTHLY

TREES AND SHRUBS PRUNED AFTER FLOWERING OR FOR SHAPE WHEN THEY REQUIRE

HEDGES TRIMMED TWICE A YEAR

PEST AND DISEASE CONTROL OF LAWNS AND GARDEN

MAINTAIN BARK AND MULCH LEVELS

FEED FRUIT AND CITRUS TREES ANNUALLY

TREAT PATIOS, DRIVEWAYS AND OUTDOOR FURNITURE FOR MOSS AND MOULD


SERVICE IRRIGATION SYSTEM IN SPRING AND ADJUST SEASONALLY.


곳 왕 ST

ERIN( ROAD 2863 CROWN F. N.H. ્શ્ર કહ્યું 335 SECON BARRINGTA SCALE : R

A. BERRY

PAGE 4 OF





). WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES AND FILTER CLOTH SHALL BE FASTENED TO WOVEN WIRE EVERY 24" AT TOP MID AND BOTTOM SECTIONS AND BE EMBEDDED INTO GROUND A MINIMUM OF 8" THE FENCE POSTS SHALL BE A MINIMUM 48° LONG, SPACED A

MENUMUM 49 LUNIS, SHACED A

2. MAXIMUM 10' APART, AND DRIVEN A MINIMUM OF 16° INTO THE GROUND WHEN TWO SECTIONS
OF FILTER CLOTH ADJOIN EACH OTHER,

3. THE ENDS OF THE FABRIC SHALL BE OVERLAPPED BY SIX INCHES, FOLDED AND STAPLED TO
PREVENT SEDIMENT FROM BY—PASSING MAINTENANCE SHALL BE PERFORMED AS NEEDED AND
SEDIMENT

SEDIMENT
4. REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE AND PROPERLY DISPOSED OF PLACE THE
ENDS OF THE SILT FENCE UP CONTOUR TO PROVIDE
5. FOR SEDIMENT STORAGE SILT FENCES SHALL BE REMOVED WHEN NO LONGER NEEDED AND
6. THE SEDIMENT COLLECTED SHALL BE DISPOSED AS DIRECTED BY THE ENGINEER. THE AREA
DISTURBED BY THE REMOVAL SHALL BE SMOOTHED AND RE-VEGETATED

SILT FENCE MAINTENANCE

1. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REPAIRS THAT ARE REQUIRED SHALL BE MADE IMMEDIATELY IF THE FABRIC ON A SILT FENCE SHOULD DECOMPOSE OR BECOME

2. INEFFECTIVE DURING THE EXPECTED LIFE OF THE FENCE, THE FABRIC SHALL BE REPLACED PROMPTLY. SEDIMENT DEPOSITS SHOULD BE INSPECTED AFTER EVERY STORM

EVENT.
3. THE DEPOSITS SHOULD BE REMOVED WHEN THEY REACH APPROXIMATELY ONE HALF
THE HEIGHT OF THE BARRIER. SEDIMENT DEPOSITS THAT ARE REMOVED OR LEFT IN PLACE
AFTER THE
4. FABRIC HAS BEEN REMOVED SHALL BE GRADED TO CONFORM WITH THE EXISTING

TOPOGRAPHY AND VEGETATED.

SILT FENCE DETAIL

E 1

STABILIZED CONSTRUCTION ENTRANCE N.T.S. FRITTER CLOSHas sex d 10" BEN. DUSTRIG

PLAN VIEW 1. STONE FOR A STABILIZED CONSTRUCTION ENTRANCE SHALL BE 1 TO 2 INCH STONE, RECLAMED STONE, OR RECYCLED CONCRETE EQUIVALENT.

THE LENGTH OF THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN SO FEET, EXCEPT FOR A SHIGLE RESPENDAL LOT WHERE A 30 FOOT MARKAY LENGTH WORLD APPLY.

3. THE THICKNESS OF THE STONE FOR THE STANGLIZED ENTRANCE SHALL NOT BE LESS THAN 8 INCHES.

4. THE WIDTH OF THE ENTRANCE SHALL NOT BE LESS THAN THE FULL WIDTH OF THE ENTRANCE WHERE INGRESS OR EGRESS OCCURS OR 10 FEET, WHICH EVER IS GREATER.

GEOTEXTILE FILTER CLOTH SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACEK THE STONE, FILTER CLOTH IS NOT REQUIRED FOR A SINGLE FAMILY RESIDENCE LOT.

7. THE ENTRANCE SHALL BE MARTIARNED BY A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDMENT ONTO PUBLIC ROTHOS—OF—WAY. THIS MAY REQUIRE PERMODE TO PERSONA WITH ADDITIONAL STONE AS CONDITIONS DEBAND, AND REPAR AND/OR CLEAR OUT OF ANY MESSARES USED TO TRAP SEDMENT. ALL SEDMENT SPILLED, WASHED, OR TRACKED ONTO PUBLIC ROGHT—OF—WAY MUST BE REMOVED PROPERTY.

THE DISTANCE SUCH THAT POINTS A AND 8 ARE OF EQUAL ELEVATION.

SPACING BETWEEN STRUCTURES

1.) CHECK DAMS SHOULD BE INSTALLED BEFORE RUNOFF IS DIRECTED TO THE SWALE OF DRAINAGE DITCH

2.) THE MAXIMUM CONTRIBUTING DRAINAGE AREA TO THE DAM SHOULD BE LESS THEN ONE ACRE. 3.) THE MAXIMUM HEIGHT OF THE DAM SHOULD BE TWO FEET.

4.) THE CENTER OF THE DAM SHOULD BE AT LEAST SIX INCHES LOWER THAN THE OUTER EDGES.

5.) THE MAXIMUM SPACING IS AS SHOWN ON THE PROJECT SITE PLANS.

6.) CHECK DAMS WILL NOT BE USED IN A FLOWING STREAM.

7.) TEMPORARY CHECK DAMS WILL BE REMOVED ONCE THE SWALE OR DITCH IS DETERMINED STABLE.

6"

NOTE: KEY STONE INTO CHANNEL BANKS AND EXTEND IT BEYOND THE

ABUTMENTS A MINIUM OF 18" TO PREVENT FLOW AROUND THE DAM.

E9

ANGULAR STONE FLOW STONE GRADE STABILIZATION STRUCTURE PROTECTED FLOW SILT FENCE/HAYBALE BARRIER DETAIL

THIS METHOD TO BE USED AT ALL LOCATIONS WHERE CONSTRUCTION IS

AS NOTED ON PLAN


GRASS TREATMENT SWALE

NOT TO SCALE

BASE WIDTH

E6

E3



BALES TO REMARK UNTIL SUBBASE PREPARATION IS COMPLETE AND PAYING IS TO BEGIN ON UNTIL ALL UPSTREAM AREAS ARE STARBUTED WITH VECTABORS.

CONSTRUCTION SPECIFICATIONS FOR STRAW OR HAY BALE BARRIERS

STRUCTURES SHALL BE INSTALLED ACCORDING TO THE DISENSERS SHARN ON THE PLANS AT THE APPROPRIATE SPACING.

2. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER SO THAT EROSION AND AIR AND WATER POLLUTION WILL BE MANNZED.

3. WHEN MAY BALES ARE USED, THE BALES SHALL BE EMBEDDED AT LEAST 4 INCRES MITO THE SOLL WHEN TRABER STRUCTURES ARE USED, THE TRABER SHALL EXTERD AT LEAST 18 INCRES INTO THE SOLL.


4. HAY OR STRAW BALES SHALL BE ANCHORED INTO THE SOIL USING 2" X 2" STAKES DRIVEN THROUGH THE BALES AND AT LEAST 18 INCHES 1970 THE SOIL.

SEEDING, FERTILIZING, AND SMALCHING SHALL CONFORM TO THE RECEMBED IN THE APPROPRIATE VEGETATIVE SMP.

4. STRUCTURES SHALL BE REMOVED FROM THE CHANNEL WHEN THEIR USEFUL LIFE HAS SEEN COMPLETED.

BLOCK AND CRAVEL DROP MALEY SEDMENT FRIER

SEDIMENT CONTROL AT CATCH BASINS



TEMPORARY EROSION CONTROL MEASURES

1. THE SMALLEST PRACTICAL AREA OF LAND SHALL BE EXPOSED AT ANY ONE TIME

2. EROSION, SEDIMENT AND DETENTION MEASURES SHALL BE INSTALLED AS SHOWN ON THE PLANS AND AT LOCATIONS AS REQUIRED, DIRECTED BY THE ENGINEER

3. ALL DISTURBED AREAS SHALL BE RETURNED TO ORIGINAL GRADES AND ELEVATIONS. DISTURBED AREAS SHALL BE LOAMED WITH A MINIMUM OF 4" OF LOAM AND SEEDED WITH NOT LESS THAN ONE POUND OF SEED PER 50 SQUARE YARDS OF AREA. (SEE SEED SPECIFICATIONS THIS SHEET)

3a. ALL DISTURBED AREAS WILL BE RESTABILIZED WITHIN 60 DAYS. AT ANY ONE TIME, NO MORE THAN 5 ACRES, (217,800 Sq. Ft.) WILL BE DISTURBED.

4. SUIT FENCES AND STRAW OR HAY BALES BARRIERS SHALL BE INSPECTED PERIODICALLY AND AFTER EVERY RAIN DURING
THE LIFE OF THE PROJECT. ALL DAMAGED AREAS SHALL BE
REPAIRED, SEDIMENT DEPOSITS SHALL PERIODICALLY BE REMOVED AND DISPOSED OF.

5. AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED, THE TEMPORARY EROSION CONTROL MEASURES ARE TO BE REMOVED AND THE AREA DISTURBED BY THE REMOVAL SMOOTHED AND

6. PER THE EPA REQUIREMENTS THERE WILL BE A LOG OF THE EROSION CONTROL INSPECTIONS EVERY 7-14 DAYS PLEASE FIND SWPPP PREPARED BY BS&E (AFTER LOCAL APPROVAL)

DITCHES, SWALES, AND BASINS SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.

8. ALL EROSION CONTROLS SHALL BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER 0.5" OR GREATER RAIN EVENT

E7

E11

MAINTENANCE

ALL STRUCTURES SHOULD BE INSPECTED AFTER EVERY RAIN STORM AND REPAIRS MADE AS NECESSARY. SEDIMENT SHOULD BE REMOVED FROM TRAPPING DEVICES AFTER THE SEDIMENT HAS REACHED A MAXIMUM OF ONE HALF THE DEPTH OF THE TRAP. THE SEDIMENT SHOULD BE DISPOSED OF IN A SUITABLE AREA AND PROTECTED FROM ERGOSION BY EITHER STRUCTURE OR VEGETATIVE MEANS. THE TEMPORARY TRAPS SHOULD BE REMOVED AND THE AREA REPAIRED AS SOON AS THE CONTRIBUTING DRAINAGE AREA TO THE INLET HAS BEEN COMPLETELY

BLOCK & GRAVEL DROP

INLET SEDIMENT FILTER

NOT TO SCALE

WINTER STABILIZATION NOTES

1. All disturbed areas that do not have at least 85% vegetative coverage prior to October 15th, shall be stabilized by applying mulch at a rate of 3-4 tons per acre. All side slopes, steeper than 4:1, that are not directed to swales or detention basins, shall be lined with biodegradable/photodegradable "jute matting" (Excelsion's Curiex II or equal). All other slopes shall be mulched and tacked at a rate of 3-4 tons per acre. The application of mulch and/or jute matting shall not accurr over existing snow cover. If the site is active after November 15th, any snow that accurrulates on disturbed areas shall be removed. Prior to spring thaw all areas will be stabilized, as directed above.

2. All swales that do not have fully established vegetation shall be either lined with temporary jute matting or temporary stone check dams (appropriately spaced). Stone check dams will be maintained throughout the winter months. If the swales are to be matted with permanent liners or riprap with engineering fabric, this shall be completed prior to winter shutdown or as soon as they are properly graded and shaped.

3. Prior to Nov. 15th all roadway and parking areas shall be brought up to and through the bank run gravel application. If these areas' elevations are proposed to remain below the proposed subgrade elevation, the subgrade material shall be proughly crowned and to 3" layer of crushed gravel shall be placed and compacted. This will allow the subgrade to shed runoff and will reduce roadway erosion. This crushed gravel does not have to conform to NH DOT 304.3, but shall have between 15-25% passing the #200 sleve and the largest stone size shall be 2". If the site is active after November 15th, any accumulated snow shall be removed from all roadway and parking areas.


4. After October 15th, the end of New Hampshire's average growing season, no additional loam shall be spread on side slopes and swales. The stockpiles that will be left undisturbed until spring shall be seeded by this date. After October 15th, any new or disturbed piles shall be mulched a orate of 3—4 tons per acre. All stockpiles that will remain throughout the winter shall be surrounded with silt fencing.

RING ROAD 2-2863 SURVEYING— ENGINEER CROWN POINT R NH 03825 {332— AS MARKED S Scond Ton, 1 RRY 335 BARRIN SCALE DATE BE

PROPOSED SITE PLAN
LAND OF
ST. MICHAELS CHURCH
AX MAP 121, LOT 139
PINE STREET
ROCHESTER, NH

A. BERRY No. 1088

- 4" (MIN.) LOAM, SEEDED



INSPECT ANNUALLY FOR EROSION, SEDIMENT ACCUMULATIONS, VEGETATION LOSS, & INVASIVE SPECIES. REPAIR AS NECESSARY.

EXISTING FARTH

MOW GRASS ANNWALLY TO A DEPTH OF 4".

E10

INLET FILTER BASKET

FILTER BASKET NOTES: INLET BASKETS SHALL BE USED ON ALL CATCH BASINS WITHIN THE PROJECT LIMITS DURING CONSTRUCTION. INLET FILTER BASKETS SHALL BE "METAL-ERA" OR APPROVED EQUAL.

2.) FILTER FABRIC SHALL BE PUSHED DOWN AND FORMED TO THE SHAPE OF THE BASKET. THE SHEET OF FABRIC SHALL BE LARGE ENOUGH TO BE SUPPORTED BY THE BASKET FRAME WHEN HOLDING SEDIMENT AND EXTEND AT LEAST 6 INCHES PAST THE FRAME. THE NILET GRATE SHALL BE PLACED OVER THE BASKET/FRAME AND WILL SERVE AS THE FABRIC ANCHOR.

THE FILTER FABRIC SHALL BE A GEO—TEXTILE FABRIC: POLYESTER, POLYPROPYLENE, STABILIZED NYLON, POLYETHYLENE OR POLYMINILDENE CHLORIDE MEETING THE FOLLOWING SPECIFICATIONS:

GRAB STRENGTH: 45 lb. MINIMUM IN ANY PRINCIPAL DIRECTION (ASTM 01682).

MULLEN BURST STRENGTH: MINIMUM 60 psi (ASTM D774). 4.) THE FABRIC SHALL HAVE AN OPENING NO GREATER THAN A NUMBER 20 U.S. STANDARD SIEVE AND MINIMUM PERMEABILITY OF 120 gpm/sq. ft.

5.) THE INLET BASKET SHALL BE INSPECTED WITHIN 24 HOURS AFTER EACH RAINFALL OR DAILY DURING EXTENDED PERIODS OF PRECIPITATION. REPAIRS SHALL BE MADE IMMEDIATELY, AS NECESSARY, TO PREVENT PARTICLES FROM ENTERING THE DRAINAGE PIPING SYSTEM AND/OR CAUSING SURFACE FLOODING.

INLET BASKETS SHALL BE MAINTAINED IN PLACE UNTIL ALL PAVING IS COMPLETED AND ALL UNPAVED AREAS HAVE BEEN STABILIZED WITH VEGETATION.

