


PROPOSED WAREHOUSE EXPANSION

COLBY FOOTWEAR, INC. 15 OAK STREET & NH ROUTE 125

MARCH 2012

ROCHESTER, NEW HAMPSHIRE 03867



CIVIL ENGINEERS

NORWAY PLAINS ASSOCIATES, INC. 2 CONTINENTAL BOULEVARD ROCHESTER, NH 03867 (603) 335-3948





OAK STREET COLBY OVERALL SITE 1" = 100'

AECENED. MAR 2 8 2012

Paning Day

OWNER / APPLICANT

COLBY FOOTWEAR, INC. 364 ROUTE 108 SOMERSWORTH, NH 03878 (800) 970-8482

CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION, CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE

SHEET INDEX OVERALL SITE PLAN EXISTING FEATURES PLAN SITE LAYOUT PLAN GRADING AND DRAINAGE PLAN UTILITY PLAN CONSTRUCTION DETAILS AS SHOWN

PLAN NO. PERLIM DWG NO. 12009\SP-2

SEPTIC SYSTEM DESIGNERS LAND SURVEYORS LEGEND 102.01' PROPERTY LINE --- COMMON PROPERTY LINE ______ JURISDICTIONAL WETLANDS BUILDING SETBACK LINES - 70NING DISTRICT BOUNDARY LINE EXISTING TREE LINE WETLANDS EXISTING MONUMENTS CONTROL PROPOSED TREE LINE MAP 13B — LOT 91 FRANK P., ANTONIO J., EVANGELINA FIGUERDO & SILVIA R. WEEKS P. D. BOX 7084 ROCHESTER, NH 03866-7084 DIG SAFE MAP 138 - LOT 90 -MAURICE A & ARLENE M. LAMPER 27 PATRIOTS WAY ROCHESTER, NH 03839 MAP 138 LOT 88 DONALD DAGGETT 31A DAK STREET ROCHESTER, NH 03839-5630 EXISTING EDGE OF — IURISDICTIONAL WETLANDS AS DELINEATED BY GZA GEOENVIRONMENTAL, INC. MAP 13B - LOT 89 61*02*02* 60.00* EXIST. 6x6" \$05° MAP 138 LOT 76 MAP 138 LOT 77 S 58*59'25" MAP 138 - LOT 80 PROPOSED 2-STORY 37,305 SF FOOTPRINT WAREHOUSE BUILDING 25' FRONT-MAP 138 - LOT 79 30,372 SF STREET BUILDING COLBY N 81 23'56" OAK STREET JERI VANDENBOSCH LIVING TRUST PO BOX 586 BARRINGTON, NH 03825 MAP 138 LOT 61 MAP 138 — LOT 59 GERALD F. & THERESA GILMAN 22 DAX STREET ROCHESTER, NH 03839—5631 MAP 138 LOT 60 MAP 138 - LOT 58-LAWERENCE & CHRISTIE
LAPIERRE
20 OAK STREET
ROCHESTER, NH 03839 MAP 138 - 10T 48 PLE REALTY, LLC
68 TEN ROD ROAD
COCHESTER, NH 03861 MAP 138 - LOT 57 BEYL MUGGELSTON IRREVOCABLE

REFERENCE PLANS:

FILE NO. 288

F.B. NO. SDR

PLAN NO. PERLIM

DWG NO. 12009\SP-2

"PLAN OF LAND - COLBY FOOTWARE, INC. - GONIC, N.H." DATED AUGUST 1967 BY G.L. DAVIS & ASSOCIATES AND RECORDED AT STRAFFORD COUNTY REGISTRY OF DEEDS, PLAN 5, POCKET 12, FOLDER 1.

"LOTS OWNED BH H.H. MEADER - GONIC, N.H" DATED APRIL 1921 BY WILLIAM A. GROVER AND RECORDED AT STRAFFORD COUNTY OF REGISTRY OF DEEDS.

"STATE OF NH DEPARTMENT OF PUBLIC WORKS & HIGHWAY - ROCHESTER F-019-1(2) S-2437 (GONIC PROJECT)" DATED 1955.

31 Mooney Street, Alton, N.H. 603-875-3948

FINIAL APPROVAL BY THE ROCHESTER PLANNING BOARD

TRANSPORTATION PLANNERS CIVIL ENGINEERS

SITE REVIEW APPROVAL

WHETHER OR NOT OTHERWISE EXPRESSLY RECITED ON THIS SITE REVIEW PLAN, THE SITE REVIEW APPROVAL GRANTED IS CONDITIONED ON FAITHFUL AND DILIGENT ADHERENCE BY THE OWNER/DEVELOPER TO ALL WRITTEN AND VERBAL REPRESENTATIONS MADE REGARDING SUCH MATTERS AS USE, NUMBER OF EMPLOYEES, DRAINAGE, CONSTRUCTION, ETC. AS WELL AS ALL OTHER TERMS, CONDITIONS, PROVISIONS, REQUIREMENTS AND SPECIFICATIONS OF THE SITE PLAN REVIEW REGULATIONS OF THE CITY OF ROCHESTER, N.H., AS AMENDED, IN EFFECT ON THE DATE OF APPROVAL. ANY VARIATION FROM THE PROPOSAL AS APPROVED MAY ALSO REQUIRE THE SUBMISSION AND APPROVAL OF A NEW SITE REVIEW APPLICATION.

REVISE PROPOSED BUILDING CONFIGURATION

CENERAL SITE PLAN NOTES:

1. THE PURPOSE OF THIS PLAN IS TO DEPICT A 38.275 S.F. 2-STORY WAREHOUSE ADDITION TO THE EXISTING BUILDING.

2. TOTAL PARCEL AREAS: MAP 138, LOTS 79 & 80

3.54 ACRES.

3. PARCEL IS ZONED BUSINESS—2 & RESIDENCECE—1.

3. ALL EXISTING UTILITIES LOCATIONS ARE APPROXIMATE AS SHOWN. THE CONTRACTOR SHALL VERIEY THEIR EXACT LOCATION PRIOR TO ANY WORK BEING PERFORMED.

4. THE STRING UTILITIES LOCATIONS ARE APPROXIMATE AS SHOWN. THE CONTRACTOR SHALL VERIEY THEIR EXACT LOCATION PRIOR TO ANY WORK BEING PERFORMED.

5. DIMENSIONAL REGULATIONS PER ZONING DRINNING. IS NOT INTENDED OR IMPLIED.

5. DIMENSIONAL REGULATIONS PER ZONING DRINNING. IS NOT INTENDED OR IMPLIED.

5. DIMENSIONAL REGULATIONS PER ZONING DRINNING.

6. DIMENSIONAL DRINGE — NO REGULATIONS (WITH WATER AND SEWER)

6. DIMENSIONAL DRINGE — SONE EXCEPT WHERE FRONTAGE IS PARTLY RESIDENCE AND PARTLY BUSINESS, THEN 25 FEET.

6. SIDE — NONE EXCEPT WHERE ABUTS RESIDENCE 1 ZONE, THEN 10 FEET RAR — 25 FEET |

6. DIMENSIONAL DRINGE — 100 FEET |

6. MINIMUM LOT SIZE — 10,000 SQUARE FEET (WITH WATER AND SEWER)

6. MINIMUM LOT SIZE— 10,000 SQUARE FEET (WITH WATER AND SEWER)

6. MINIMUM LOT SIZE— 10,000 SQUARE FEET (WITH WATER AND SEWER)

6. MINIMUM LOT SIZE— 10 FEET |

6. PRIOR 10 LOCATED WITH ZONE A (100 YR FLOOD) AS SHOWN ON FEDERAL EMERGENCY MANAGEMENT AGENCY MAP. COMMUNITY #3301750216D.

7. ORIENTATION HOR ROZONAL AND VERTICAL DATUMS — CITY OF ROCHESTER OIS.

8. ORIENTATION HOR ROZONAL AND VERTICAL DATUMS — CITY OF ROCHESTER OIS.

9. SOIL TYPES ARE PER NATIONAL RESOURCES CONSERVATION SERVICES.

80 AC — SWANTON FINE SANTON LAND TO THIS SITE PLAN, CONTRACT THE CITY OF ROCHESTER DIS.

9. SOIL TYPES ARE PER NATIONAL RESOURCES CONSERVATION SERVICES.

80 AC — SWANTON FINE SANTON LAND TO THIS SITE PLAN, CONTRACT

PARKING PROURTMENTS (CONTING REGS. SECTION 42.2(b)(19):
WHOLESALE DISTRIBUTION, WAREHOUSE:
1 SPACE PER BOD SOURCE FEET OF GROSS FLOOR AREA (GFA); OR, 1 SPACES PER EMPLOYEE IN THE MAXIMUM SHIFT; WHICHEVER IS GREATER:

TOTAL SPACES EXISTING: 30,372 SF GFA X 1 SPACES / 800 SF GFA = 09. 3B SPACES 20 EMPLOYEES x 1 SPACE / EMPLOYEE m 20 SPACES PROPOSED: 71,610 SF GFA X 1 SPACES / 800 SF GFA == 90 SPACES 11 SPACES 11 EMPLOYEES x 1 SPACE / EMPLOYEE =

128 SPACES OR 31 SPACES 82 SPACES

ACCESSIBLE PARKING (SITE PLAN REGULATIONS SECTION 6(D)(3)): THE SPACES ARE PART OF THE TOTAL ABOVE.
ACCESSIBLE PARKING SPACES = 76 TO 100 = 4 SPACES SPACES SPACES SPACES = 4 SPACES S

ALL CONSTRUCTION ACTIVITY RELATED TO THE DEVELOPMENT OF THIS SITE IS NOT RESTRICTED.

LOAM STOCKPILES SHALL BE SEEDED IN ACCORDANCE WITH THE SEEDING NOTES ON SHEET C-5, IF STORED MORE THAN 30 DAYS. SILT FENCE SHALL BE INSTALLED AT THE DOWN GRADIENT SIDE OF THE LOAM STOCKPILE AS SHOWN IN THE PLAN VIEW AROUND AT LEAST ONE HALF THE CIRCUMFERENCE OF THE PILE.

PRIZE ALL OF THE DURN SKADENT SIDE OF THE LOAM STOCKPILE AS SHOWN IN THE PLAN VEW AROUND AT LEAST ONE HALF THE CIRCUMFERENCE OF THE PILE.

DILFING ALL PHASES OF CONSTRUCTION DUST SHALL BE PREVENTED FROM BECOMING A SAFETY OR HEALTH HAZARD BY THE IMPLEMENTATION OF ACCEPTED CONTROL METHODS SUCH AS WATERING.

THE CITY RESERVES THE RIGHT TO REQUIRE ADDITIONAL EROSON CONTROL MEASURES IF ANY OFF—SITE IMPACTS ARE FOUND DURING CONSTRUCTION, ALL UTILITIES MUST BE UNDERGROUND, INCLIDING STRITUSE EXTENDED ONTO THE SITE FROM EXISTING SHES SHEST SITE.

ACCESS INTO THE SITE FOR FIRE APPARATUS MUST BE MAINTAINED AT ALL THESE DURING THE CONSTRUCTION PROCESS. THIS IS THE SOLE RESPONSIBILITY OF THE APPLICANT/DEVELOPER TO MAINTAIN THIS ACCESS. PLEASE CONTACT THE FIRE DEPARTMENT AT 330—7182 WITH ANY QUESTIONS AGOUT THE ACCESS REQUIREMENTS.

THIS DEVELOPMENT MUST BE IN COMPLIANCE WITH ALL APPLICABLE LAW — INCLIDING ALL PERTINENT PROVISIONS OF THE CITY OF ROCHESTER SITE. PLAN ESCILLATIONS.— UNLESS DITHER WISSED WAVED.

FINAL SIGN APPLICATIONS MUST BE SUBMITTED TO THE CODE ENFORCEMENT OFFICER TO ENSURE COMPLIANCE WITH ALL APPLICABLE CODES, INDEPENDENT FROM THIS SITE PLAN REVIEW, IF ANY SUBMIFICANT CHANGES OR EXPANSION IS PROPOSED TO THE DESIGN OF THE APPROVED FREESTADING SIGN OR TO THE OVERALL ADDRESSION SIGNAGE FOR THIS SITE, THE PROPOSED SIGN MUST BE PRESENTED TO THE PLANNING BOARD FOR REVIEW PRIOR TO ISSUANCE OF THOSE PERMITS.

A KNOX BOX SHALL BE PROVIDED AS SPECIFIED BY THE ROCHESTER FIRE PERMITMENT.

TRUCK PERMIS.

A KNOX BOX SHALL BE PROVIDED AS SPECIFIED BY THE ROCHESTER FIRE DEPARTMENT.

THIS SITE IS DESIGNED TO BE COMPLIANT WITH AMERICAN DISABILITY ACT FOR ACCESS TO THE PROPOSED BUILDING FROM THE PARKING AND UNLOADING

21. THIS SITE IS DESIGNED TO BE COMPLIANT WITH AMERICAN DISABILITY ACT FOR ACCESS TO THE PROPOSED BUILDING FROM THE PARKING AND UNLDADING ZOOMERS.

22. ALL ELEMENTS SHOWN ON THE APPROVED SITE PLANS MUST BE PROPERLY COMPLETED PRIOR TO ISSUANCE OF A CERTIFICATE OF DOCUPANCY, UNLESS APPROPRIATE SURFEY IS PLACED WITH THE PLANNING DEPARTMENT.

23. THIS PROJECT PROPOSED TO DISTURB OVER ONE ACRE OF EXISTING GROUND COVER AND MEETS OTHER SPECIFIC REQUIREMENTS RELATED TO PERMIT CRITERIA FOR EPA NAPISE COMPLIANCE. THE CONTRACTOR IS RESPONSIBLE FOR DEVELOPMENT AND MEJEMENTATION OF A STORM WATER POLLITION PREVENTION PLAN (SWPPP), SUBMISSION OF A NOTICE OF TERMANDAY MAD MAINTENANCE ACTIVITIES, AND SUBMISSION OF A NOTICE OF TERMANDAY MAD MAINTENANCE ACTIVITIES, AND SUBMISSION OF A NOTICE OF TERMANDAY MAD MAINTENANCE ACTIVITIES, AND SUBMISSION OF A NOTICE OF TERMANDAY MAD MAINTENANCE ACTIVITIES, AND SUBMISSION OF A NOTICE OF TERMANDAY MAD MAINTENANCE ACTIVITIES, AND SUBMISSION OF A NOTICE OF TERMANDAY MAD MAD MAD MAD AND MAD REPORT OF THE ACTIVITIES AND SUBMISSION OF A NOTICE OF TERMANDAY MAD AND MAD MAD MAD MAD THE ACTIVITIES AND SUBMISSION OF A NOTICE OF TERMANDAY MAD AND MAD MAD MAD THE ACTIVITIES AND SUBMISSION OF A NOTICE OF TERMANDAY MAD AND MAD MAD AND MAD THE ACTIVITIES AND THE ADDRESS OF THE ACCIDITIES AND THE ADDRESS OF THE ACCIDITIES AND THE ADDRESS OF THE ACCIDITIES AND THE ADDRESS OF THE STORMANDAY MAD AND ADDRESS OF THE STORMANDAY MAD ADDRESS OF THE STORMANDAY MAD ADDRESS OF THE STORMANDAY MAD ADDRESS OF THE STOR

MAP 138, LOTS 79 & 80 OWNER OF RECORD: COLBY FOOTWEAR, INC. 364 ROUTE 108 SOMERSWORTH, NH 03878 BK. 2017, PG. 792


OVERALL SITE PLAN OAK STREET / ROUTE 125

ROCHESTER, NH


PREPARED FOR


COLBY FOOTWEAR. INC.


JANUARY 2012 SCALE: 1"= 60' GRAPHIC SCALE





2 Continental Blvd., Rochester, N.H. 603-335-3948















31 Mooney Street, Alton, N.H. 603-875-3948


NORWAY PLAINS ASSOCIATES,

2 Continental Blvd., Rochester, N.H. 603-335-3948



TRENCH DETAIL FOR

WATER PIPE NOT TO SCALE



WATER MAIN CONNECTION

NOT TO SCALE -2-1/2" DIA. STEEL TARGET WELDED TO END OF 1/2" DIA. REBAR WRAP REBAR AROUND HYDRANT ARM TARGET & REBAR TO BE PAINTED 1 J" PENTAGON ---NATIONAL STANDARD OPERATING NUT EDGE OF PARKING LOT "WATER" EMBOSSED ON "- }" CLEAN SCREENED GRAVEL OR CRUSHED STONE PIT 3' DIA. & 2' DEEP TO 6" ABOVE S" IRON BODY RESILIEN WEDGE TYPE GATE VALVE MEETING OR EXCEEDING ADJUSTABLE-VALVE BOX DRAIN A.W.W.A. C509 2,500 LB. POURED VALVES SHALL OPEN CONC. THRUST BLOCK- 5S.F. AGINST UNDISTURBED EARTH CLOCKWISE (RIGHT) FELT PAPER BETWEEN PIPE

INED DUCTILE

AND CONCRETE

FILE NO. 288

F.B. NO. SDR

PLAN NO. PERLIM DWG NO. 12009\SP-2

TYPICAL HYDRANT SECTION

NOT TO SCALE

NOTES: HYDRANTS ARE TO BE KENNEDY GUARDIAN MODEL #K81A (OR EQUAL) WITH 6"
MECHANICAL JOINT SHOE WITH BREAK FLANGE TO BE PROVIDED WITH
DRAIN-OPENING CLOCKWISE (RIGHT).

THE RODS OPT. (IF USED THRUST BLOCK AT HYD.

-ANCHOR


SETTING BLOCK AGINST UNDISTURBED MATERIAL MIN. 2'-0" AT BOTTOM

(TYP. ALL BRIDLED

HYDRANTS TO BE OSHA RED

HYDRANTS SHALL HAVE ONE 5 INCH PUMPER OUTLET AND TWO 22-INCH HOSE


OUTLETS.
HYDRANT SHALL BE GATED WITH A 5 INCH BOTTOM VALVE.
HYDRANTS SHALL MEET OR EXCEED ALL REQUIREMENTS OF A.W.W.A. STANDARD



ELEVATION

TYPICAL AT NON BRIDLED VALVE


NOT TO SCALE



PLAN VIEW

TYPICAL VALVE CONNECTION

NOT TO SCALE




WATER MAIN THRUST BLOCK DETAILS

NOT TO SCALE

NOTE: SIZE OF THRUST BLOCKS MAY BE INCREASED BY THE ENGINEER TO MEET SOIL CONDITIONS FOUND DURING CONSTRUCTION.

CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION. SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WITH IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS ASSOCIATES, INC. (603)—335—3948.

CIVIL ENGINEERS



- NOTES:

 A.R. NON-METALUC CONDUIT AND FITTINGS SHALL BE FLECTRICAL GRADE, SCHEDULE 40 PVC, AND SHALL CONFORM TO THE
 ARE NON-METALUC CONDUIT NORMA TC2-1990 AND BE UL USTED. <u>ONLY CRIAY-COLORED CORPUET WILL BE ACCEPTED.</u> ANY PVC
 CORDUIT NOT HANNON THE PROPER INMA AND UL MARKINGS WILL NOT BE ACCEPTED. ALL SPEEL COMOUNTS SHALL BE SEALED
 TO ASTM AT 20 AND BE RIGID GALVANIZED STEEL. ALL PVC JOHTS MUST BE CREATED. STEEL FITTINGS SHALL BE SEALED
 WITH COMPOUND.
- WITH COMPICIND.
 MILE OF DEGREE SWEEPS WILL BE MADE USING RIGID GALVANIZED STEEL WITH A MEMBIUM RADIUS OF 36 INCHES FOR PRIMARY
 CABLES AND 24 INCHES FOR SECONDARY CABLES. ALL STEEL SWEEPS WITHIN 18" OF THE SURFACE SHALL BE PROPERLY

- 2 ML SO DECREE SWEEPS MILL BE MADE USING RIGID GALVANIZED SITES, WITH A MEMBRAIN RADIUS OF 30 MINUTES THE PROPERTY CARLES AND 24 MICHES FOR SECONDARY CABLES. ALL STEELS WEEPS WITHIN 16" OF THE SURFACE SHALL BE PROPERTY GROUNDED.

 A 10-FOOT HORIZONFAL SECTION OF RIGID CALVANIZED SITEL CONDUIT WILL BE RECURRED AT EACH SWEEP, UNLESS IN THE OPENING OF THE PRINCIPLE STEELS OF THE OPENING OF THE SWEEP. PLY SUBJECT TO FAILURE DURING CABLE PLULIABLE BY PSINL SEARCHLE MAY BE MADE MITTER SWEEP. PLY SUBJECT TO FAILURE DURING CABLE PLULIABLE BY PSINL SEARCHLE MAY BE MADE MITTER SWEEP. PLY SOME OF THE SCHOOL OF THE SHAPE OF THE SWEEP. THE SWEEP WAS AND FURBISH. ORGANIC MATERIAL SHALL NOT BE USED AS BEACHEL. BALL BE TROBUGUELY CORDS, CEBRIS, AND FURBISH. ORGANIC MATERIAL SHALL NOT BE USED AS BEACHEL. BALL BE TROBUGUELY CORDS, CEBRIS, AND FURBISH.

 5. A SUITABLE PULL STRING, CAPAGLE OF 200 POUNDS OF PULL, MUST BE INSTALLED IN THE CONDUIT BEFORE PSINL IN KOTIFED TO INSTALL CABLE. THE STRING GHOULD BE BLOWN INTO THE CONDUIT ATTO THE CABLE ASSEMBLED TO AVOID BROWING THE STRING TO THE CONDUIT AND INSPECTION PRINCIPLE SHAPE AND SUPPLY OF THE CONDUIT AND INSPECTION OF THE CONDUIT. THE CONDUIT INSTALLATIONS WAS BEEN AND SECONDARY VOLTAGE CONDUIT. THE CONDUIT INSTALLATIONS WAS SECONDARY AND SHALL BE PRINCIPLE FORMARY.

 ALL C

ELECTRICAL & UNDERGROUND UTILITY TRENCH INSTALLATION DETAIL

NOT TO SCALE

UTILITY NOTES:

- UTILLIT NUTLES:

 1.) CONTRACTOR SHALL NOTIFY DIG-SAFE (1-888 344-7233) 72 HOURS PRIOR TO THE START OF CONSTRUCTION.

 2.) ALL EXISTING UTILITY LOCATIONS ARE APPROXIMATE AS SHOWN. THE CONTRACTOR SHALL VERIFY THEIR LOCATIONS AND ELEVATIONS.

 3.) THESE PLAN SHOWS ONLY THOSE FEATURES THAT WERE VISUALLY APPARENT ON THE DATE OF THE SURVEY. THE ABSENCE OF SUBSURFACE STRUCTURES, UTILITIES, ETC. FROM THESE PLAN, BUT IN EXISTENCE IS NOT INTENDED OR IMPLIED.
 - WATERINE CONSTRUCTION:

 A) ALL PROPOSED WATER LINE MATERIAL USED SHALL MEET ROCHESTER WATER
 DEPARTMENT AND ROCHESTER ENGINEERING DEPARTMENT SPECIFICATIONS. WATER
 LINES SHALL BE A.W.W.A C 151, CLASS 52, CEMENT LINED, DUCTILE IRON PIPE.

TRANSPORTATION PLANNERS

- POLYWRAPPED.

 B.) PROPOSED WATER GATE VALVES SHALL BE MANUFACTURED BY KENNEDY OF AMERICAN FLOW CONTROL, RESILIENT SEAT TYPE.

 C.) ALL WATER LINES SHALL BE BURIED A MINIMUM OF 5.5'.

 D.) ALL WATER FITTINGS SHALL BE CLASS 350.

 E.) PROPOSED WATER GATE VALVE SHALL OPEN COUNTER CLOCKWISE (RIGHT).

 5.) WORK TO CONNECT INTO THE WATER REQUIRES A PERMIT FROM THE ROCHESTER PUBLIC WORKS DEPARTMENT. CONTRACTORS ARE TO BE PRE—QUALIFIED.

 6.) CONTRACTOR SHALL LOCATED EXISTING SERVICES AND COORDINATE WITH THE CITY OF ROCHESTER FOR CONNECTION TO THESE SERVICES.

 7.) ALL UTILITIES SHALL BE BURIED UNDERGROUND AS REQUIRED BY THE CITY OF ROCHESTER AND THE UTILITY COMPANIES.

 8.) WATER AND SEWER LINES SHALL BE INSTALLED A MINIMUM OF 10-FT APART
- ROCHESTER AND THE UTILITY COMPANIES.

 8.) WATER AND SEWER LINES SHALL BE INSTALLED A MINIMUM OF 10-FT APART HORIZONTALLY.

 9.) WHERE SEWER AND WATER LINES MUST CROSS, SEWER PIPE JOINTS SHALL BE LOCATED A MINIMUM 9-FT HORIZONTALLY FROM THE WATER LINE AND A VERTICAL SEPARATION OF 18-INCHES SHALL BE MAINTAINED.

 10.) SEWER PIPE JOINTS SHALL BE TESTED WITH ZERO LEAKAGE AT 25 POUNDS PER SQUARE INCH FOR GRAVITY SEWER AND AT 1-1/2 TIMES WORKING PRESSURE FOR ALL FORCE MAINS.

- WALL PACK LIGHTING SPECIFICATIONS:

 1. ALL STEWORK SHALL CONFORM TO CITY OF ROCHESTER STANDARDS AND LOCAL AUTHORITIES HAVING JURISDICTION.

 2. ALL MATERIAL WORMANSHIP SHALL CONFORM TO THE LATEST EDITIONS OF THE FOLLOWING STANDARDS, NEW HAMPSHIRE ELECTRIC CODE, FIRE PROTECTION ASSOCIATION, NATIONAL ELECTRICAL MANUFACTURER'S ASSOCIATION, NATIONAL ELECTRICAL MANUFACTURER'S ASSOCIATION.
- nufacturer's association. . Exterior conduits for lighting shall be 1 1/2" Diameter o schedule 40, all elbows shall be galvanized rigid steel . Conduits under roadways and parking areas shall havi
- ALL CONDUITS LINDER ROADWAYS AND PARKING AREAS SHALL HAVE MINIMUM COVER OF THEE (3) FEET.

 4. ALL UNDERGROUND CONDUITS WALL HAVE NYLON PULL ROPE TO FACILITATE PULLING IN CABLES.


 5. ALL NO. B WIRE AND LANGER SHALL BE TYPE THAN COPPER. NO. B WIRE AND SMALLER SHALL BE THEM COPPER.

 5. PROVIDE FUSING ON ALL LUMBARIES. FUSES TO BE LOCATED AT POLY. HANDOLGE. ALL LUMBARIES. STY VOLT.
- WALL PACK CATALOG INFORMATION

WST 175M (CLEAR LAMP)

BUILDING MOUNTED LUMINAIRE, 175 WATT, METAL HALDE, CLEAR LAMP, CUTOFF

16-FT (ABOVE FINISHED GROUND)



WALL PACK LIGHT DETAIL

NOT TO SCALE

UTILITY DETAILS OAK STREET / ROUTE 125

ROCHESTER. NH

PREPARED FOR

COLBY FOOTWEAR, INC.

SCALE: AS SHOWN

MARCH 2012

2 Continental Blvd., Rochester, N.H. 603-335-3948

31 Mooney Street, Alton, N.H. 603-875-3948


NORWAY PLAINS ASSOCIATES, INC.

____FLOW

WIRE SCREEN

CONCRETE BLOCK (HOLLOW)

STONE



SLOPE INSTALLATION

MAINTENANCE REQUIREMENTS:

. ALL BLANKET AND MATS SHOULD BE INSPECTED WEEKLY DURING THE CONSTRUCTION PERIOD, AND AFTER ANY RANFALL EVEN

- MAINTENANCE REQUIREMENTS

 1. ALL BALNIET AND MATS SHOULD BE INSPECTED WEERLY DURING THE CONSTRUCTION PERIOD, AND AFTER ANY RAINFALL EVENT EXCEEDING 1/2 INCH IN A 224-HOUR PERIOD.

 2. EXCEEDING 1/2 INCH IN A 224-HOUR PERIOD.

 3. EXCEEDING 1/2 INCH IN A 244-HOUR PERIOD.

 3. EXCEEDING 1/2 INCH IN A 244-HOUR PERIOD.

 3. EXCEEDING 1/2 INCH IN AND EXCEED.

 3. A PREPARE SOIL BEFORE INSTALLATION INSTRUCTIONS:

 4. A PREPARE SOIL BEFORE INSTALLATION BY EXCEED 10 NOT SEED PREPARED AREA. CELL—0-SEED MUST BE INSTALLED WITH PAPER NOTE. WHEN 193M CELL—0-SEED 10 NOT SEED PREPARED AREA. CELL—0-SEED MUST BE INSTALLED WITH PAPER NOTE. WHEN 193M CELL—0-SEED 10 NOT SEED PREPARED AREA. CELL—0-SEED MUST BE INSTALLED WITH PAPER NOTE. WHEN 193M CELL—0-SEED 10 NOT SEED PREPARED AREA. CELL—0-SEED MUST BE INSTALLED WITH PAPER NOTE. WHEN 193M CELL—0-SEED 10 NOT SEED PREPARED AREA. CELL—0-SEED MUST BE INSTALLED WITH PAPER NOTE. WHEN 193M CELL—0-SEED 10 NOT SEED PREPARED AREA. CELL—0-SEED MUST BE INSTALLED WITH PAPER NOTE. WHEN 193M CELL—0-SEED 10 NOT SEED PREPARED AREA. CELL—0-SEED MUST BE INSTALLED WITH PAPER NOTE. WHEN 193M CELL—0-SEED 10 NOT SEED PREPARED AREA. CELL—0-SEED MUST BE INSTALLED WITH A PAPER NOTE. AND CELL—0-SEED 10 NOT SEED PREPARED AREA. CELL—0-SEED MUST BE INSTALLED WITH A PAPER NOTE. AND CELL—10 NOTE. THE RECCH AND CELL—10 NOTE. AND CELL—10 N

 - STAPLE PATTERN. THE EDGES OF PARALLEL RECP's MUST BE STAPLED WITH APPROXIMATELY 2" 5" (5 CM 12.5 CM) OVERLAP
 - THE EDGES OF PAGALLEL RELP'S MOST BE STAPLED WITH APPROXIMATELT 2 5 (5 LM 12.5 CM) OFFENDING ON RECP'S TYPE DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMAZE 3" (7.5 CM) OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" (30 CM) APART ACROSS ENTIRE RECP'S WIDTH.
 NOTE: IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" (15 CM) MAY BE NECESSAR! TO PROPERLY SECURE THE RECP'S.
- PREPARATION PEPARATION IS ESSENTIAL TO ENSURE COMPLETE CONTACT OF THE PROTECTION MATTING WITH THE SOR., GRADE AND SHAPE AREA IF INSTALLATION. REMOVE ALL ROCKS, CLODE, TRUSH, VEGETATIVE OR OTHER OBSTRUCTIONS SO THAT THE INSTALLED BLANKETS WILL HAVE DIRECT CONTACT WITH THE SON. DICHES OF TOPSOIL ABOVE FINAL GRADE. PREPARE SEEDED BY LOOSENING 2-3 INCHES OF TOPSOIL ABOVE FINAL GRADE. INCORPORATE ABREDIATIONS, SUCH AS LIME AND FERTILIZER, INTO SOIL ACCORDING TO SOIL YEST AND THE SEEDING PLAN.

- EDING:
 SEED AREA BEFORE BLANKET INSTALLATION FOR ERGISION CONTROL AND REVEGETATION. SEEDING AFTER MAT INSTALLATION IS
 OFTEN SPECIFIED FOR TURF REINFORGEMENT APPLICATIONS, WHEN SECONG PRIOR TO BLANKET INSTALLATION, ALL CHECK SLOTS
 AND OTHER AREAS DISTURBED DURING INSTALLATION MUST BE RESECTED.
 WHEN SOIL FILLING IS SPECIFIED, SEED THE MATTING AND THE ENTIRE DISTURBED AREA AFTER INSTALLATION AND PRIOR TO
 FILLING THE MAT WITH SOIL.

TEMPORARY EROSION CONTROL BLANKET DETAIL


NOT TO SCALE

TEMPORARY VEGETATION SEEDING RECOMMENDATIONS

The same of the sa	40 40 40	<u> </u>	
SPECIES	PER ACRE BUSHELS (BU) OR POUNDS (LBS.)	PER 1,000-SF	REMARKS
MW.TER RYE	2.5 BU OR 112 LBS.	2.5 £8S.	BEST FOR FALL SEEDING. SEED FROM AUGUST 15 TO SEPTEMBER 15 FOR BEST COVER. SEED TO A DEPTH OF 1 INCH.
OATS	2.5 BU OR 80 LBS.	2.0 LBS.	BEST FOR SPRING SEEDING. SEED NO LATER THAN MAY 15 FOR SUMMER PROTECTION. SEED TO A DEPTH OF 1 INCH.
ANNUAL RYE GRASS	40 LBS.	1.0 LB.	GROWS QUICKLY, BUT IS OF SHORT DURATION, USE WHERE APPEARANCES ARE IMPORTANT, SEED EARLY SPRING AND/OR BETWEEN AUGUST 15 AND SEPTEMBER 15. COVER THE SEED WITH NO MORE THAN 0.25 INCH OF SOIL.
PERENNIAL RYE GRASS	30 LBS.	0,7 LBS.	BEST FOR FALL SEEDING. SEED FROM AUGUST 15 TO SEPTEMBER 15 FOR BEST COVER. SEED TO A DEPTH OF 1 INCH.
SOURCES:			

NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME 3, TABLE

MINNICK FI AND HIT MARSHALL (AUGUST 1992)



- ANTENANCE REQUIREMENTS:

 FENCES SHOULD BE INSPECTED AND MAINTAINED IMMEDIATELY AFTER EACH PARKELL AND AT LEAST DAILY DURRING PROLONGED RAINFALLS. SEGMENT DESCRIBED AND MAINTAINED IMMEDIATELY AFTER EACH PARKELLA AND AT LEAST DAILY DURRING PROLONGED RAINFALLS. SEGMENT DESCRIBED AND ACCIDENCE AND ADMINISTRATION OF THE FENCE, AND THE PROCESS OF THE ACCIDENCE AND THE PROCESS OF THE P

- CONSTRUCTION SPECIFICATIONS.

 CONSTRUCTION SPECIFICATIONS.

 FRINCES SHOULD BE USED IN AREAS WHERE EROSION WILL DOOUR ONLY IN THE FORM OF SHEET EROSION AND THERE IS NO CONCENTRATION OF WATER IN A CHANNEL OR DRAINAGE WAY ABOVE THE FEDNE. SCIUNKINT BARRIERS SHOULD BE INSTALLED PRIOR TO ANY SOIL DISTURBANCE OF THE CONTRIBUTING DRAINAGE AREA ABOVE THEM.

 THE MAXIMUM CONTRIBUTING DRAINAGE AREA ABOVE THEM.

 THE MAXIMUM CONTRIBUTING DRAINAGE AREA ABOVE THEM SHOULD BE LESS THAN 1A ACRE PER 100 LINEAR FEET OF FENCE;

 HE MAXIMUM CONTRIBUTING DRAINAGE AREA FENCE SHOULD BE 100 FEET;

 THE MAXIMUM SLOPE ABOVE THE FENCE SHOULD BE 100 FEET;

 FENCES SHOULD BE INSTALLED FOLLOWING THE CONTROL OF THE LAND AS CLOSELY AS POSSIBLE, AND

 A. THE MAXIMUM SLOPE ABOVE THE FENCE SHOULD BE FLARED UPSLOPE;

 B. THE FABRIC SHOULD BE EMBEDDED A MAINIMUM OF 4 NICHES IN DEPTH AND INCHES IN WOTH IN A TRENCH EXCAVATED INTO THE GROUND, OR IT STEE CONDITIONS INCLUDE FROZER GROUND, LEGGLE, OR THE PRESENCE OF HEAVY ROOTS, THE BASE OF THE FABRIC SHOULD BE EMBEDDED WITH A MINIMUM THICKNESS OF 8 INCHES OF 3/4-INCH STONE;

 C. THE SOIL SHOULD BE COMPACTED OVER THE CARBOD FORMS;

 D. SUPPORT POSTS SHOULD BE SZED AND ANDHORED ACCRONING TO THE MANUFACTURER'S INSTRUCTIONS WITH MAXIMUM POST SPACING OF 6 ALLERDORS OF THE FERSING FROM A CONTROLLED FROZER OF AND ANDHORED ACCRONING TO THE MANUFACTURER'S INSTRUCTIONS WITH MAXIMUM POST SPACING OF 6 ALLERDORS OF THE SECOND OF THE CARBOD OF A MAINING SECONDAY.

- IN SUPPLIAR PUSIS SHOULD BE SIZED AND ANCHORED ACCORDING TO THE MANUFACTURER'S INSTRUCTIONS WITH MAXIMUM POST SPACING OF 6 EXECUTIONS OF THE FENCE SHOULD BE OVERLAPED BY A MINIMUM OF 6 NORTHS (24 INCHES 19 PREFERED), FOLDED AND STAPLED TO A SUPPORT POST IF WETAL POSTS ARE USED, FRANCE OF HEARING SHOULD NOT BE STAPLED OR NAILD TO TREES.
 BUT FENCING SHOULD NOT BE STAPLED OR NAILD TO TREES.
 BUT FERSON SHOULD NOT BE STAPLED OR NAILD TO TREES.
 BUT FERSON SHOULD BE A PERMOND SHET OF PROPEREN, INVON, POLYESTER OR ETHYLENE YARN AND SHOULD BE CERTURED BY THE MANUFACTURER OR SUPPLIER.
 BUT FERSON SHOULD CONTAIN ULTRAVIOLET RAY INHIBITORS AND STABILIZERS TO PROVIDE A MINIMUM OF 6 MONTHS OF EXPECTED USABLE CONSTRUCTION LIFE AT A TEMPERATURE RANGE OF D DEGREES FARRENHETT TO 120 BEGREES FARRENHETT FOR STAPLED STAPLED STAPLED BY THE POSTS FOR SUIT FERSON STAPLED BY THE ALMOST AND STABILIZERS TO PROVIDE A MINIMUM OF 6 MONTHS OF EXPECTED USABLE CONSTRUCTION LIFE AT A TEMPERATURE RANGE OF D DEGREES FARRENHETT TO 120 BEGREES FARRENHETT.

 FIGURE STATE STAPLED STAPLED BY THE ALMOST DATE A "ALMOST DAMERE WOOD OR 1.3.3 POLVINGS FER INDRAF TOOT STEEL WITH A MINIMUM LENGTH OF 5 FEEL. STEEL, POSTS SHOULD BE THAT A "ALMOST DATE WOOD OR 1.3.3 POLVINGS FER INDRAF TOOT STEEL WITH A MINIMUM LENGTH OF 5 FEEL. STEEL, POSTS SHOULD BE TRAVELED BY THE FARREN.

 FIRE ARROS.

- FABRIC.

 10. THE HEIGHT OF A SILT FENCE SHOULD NOT EXCEED 36 INCHES AS HIGHER FENCES MAY IMPOUND VOLUMES OF WATER SUFFICIENT TO CAUSE FALURE OF THE STRUCTURE.

 11. THE FILTER FABRIC SHOULD BE PURCHASED IN A CONTINUOUS ROLL OUT TO THE LENGTH OF THE BARRIER TO AVOID THE USE OF JOINTS, WHEN JOINTS ARE NECESSARY, TRIVER COTH SHOULD BE SPLICED TOGETHER ONLY AT SUPPORT POST, WITH A MINIMUM 6-INCH OVERLAP, AND SECURELY SALED.
- SECURELY SEALED. A MANUFACTURED SILT FENCE SYSTEM WITH INTEGRAL POSTS MAY BE USED. POST SPACING SHOULD NOT EXCEED 8 FEET. A THENCH SHOULD BE EXCANATED APPROXIMATELY 4 INCHES WIDE AND 4 NOMES DEEP ALONG THE LINE OF POSTS AND UP GRADIENT FROM THE
- 14. A THENON SHOULD BE EXCAVATED APPROXIMATELY 4 INCHES WIDE AND 4 INCHES DEEP ALONG THE LINE OF POSTS AND UP GRADIENT FROM THE BARRIER.

 15. THE STANDARD STRENGTH OF FILTER FABRIC SHOULD BE STANDLED OR WREET TO THE POST, AND B INCISES SHOULD HOT EXTEND MORE THAN 36 INCHES ABOVE THE ORIGINAL GROUND SURFACE.

 16. THE TRENCH THE FABRIC SHOULD NOT EXTEND MORE THAN 36 INCHES ABOVE THE ORIGINAL GROUND SURFACE.


 17. THE TRENCH SHOULD STALLED BY "SILEND" USING MECHANICAL COUPMENT SPECIFICALLY DESIGNED FOR THIS PROCEDURE. THE SUIGN METHOD MISNALLY DISSURED THE SUL STENDE BEHIND A TRACTOR TO "PLOW" OR SILED ETH SET FERRE MATERIAL INTO SOIL THE SULCING METHOD MISNALLY DISSURDED THE SOIL UPWARD AND SLIGHTLY DISPLACES THE SOIL, MAINTAINING THE SOIL'S PROFILE AND CREATING AN OPTIMAL CONDITION FOR SUBSECURITY MECHANICAL COMPACTION.

 18. SILT FENCES SHOULD BE INSTALLED WITH "SMILES" OR "J—HOOKS" TO REDUCE THE BRAINAGE AREA THAT ANY SECMENT WILL IMPOUND.

 19. THE ENDS OF THE FERCE SHOULD BE INSTALLED WITH "SMILES" OR "J—HOOKS" TO REDUCE THE DRAINAGE AREA THAT ANY SECMENT WILL IMPOUND.

 20. SILT FENCES PLACED AT THE TOE OF A SLOPE SHOULD BE SET AT LEAST B FEET FROM THE TOE M ALLOW SPACE FOR SMALLOW PONDING AND TO ALLOW FOR MAINTENANCE ACCESS WITHOUT DISTURBNO THE SUSPIL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREAS HAVE BEEN PERMANENTLY STRABLED.

SILTATION CONTROL FENCE DETAIL NOT TO SCALE



FLOW ____

CONSTRUCTION SPECIFICATIONS

1. PLACE CONCRETE BLOCKS LENGTHWISE ON THEIR SIDE IN A SINGLE ROW AROUND THE PERIMETER OF THE INILET, WITH THE ENDS OF ADJACENT BLOCKS ABUTTING, THE HEIGHT OF THE BARRIER CAN BE VARIED, DEPENDING ON DESIGN NEEDS, BY STACKING COMBINATIONS OF 4-INICH, B-INICH AND 12-INICH WIDE BLOCKS. THE BARRIER OF BLOCKS SHALL BE AT LEAST 12 INICHES HIGH AND NO GREATER THAN 24 INICHES HIGH.

2. WIRE MESH SHALL BE PLACED OVER THE OUTSIDE VERTICAL FACE (WEBBING) OF THE CONCRETE BLOCKS TO PREVENT STONE FROM BEING WASHED THROUGH THE HOLES IN THE BLOCKS. HARDWARE CLOTH OR

SECTION

CATCH BASIN

<u>PLAN</u>

-WIRE SCREEN

- WASHED THROUGH THE HOLES IN THE BLOCKS. HARDWARE CLOTH OR COMPARABLE WIRE MESH WITH 1/2-INCH OPENINGS SHALL BE USED. STONE SHALL BE PILED AGAINST THE WIRE TO THE TOP OF THE BLOCK BARRIER, AS SHOWN IN FIGURE 16.7. STONE GRADATION SHALL BE WELL GRADED WITH THE MAXIMUM STONE SIZE OF 6 INCHES AND MINIMUM STONE SIZE OF 1 INCH.

 IF THE STONE FILTER BECOMES CLOGED WITH SEDIMENT SO THAT IT NO LONGER ADEQUATELY PEFFORMS ITS FUNCTION, THE STONE MUST BE PULLED AWAY FROM THE BLOCKS, CLEANED AND REPLACED.
- MAINTENANCE 1. THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN AND REPAIRS
- MADE AS NEEDED.
 SEDIMENT SHALL BE REMOVED AND THE TRAP RESTORED TO ITS ORIGINAL. SEMMENT SHAEL BE REMOVED AND THE WAR RESTORED TO THE ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF THE TRAP. REMOVED SEDIMENT SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT EROBE. STRUCTURES SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE REMAINING DRAINAGE AREA HAS BEEN PROPERTY STABILIZED.

BLOCK AND GRAVEL DROP INLET SEDIMENT FILTER

NOT TO SCALE



TEMPORARY VEGETATION:

- SPECIFICATIONS
 SITE PREVAINTIONS
 SITE PREVAINTIONS
 THE PREVAINT THE PROSENT AND SEDIMENT CONTROL MEASURES SUCH AS SILTATION BARRIERS, DIVERSIONS, AND SEDIMENT TRAPS.
 2. GRADE AS NEEDED FOR THE ACCESS OF EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH APPLICATION, AND MULCH ANCHORING.
 3. RUNDER SHOULD BE DIVERTED FROM THE SEEDBED AREA.
 4. ON SLOPES 4-1 OR SIEPPER, THE FINAL PREPARATION SHOULD INCLUDE CREATING HORIZONTAL GROOVES PREPARATION OF THE SLOPE TO CATCH SEED AND REDUCE RUNGEF. PERPENDICULAR O THE DIRECTION OF THE SLOPE TO CATCH SEED AND REDUCE RUNOFF.

 ESCIDED, PERPARATION:

 1. STONES AND TRASH SHOULD BE REMOVED SO AS NOT TO INTERFERE WITH THE SEEDING AREA.

 2. WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOGSEN SOIL TO A DEPTH OF 2 INCHES BEFORE APPLYING FERTILIZER, LIME AND SEED.

 1. FAPPLICABLE, FERTILIZER AND ORGANIC SOIL AMENDMENTS SHOULD BE APPLIED DURING THE GROWING
- IF APPLICABLE, FERNIZER AND FERTILIZER ACCORDING TO SOIL TEST RECOMMENDATIONS. IF SOIL TESTING IS NOT APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TEST RECOMMENDATIONS. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES, OR WHERE TIMING IS CRITICAL FERTILIZER AND LIMESTONE MAY BE APPLIED AT THE FOLLOWING RATES:

NAMESTONE APPLICATION RATE = 3 TONS/ACRE (\$38 LB./1,000-SF)*
*EQUIVALENT TO 50% CALCIUM PLUS MAGNESIUM OXIDE

FERTILIZER APPLICATION RATE = 600 LB./ACRE (13.8 LB./1,000-SF)*
*LOW PHOSPHATE FERTILIZER (N~P205~K20) OR EQUIVALENT

FERTILIZER SHOULD BE RESTRICTED TO LOW PHOSPHATE, SLOW RELEASE NITROGEN FERTILIZER WHEN APPUED TO AREAS BETWEEN 25 AND 250-FT FROM A SURFACE WATER BODY, NO FERTILIZER EXCEPT LIMESTONE SHOULD BE APPLIED WITHIN 25-FT OF A SURFACE WATER BODY. THESE ARE THE REQUIREMENTS FOR ANY WATER BODY PROTECTED BY THE COMPREHENSIVE SHORELAND PROTECTION ACT.

WATER BODY PROTECTED BY THE COMPREHENSIVE SHORELAND PROTECTION ACT.

SEDING.

1. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL CULTDPACKER TYPE SEEDER OR HYDRO SEEDER
(SLURRY INCLUDING SEED AND FERTILIZER). NORMAL SEEDING DEPTH IS FROM 1/4 TO 1/2 INCH.
HYDROSEEDING THAT INCLUDES MALCH MAY BE LEFT ON SOIL SURFACE. SEEDING RATES MUST BE
NORGASED BY 1078 WHEN HYDROSEEDING TO SEPTEMBER 15.

2. TEMPORARY SEED SHOULD TYPICALLY OCCUP PRIOR TO SEPTEMBER 15.

3. AREAS SEEDED BETWEEN MAY 15 AND AUDIST 15 SHOULD BE COVERED WITH HAY OR STRAW MILCH,
ACCURDING TO THE "TEMPORARY AND PERMANENT MUCHING" PRACTICE DESCRIBED IN THE MISSIAL VOL 3.


YEED TATED BROWTH COVERNING AT LEAST BOS OF THE DISTURBED AREA SHOULD BE ACHEVED PRIOR TO
OCTOBER 15. IT THIS CONDITION IS NOT ACHEVED, APPLEMENT OTHER TEMPORARY STABILIZATION MEASURES
FOR OVER WINTER PROTECTION.

- MAINTENANCE REQUIREMENTS:

 1. TEMPORARY SEEDING SHOULD BE INSPECTED WEEKLY AFTER ANY RAINFALL EXCEEDING 1/2 INCH IN 24 HOURS DN ACTIVE CONSTRUCTION SITES. TEMPORARY SEEDING SHOULD BE INSPECTED JUST PRIOR TO SEPTEMBER 15, TO ASCERTAIN WHICH THE ADDITIONAL SEEDING IS REQUIRED TO PROVIDE STABILIZATION OVER THE WINTER PERIOD.

 2. BASED ON INSPECTION, AREAS SHOULD BE RESEEDED TO ACHIEVE FILL STABILIZATION OF EXPOSED SOILS. IF IT IS TOO LATE IN THE PLANTING SEASON TO APPLY ADDITIONAL SEED, THEN OTHER TEMPORARY STABILIZATION MEASURES SHOULD BE INPLEMENTED.

 3. FAMY EVED DO LATE IN THE PLANTING SEASON TO APPLY ADDITIONAL SEED, THEN OTHER TEMPORARY SHOULD BE MOVED. THE TEMPORARY MEASURES SHOULD BE MADE AND AREAS SHOULD BE RESEEDED, WITH OTHER TEMPORARY MEASURES (I.E. MULCH, ETC.) USED TO PROVIDE EROSION PROTECTION DURING THE PERIOD OF VECTATION ESTABLISHMENT.



PLAN

MAINTENANCE REQUIREMENTS:

1. WHEN THE CONTROL PAD BECOMES INEFFECTIVE. THE STONE SHOULD BE REMOVED ALONG WITH THE COLLECTED SOIL MATERIAL, REGRADED ON SITE, AND STABILIZED. THE ENTRANCE SHOULD THE BE RECONSTRUCTED.

2. THE CONTRACTOR SHOULD SWEET THE PAWEMENT AT EXITS WHENEVER SOIL MATERIALS ARE TRACKED ONTO THE ADJACENT PAWEMENT OR TRAVELED WAY.

3. WHEN WHELE WASHING IS REQUIRED, IT SHOULD BE CONDUCTED ON AN AREA STABILIZED WITH AGGREGATE, WHICH DRAINS INTO AN APPROVED SEDIMENT-TRAPPING DEVICE. ALL SEDIMENT SHOULD BE PREVENTED FROM ENTERING STORM DRAINS, DITCHES, OR WATERWAYS.

CONSTRUCTION SPECIFICATIONS:

1. THE MINIMUM STONE USED SHOULD BE 3-INCH CRUSHED STONE.

2. THE MINIMUM LENGTH OF THE PAO SHOULD BE 75 FEET, EXCEPT THAT THE MINIMUM LENGTH MAY BE REDUCED TO 50 FEET IF A 3-INCH TO 8-INCH BERM IS INSTALLED AT THE ENTRANCE OF THE PROLECT STIE.

3. THE PAO SHOULD BE THE FULL WIGHTH OF CONSTRUCTION ACCESS ROAD OR 10 FEET, WHICHEVER IS GREATER.

WHICHEVER IS GREATER.

THE PAD SHOULD SLOPE WANY FROM THE EXISTING ROADWAY.

HE PAD SHOULD SLOPE WANY FROM THE EXISTING ROADWAY.

HE GEORETHICK.

HE GEORETHIC FLUTER FABRIC SHOULD BE PLACED BETWEEN THE STONE PAD AND

THE EARTH SURFACE BELOW THE PAD.

HE PAD SHOULD BE MANIAMED OR REPLACED WHEN MUD AND SOIL PARTICLES

CLOO THE VOIDS IN THE STONE SUCH THAT MUD AND SOIL PARTICLES

CLOO THE VOIDS IN THE STONE SUCH THAT MUD AND SOIL PARTICLES

COFF-SHE.

MILE OF THE CROSSES THE LOCATION OF THE STONE PAD SHOULD BE STERREPTED AND PIPED BENEATH THE PAD, AS NECESSARY, WITH SUTTABLE OUTLET BENEATH.

TEMPORARY CONSTRUCTION ENTRANCE NOT TO SCALE

TEMPORARY EROSION AND SEDIMENTATION CONTROL DETAILS

OAK STREET / ROUTE 125 ROCHESTER, NH

PREPARED FOR

COLBY FOOTWEAR, INC.

SCALE: AS SHOWN

MARCH 2012

C-8

FILE NO. 288 PLAN NO. PERLIM DWG NO. 12009\SP-2 P.B. NO. SDR

ASSOCIATES, INC. (603)-335-3948.

CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION.

ICAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION. SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WITH IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS

NORWAY PLAINS ASSOCIATES, INC.

2 Continental Blvd., Rochester, N.H. 603-335-3948

SITE PREPARATION:

1. INSTALL NEEDED EROSION AND SEDIMENT CONTROL MEASURES SUCH AS SILTATION BARRIERS, DIVERSIONS, AND SEDIMENT TRAPS.

2. GRADE AS NEEDED FOR THE ACCESS OF EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH APPLICATION, AUTO MILLON AND MILLON APPLICATION, AUTO MILLON AND MILLON APPLICATION, AUTO MILLON AND MILLON APPLICATION, AND MILLON APPLICATION SHOULD BE DIVERTED FROM THE SEEDBED AREA.

3. RUNOFF SHOULD BE DIVERTED FROM THE SEEDBED AREA.

4. ON SLOTES 4.1 ON STEPPER, THE RIVAL PREPARATION SHOULD INCLUDE CREATING HORZON TAIL GROOVES PERPENDICULAR O THE DIRECTION OF THE SLOPE TO GATCH SEED AND REDUICE RUNOFF.

SEDGED REPERANTION:

1. WORK LINE AND FERRILIZER INTO THE SOIL AS NEARLY AS PRACTICAL TO A DEPTH OF 4 MCHES WITH A DISC. SPRING TOOTH HARROW OR OTHER SISTABLE EQUIPMENT. THE FINAL HARROWNO OPERATION SHOULD BE ON THE GENERAL CONTOUR. CONTINUE TILLAGE UNTIL A REASONABLY UNIFORM, FIRS. SEEDBED IS PREPARED. ALL BUT DLAY AND SLIT SOILS SHOULD BE ROLLED TO FIRM THE SEEDBED WHEREVER FEASIBLE.

2. REMOVE FROM THE SUPPLACE ALL STORES ZINCHES OR LARGER IN ANY DIMENSION. REMOVE ALL OTHER DEBNIS, SUCH AS WINE, CABLE, TREE ROOTS, CONCRETE CLODS, LUMPS, TRASH OR OTHER DISSUITABLE MATERIAL.

3. INSPECT SEEDBED JUST BEFORE SEEDING, IF TRAFFIC HAS LEFT THE SOIL COMPACTED; THE AREA MUST BE TILLED AND FIRMED AS ABOVE.

4. WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LODSEN SOIL TO A DEPTH OF 2 INCHES BEFORE APPLIANG FERNILERS, LIME AND SEED.

5. IF APPLICABLE, FERTILIZER AND ORGANIC SOIL AMENDMENTS SHOULD BE APPLIED DURING THE GROWNS EXASON.

GROWING SEASON.

APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TEST RECOMMENDATIONS. IF SOIL

TESTING IS NOT FEASIBLE ON SMALL OR VARABLE SITES, OR WHERE TIMING IS CRITICAL

FERTILIZER AND LIMESTONE MAY BE APPLIED AT THE FOLLOWING RATES:

LIMESTONE APPLICATION RATE = 3 TONS/ACRE (138 LB./1,000-SF)*
*EQUIYALENT TO 50% CALCRIM PLUS MAGNESIUM OXIDE

FERRILIZER SHOULD BE RESTRICTED TO LOW PHOSPHATE, SLOW RELEASE NITROGEN FERTILIZER
WHEN APPLIED TO AREAS BETWEEN 25 AND 250-FT FROM A SURFACE WATER BOOY. NO
FERRILIZER EXCEPT LIMESTONE SHOULD BE APPLIED WHITH 25-FT OF A SURFACE WATER
BOOY. THESE ARE THE REQUIREMENTS FOR ANY WATER BOOY PROTECTED BY THE
COMPREHENSIVE SHORELAND PROTECTION ACT.

COMPREHENSIVE SHORELAND PROTECTION ACT.

SEEDING:

1. INCLUATE ALL LEGIME SEED WITH THE COPRECT TYPE OF INOCULANT.

1. INCLUATE ALL LEGIME SEED WITH THE COPRECT TYPE OF INOCULANT.

2. APPLY SEED LINFORMLY BY HAND, CYCLOME SLEDER DRILL CULTIPACKER TYPE SEEDER OR HYDROSESEDER THAT INCLUDES MUCH MAY SEED LINFORD. SUFFACE.

3. WHERE FEASIBLE EXCEPT WHERE EITHER CULTIPACKER TYPE. SEEDER OR HYDROSESEDER IS.

USED, THE SEEDBED SHOULD BE FRINGED FOLLOWING SEEDING D'ERATIONS WITH A ROLLER, OR LIGHT DRAG.

4. SPRING SEEDING USUALLY GIVES THE BEST RESULTS FOR ALL SEED MIXES OR WITH LEGUMES. PERMANENT SEEDING SHOULD BE COMPLETED 45 DAYS PRIOR TO FIRST KULTING FROST. WHEN CROWN YETCH IS SEEDED IN LATE SIMMER AT LEAST 35% OF THE SEED SHOULD BE HARD SEED (UNISCARIBED). IF SEEDING CANNOT BE DONE WITHIN THE SPECIFIED SEEDING DATES, MULCH ACCORDING TO THE "TEMPORARY AND PERMANENT MUCH MICH PRACTICE DESCRIBED WITH NEXT RECOMMENDED SEEDING PERIOD.

3. AREAS SEEDED BETWEEN MAY 15 AND AUGUST 15 SHOULD BE COVERED WITH ANY OR STRAM MULCH, ACCORDING TO THE "TEMPORARY AND PERMANENT MULCHING" PRACTICE DESCRIBED IN THE HYBOX, VOL. 3. AND GELAY SEEDING UNTIL THE NEXT RECOMMENDED SEEDING PERIOD.

3. AREAS SEEDED BETWEEN MAY 15 AND AUGUST 15 SHOULD BE COVERED WITH ANY OR STRAM MULCH, ACCORDING TO THE "TEMPORARY AND PERMANENT MULCHING" PRACTICE DESCRIBED IN THE HYBOX, VOL. 3. IN THE HYBOX TO COTORER IS. IF THIS CONDITION IS NOT ACHIEVED, INPLEMENT OTHER TEMPOR

HYDROSSEDING:

1. WHEN PHOPOSEEDING (HYDRAULIC APPLICATION), PREPARE THE SEEDBED AS SPECIFIED ABOVE OR BY HAND RANING TO LOOSEN AND SMOOTH THE SOIL AND REMOVE SURFACE STONES LARGER THAN 2: INCHES IN DIAMETER.

2. SLOPES BUST BE NO STEEPER THAN 2: (2 FEET HORIZONTALLY BY 1 FOOT VERTICALLY.

3. LIME AND FETRILIZER MAY BE APPLIED SMALTANEOUSLY WITH THE SEED, THE USE OF FIBER MUCH ON ORTICAL AREAS IS NOT RECOMMENDED (UNLESS IT IS USED TO HOLD STRAW OR HAY). BETTER PROTECTION IS GARNED BY USING STRAW MILCH AND MICHORALS OR TOE POUNDS FER ACRE OF WOOD FIBER MULCH.

4. SEEDING MATERIALS OR TOE FOUNDS FER ACRE OF WOOD FIBER MULCH.

MARIEMANCE REQUIREMENTS

1. PERMANENT SECRED AREAS SHOULD BE INSPECTED AT LEAST MONTHLY DURING THE COURSE

1. PERMANENT SECRED AREAS SHOULD CONTINUE

AND COMMECTIVE_ACTIONS SHOULD CONTINUE

PLEMBARENT SECOED AREAS SHOULD BE INSPECTED AT LEAST MONTHLY DURING THE COUR OF CONSTRUCTION. INSPECTION, MAINTENANCE AND CORPECTIVE ACTIONS SHOULD CONTIN-UNTLITTED UNITER ASSUMES PERMANENT OPERATION OF THE STE-SEEDED AREAS SHOULD BE MOWED AS RECURRED TO MAINTAIN A HEALTHY STAMD OF VECETATION. MOMING HEIGHT AND FREQUENCY DEPEND OF TYPE OF GRASS COVER. BASED ON INSPECTION, AREAS SHOULD BE RESEDED TO ACHIEVE FULL STABILIZATION OF EXPOSED DOILS.

EXPOSED SOLS. AT A MINIMUM 55% OF THE SOIL SURFACE SHOULD BE COVERED BY VEGETATION IF ANY EVIDENCE OF EROSICN OR SEDIMENTATION IS APPARENT, REPAIRS SHOULD BE MADE AREAS SHOULD BE RESEEDED, WITH OTHER TEMPORARY MEASURES (I.E. MULCH, ETC.) UNSD TO PROVIDE EROSION PROTECTION DURING THE PERIOD OF VEGETATION ESTABLISHMENT.

PIPE OUTLET PROTECTION DETAIL PERMANENT VEGETATION SEEDING RECOMMENDATIONS

STEEP CUTS AND FLES, BORROW A CREEPING RED FESCUE 20 0.45	USE	MIXTURE	SPECIES	LBS./ACRE	LBS./ 1,000-SF
EMERGENCY CREEPING RED FESCUE 20 0.45	FILLS, BORROW AND DISPOSAL	A	CREEPING RED FESCUE REDTOP	20	0.45 0.05
PARKING LOTS. CREEPING RED FESCUE 20	EMERGENCY SPILLWAYS, AND OTHER CHANNELS WITH	A	CREEPING RED FESCUE REDTOP	20 2	0.45 0.05
AND ATHLETIC KENTUCKY BLUEGRASS 50 1.15 FIELDS (TOPSOIL ESSENTIAL FOR 100 2.30	PARKING LOTS, ODD AREAS, UNUSED LANDS, AND LOW INTENSITY RECREATION	A	CREEPING RED FESCUE REDTOP	20 20 2 42	0.45 0.05
	AND ATHLETIC FIELDS (TOPSOIL ESSENTIAL FOR	F	KENTUCKY BLUEGRASS	50	1,15

SOURCES:

1. NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME 3, TABLES 4-2 AND 4-3

2. MINNICK, E.L. AND H.T. MARSHALL, (AUGUST 1992)

STOCKPILE PRACTICES:

LOCATE STDCKPLES A MINIMUM OF 50-FT. AWAY FROM CONCENTRATED FLOWS OF STORMWAITER, DRAINAGE COURSES OR INLETS.
PROTECT ALL STOCKPLES FROM STORMWAITER RUN-ON USING TEMPORARY PERMETER MEASURES SUCH AS DIVERSIONS, BERMS, SANOBAGS OR OTHER APPROVED PRACTICES.

APPROVED PRACTICES.

3. STOCKPLES SHOULD BE SURROUNDED BY SEDIMENT BARRIERS AS DESCRIBED ON THE PLANS AND IN INFISMM VOL. 3. TO PREVENT MIGRATION OF MATERIAL BEYOND THE IMMEDIATE CONFINES OF THI

STOCKPRE.

MID EROSION CONTROL PRACTICES AS APPROPRIATE ON ALL STOCKPRED MATERIAL.

PLACE BAGSED MATERIALS ON PALLETS OR UNDERCOVER.

PROTECTION OF INACTIVE STOCKPILES:
6. INACTIVE SOIL STOCKPILES SHOULD BE COVERED WITH ANCHORED TARPS OR PROTECTED WITH SOIL STRUBLING BE COVERED WITH ANOTHER UNIT AND OR PROTECTED WITH SOIL STRUBLING AND REASURES (TEMPORARY SEED AND MULCH OR OTHER TEMPORARY STRUBLIZATION PRACTICE) AND TEMPORARY PERINETER SEDIMENT BARRIERS (LE. SIR FENCE, ETC.) ATALL TIMES, INACTIVE STOCKPILES OF CONCRETE RUBBLE, ASPHALT CONCRETE RUBBLE, ASPHALT CONCRETE RUBBLE, ASPRALT CONCRETE RUBBLE

AGGREGATE MATERIALS, AND SMILLAR MATERIALS SHOULD BE PROTECTED WITH TEMPORARY SEDIMENT PERIMETER BARRIERS (I.E. SILT FENCE, ETC.) AT ALL TIMES. IF THE MATERIALS ARE A SOURCE OF DUST, THEY SHOULD ALSO BE COVERED.

PROJECTION OF ACTIVE STOCKPIES.

8. ALL STOCKPIES SHOULD BE SURROUNDED WITH TEMPORARY LINEAR SEDMENT BARRIERS (IS. SLI FENCE, ETC.) PRIOR TO THE ONSET OF PRECIPITATION. PERMETER BARRIERS SHOULD BE MAINTAINED AT ALL TIMES, AND ADJUSTED AS NEEDED TO ACCOMMODATE HE DELIVERY AND REMOVAL OF MATERIAL FROM THE STOCKPIES. THE INTEGRITY OF THE BARRIER SHOULD BE INSPECTED AT THE END OF EACH WORKING DAY.

9. WHEN A STORM BE PREDICTION STOCKPIES SHOULD BE PROTECTED WITH AN ANCHORD PROTECTIVE COVERNIG.

GENERAL CONSTRUCTION PHASING:

STABLIZATION

A STE S DEFARED STABLIZED WHEN IT IS IN A CONDITION IN WHICH THE SOIL ON SITE MILL

A STE STEARED STABLIZED WHEN IT IS IN A CONDITION IN WHICH THE CONDITIONS OF A

CONTROL STABLE STABLIZED OF UNIVERSE TO THE CONDITIONS OF A

(A) ILLAREAS THAT MILL NOT BE PAYED:

(3) A MINAMAN OF BES X-ECETATIVE COVER HAS BEEN ESTABLISHED:

(4) A MINAMAN OF BES X-ECETATIVE COVER HAS BEEN ESTABLISHED:

(5) A MINAMAN OF BES X-ECETATIVE COVER HAS BEEN ESTABLISHED:

(6) A MINAMAN OF BES X-ECETATIVE COVER HAS BEEN ESTABLISHED:

(7) A MINAMAN OF BES X-ECETATIVE COVER HAS BEEN ESTABLISHED:

(8) BERGSION CONTROL BLANKETS HAVE BEEN INSTALLED.

(9) IN A BERS TO BE PAYED:

B) IN AREAS TO BE PAYED:

1) BASE COURSE GRAVELS HAVE BEEN INSTALLED.

D) BASE COURSE GRAVELD HAVE DEEP INSURANCE.

INDEPENDENT STABILIZATION.

ALL AFEAS OF EXPOSED OR DISTURBED SOIL SHOULD BE TEMPORARILY STABILIZED AS SOON

AS PRACTICABLE BUT NO LATER THAM AS DAYS FROM THE TIME OF INITIAL DISTURBANCE.

UNLESS A SHORTER TIME IS SPECIFIED BY LOCAL AUTHORITIES. THE CONSTRUCTION
SEQUENCE APPROVED AS PART OF THE ISSUED PERMIT OR AN INDEPENDENT MONITOR.

AND THE CONSTRUCTION.

AN

SEQUENCE APPROVED AS PART OF THE ISSUED PERMIT OR AN INDEPENDENT MONITOR.

2ERMARINT. STABILIZATION:
ALL AREAS OF EXPOSED ON DISTURBED SOIL SHOULD BE PERMANENTLY STABILIZED AS SOON
AS PRACTICABLE BUT NO LATER THAN 3 DAYS FOLOMBIC FINAL SKADING.

4. MAXIMUM AREA OF DISTURBANCE:
THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT IN NO
CASE EXCEED 5 ACRES AT ANY ONE TIME BEFORE DISTURBED AREA ARE STABILIZED.

5. ONLY DISTURB, CLEAR, OR GRADE AREAS NECESSARY FOR CONSTRUCTION.

ONLY DISTURB, CLEAR, OR GRADE AREAS NECESSARY FOR CONSTRUCTION.
 A) FLAG OR OTHERWISE BELLIHAET, RAREA NOT TO BE DISTURBED.
 B) EXCLUDE VEHICLES AND CONSTRUCTION EQUIPMENT FROM THESE AREAS TO PRESERVE NATURAL VEGETATION.
 ALL GRADED OR DISTURBED AREAS INCLUDING SLOPES SHOULD BE PROTECTED DURING CLEARING AND CONSTRUCTION IN ACCORDANCE WITH THE APPROVED EROSION AND SCIDMENT CONTROL DEPICTED ON SHEET C.3.
 ALL EROSION AND SCIDMENT CONTROL PRACTICES AND MEASURES SHOULD BE CONSTRUCTED, APPLED AND MAINTAINED IN ACCORDANCE WITH THE APPROVED EROSION AND SEDIMENT CONTROL DEPICTED ON SHEET C.3.
 TOPSOIL, REQUIRED FOR THE STABLISHMENT OF VEGETATION SHOULD BE STOCKFULED IN THE AMOUNT INCESSARY TO COMPLETE FRISHED GRADING AND BE PROTECTED FROM EROSION.

STOCKPILES, BORROW AREAS AND SPOILS SHALL BE STABILIZED AS DESCRIBED UNDER SOIL

9. STOCKPILES, BORROW AREAS AND SPOILS SHALL BE STABILIZED AS DESCRIBED UNDER SOIL

STOCKPILE PRACTICES*

10. SLOPES SHOULD NOT BE OFFAITED SO CLOSE TO PROPERTY LINES AS TO ENDANGER
ADJAINING PROPERIES WITHOUT ADCOUNTE PROFECTION AGAINST SEDIMENTATION, EROSION,
SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER RELATED DAMAGE.

13. AREAS TO BE FILLED SHOULD BE CLEARED, BRUBBED AND STRIPPED OF TOPSOIL TO REMOVE
TREES, VEGSTATION, ROOTS AND/OR OTHER OBJECTIONABLE MATERIALS.

12. AREAS SHOULD BE SCARPIED TO A MINIMUM DEPTH OF 3-M-NORES PRIOR TO PLACEMENT OF
TOPSOIL. TOPSOIL SHOULD BE PLACED WITHOUT SIGNIFICANT COMPACTION TO PROVIDE A
LOSS BECODING FOR PLACEMENT OF SECORDANCE WITH PROJECT SPECIFICATIONS TO

13. ALL FILLS SHOULD BE COMPACTED IN ACCORDANCE WITH PROJECT SPECIFICATIONS TO
RESTORMED SUPPORT PUBLISHES SHOULD BE COMPACTED WITHOUT SIGNIFICANT FOR PROPERTY OF THE
PROJECT OF SUPPORT PUBLISHES SHOULD BE COMPACTED WITHOUT SIGNIFICANT LODGE SHOULD SHE OF THE BLOOKES SHOULD BE COMPACTED IN ACCORDANCE WITH LOCAL REQUIREMENTS OR CODES,
IN IS CENTERAL, FILLS SHOULD BE COMPACTED IN LARGE SHAULD FROM S TO 24 ROOMES

IN CONTROL OF THE SHOULD BE COMPACTED WITH PROJECT SECTEMENTS OR CODES,
IN IS CONTROL OF SHOULD BE COMPACTED WITH ACCORDANCE WITH LOCAL REQUIREMENTS OR CODES,
IN IS CONTROL FILL SHOULD BE COMPACTED WITH ACCORDANCE WITH LOCAL REQUIREMENTS OR CODES,
IN IS CONTROL FILL SHOULD BE COMPACTED WITH ACCORDANCE METHOD AND A ROOMES AND SHOULD BE SECOND FOR THE PROJECT GEOTECHNICAL REPORT

AND/OR THE "PROJECT ESPECIE CHARMENTS NOTES." FOR SPECIES COURANCE.

20. SEEPS OR SPRINGS ENCOUNTERED DURING CONSTRUCTION SHOULD BE EVALUATED BY A
<u>PROCESSIONAL ENGINEER</u> (PREFERABLY THE DESIGN ENGINEER) TO SETERMINE IF THE
PROPOSED DESIGN SHOULD BE REVISED TO PROPERLY MANAGE THE CONDITION.

21. STABILIZE ALL GRADED AREAS (AS ABOVE) WITH VEGETATION, CRUSHED STONE, COMPOST
BLANKET, OR OTHER ROUND COVER AS SOON AS GRADING IS COMPLETE OR IF WORK IS
INTERRUPTED FOR 21 WORKING DAYS OR MORE. USE MOLECH OR OTHER APPROVED METHODS
TO STABILIZE AREAS EMPORABLY WHERE FINAL GRADING MUST BE DELLAYED.

22. ALL GRADED AREAS SHOULD BE PERMANENTLY STABILIZED IMMEDIATELY FOLLOWING FINISHED
GRADING.

ABOVE NOTES EXCERPTED, ADAPTED AND REFERENCED FROM "NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME 3 CONSTRUCTION PHASE EROSION AND SEDMENT CONTROLS, DECEMBER 2008" (NHSMM, VOL. 3)

WINTER STABILIZATION & CONSTRUCTION PRACTICES:

CIVIL ENGINEERS -

MAINTENANCE REQUIREMENTS:

1. MAINTENANCE MEASURES SHOULD BE PERFORMED THROUGHOUT CONSTRUCTION, INCLUDING OVER THE WINTER PERSO. AFTER EACH RAINFALL, SNOWSTORM, OR PERIOD OF THAMMO AND RUMOFF, THE SITE CONTRACTOR SHOULD CONDUCT INSPECTION OF ALL INSTALLED EROSION CONTROL PRACTICES AND PERFORM REPAIRS AS NEEDED TO INSURE THEIR CONTROLED FUNCTION.

2. FOR ANY AREA STABILIZED BY TEMPORARY OR PERMAMENT SEEDING PINOR PINOR CONDUCT OR INSPECTION IN THE SPENIOT OF AGETTAIN THE CONDITION OF THE VECETATION AND REPAIR ANY DAMAGED AREAS OR BARE SPOTS AND REPERE AS PETABLISHED VECETATION AND REPAIR ANY DAMAGED AREAS OR BARE SPOTS AND RESERVED AS OPENION AND REPAIR ANY DAMAGED AREAS OR BARE SPOTS AND RESERVED AS OPENIONED TO ACCEPTED VECETATION COVER (AT

RESEED AS REQUIRED TO ACHIEVE AN ESTABLISHED VEGETATIVE COVER (AT LEAST 85% OF AREA VEGETATED WITH HEALTHY, VIGOROUS CROWTH.)

SECUTIONS:
THE FOLLOWING STABILIZATION TECHNIQUES SHOULD BE EMPLOYED DURING THE PERIOD FROM OCTOBER 15 THROUGH MAY 15.

THE AREA OF EXPOSED, UNSTABILIZED SOIL SHOULD BE LIMITED TO 1—ACRE AND SHOULD BE PROTECTED ACAINST EROSION BY THE METHODS DISCUSSED IN NHSMM, VOL. 3 AND ELSEWHERE IN THIS PLAN SET, PRIOR TO ANY THAW OR SPRING MELT EVENT.

STABILIZATION AS FOLLOWS SHOULD BE COMPLETED WITHIN A DAY OF ESTABLISHING THE GRADE THAT IS FINAL OR THAT OTHERWISE WILL EXIST FOR MORE THAM 5 DAYS:

MORE THAN 5 DAYS

2. ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF LESS THAN 15% WHICH DO NOT EMHIBIT MINIMUM 80% VEGETATIVE GROWTH BY OR ARE DID A TO SET THAN 15% WHICH DO NOT EMHIBIT MINIMUM 80% VEGETATIVE GROWTH BY OR ARE DID A TOOLS OF HAY OR STEAM WHICH PER ACRE SECURED WITH A ANCHORD NETTING, OR 2 NICHES OF EROSION CONTROL MIX (REFER TO NIHSMM, VOL. 3 FOR SPECIFICATION).

3. ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF GREATER THAN 15 % WHICH DO NOT EMHIBIT A MINIMUM OF 80% VEGETATIVE GROWTH BY OR ARE DISTURBED AFTER OCTOBER 15 HOULD BE SECEDED AND COVERED WITH A PROPERLY INSTALLED EROSION CONTROL MIX, UNLESS OTHERWISE SPECIFIED BY THE MANUFACTURER. NOTE THAT COMPOST BLANKET OR WITH A SHOULD NOT EXCEDED 2 TROCES ON THORNESS OTHERWISE SPECIFIED BY THE MANUFACTURER. NOTE THAT COMPOST BLANKETS SHOULD NOT EXCEDED 2 TROCES ON THORNESS OTHERWISE SPECIFIED BY THE MANUFACTURER. NOTE THAT COMPOST BLANKETS SHOULD NOT EXCEDED 2 TROCES ON THORNESS OTHERWAY OF THE MAY OF THE MAY

4. ALL STONE COMPRED SLOPES MUST BE CONSTRUCTED AND STABILIZED BY OCTOBER 15.

5. INSTALLATION OF ANCHORED HAY MULCH OR EROSION CONTROL MX SHOULD NOT OCCUP OVER SNOW OF GREATER THAN 1 INCH IN OFFITH.

6. ALL MULCH APPLIED DURING MINTER SHOULD BE ANCHORED (I.E. BY NETTING, TRACKING, WOOD CELLUROS FIBER).

7. WITHIN 24 HOURS OF STOCKPLING SOL MATERIALS SHOULD BE MULCHED FOR OVER MINTER PROTECTION WITH HAY OR STRAW AT TIMEE THE MORMAL RATE OR WITH A WITH LAY OR STRAW AT TIMEE THE MORMAL RATE OR WITH A WITH LAY OR STRAW AT TIMEE THE MORMAL RATE OR WITH A WITHIN LAY OR STRAW AT TIMEE THE MORMAL RATE OF WITH A WITHIN LAY OR STRAW AT TIMEE THE MORMAL RATE OF WITH A WITHIN LAY OR STRAW AT TIMEE THE MORMAL WITHIN THE WITHIN THE WITHIN SOLUTION OF THE WITHIN THE WITHIN LAY OR STRAW AT THE WITHIN CONTROL OF ANY WETLAND OR OTHER WATER RESOURCE AREA.

EPOLYCH MATERIAL (IE EPOLS) LAWE PREMOUND THE RINGS WHITE

NO SUE STOCKPILE SHOULD BE PLACED (EVEN COVERED WITH MULCH)
WITHIN 100-FT OF ANY WELLAND OR OTHER WATER RESOURCE AREA.

5. FROZEN MATERIA: (I.E. FROST LATER REMOVED DURING WHITER
CONSTRUCTION) SHOULD BE STOCKPILED SEPARAFLY AND WITH
CONSTRUCTION SHOULD BE STOCKPILED SEPARAFLY AND WITH
ALD DURING AND SEPARAFLY AND ADDRESS OF THE STOCKPILES CAN MELT IN SPRING AND BECOME UNMORKABLE AND
DIFFICULT TO TRANSPORT DUE TO SHOH SOIL MOISTURE CONTENT.

9. INSTALLATION OF EROSION CONTROL BLANKETS SHOULD NOT COCUR OVER
SNOW OF GREATER THAN 1 INCH IN DEPTH OR ON FOREXTH GROWN.

10. ALL GRASS-LINED DITCHES AND CHANNELS SHOULD BE CONSTRUCTED BY
SEPTEMBER 1. ALL DITCHES AND CHANNELS SHOULD BE CONSTRUCTED BY
VEGETATIVE GROWTH BY OR ARE DISTURBED AFTER OCTOBER 15. SHOULD
BE STABULZED TEMPORABLY WITH STONE OF ROSION CONTROL BLANKETS
PROCESSIONAL BEGINNER. IF, STONE UNING IS NECESSARY. THE BY A
PROCESSIONAL BEGINNER. IF, STONE UNING IS NECESSARY. THE BY A
PROCESSIONAL BEGINNER. IF, STONE UNING IS NECESSARY. THE BY A
PROVIDE ABCULATE CROSS-SECTION AFTER ALLOWING FOR PLACEMENT OF
THE STONE.

PROVIDE ADEQUATE CRUSS—SECTION OF INC. ABABT.

17. ALL STONE LINED DITCHES AND CHANNELS MUST BE CONSTRUCTED AND STABILIZED BY OCTOBER 15.

12. AFTER NOVEMBER 15, INCOMPLETE ROAD OR PARKING AREAS WHERE ACTIVE CONSTRUCTION HAS STOPPED FOR THE WINTER SHOULD BE PROTECTED WITH A WINNIGHT 3 INCH LAYER OF SAND AND GRAVEL WITH A GRADATION THAT IS LESS THAN 12X OF THE SAND PORTION, OR MATERIAL PASSING THE NUMBER 20D GIVE

SIEVE.
SIEVE.
SIEVE.
SEDIENT BARRERS THAT ARE INSTALED DURING FROZEN COMDITIONS
SHOULD CONSIST OF EROSION CONTROL M/N BERMS, OR CONTRIBUDIS
CONTAINED BERMS, SILT FENCES AND HAY BALES SHOULD NOT BE
INSTALLED WHEN FROZEN CONDITIONS PREVENT PROPER EMBEDMENT OF
THESE BARRIERS.

PROJECT SPECIFIC CONSTRUCTION PHASING:

TRANSPORTATION PLANNERS

REFER TO THE "CEMERAL CONSTRUCTION PHASING" NOTES PRIOR TO COMMERCING CONSTRUCTION PHASING NOTES PRIOR TO COMMERCING CONSTRUCTION PHASING. THE FOLLOWING PHASING, THE "CEMERAL CONSTRUCTION PHASING." NOTES APPLY TO THE OVERALL CONSTRUCTION AND SHALL BE ADHERED TO.

INSTALL ALL TEMPORARY SEDIMENT CONTROL BARRIERS (I.E. SLT FENCE, STONE CHECK DAMS, TIC.) AROUND THE OUTER PERIMETER OF THE CONSTRUCTION SITE AS DEPICTED ON SHELT. C.3. PRIOR TO EARTH MOVING OPERATIONS.

REMOVE ALL TRUCTURES, UTLITIES AND PAVEMENT AS DEPICTED ON SECOND AND DISPOSE OFF—SITE IN ACCORDANCE WITH STATE AND CLEAR, GRULATIONS.

CLEAR, GRULATIONS.

CLEAR, GRULATIONS.

REVISIONS

CLOCAL REGULATIONS.

CLOCAR GRUB AND STRIP THE SITE. STUMPS, BRUSH AND OTHER ORGANIC WASTE SHALL BE DISPOSED OF OFF-SITE IN ACCORDANCE WITH STATE AND LOCAL REGULATION.

SITE OF THE STATE OF THE STATE OF THE STATE OF THE STATE AND LOCAL REGULATION.

IN AN APPROPRIATE LOCATION IN ACCORDANCE WITH THE "SOIL STOCKPILES PRACTICES." MAINTAIN THE STOCKPILES AS DIRECTED IN THE STOCK OF THE REST OF THE STOCKPILES AS DIRECTED IN THE STOCKPILES AS DIRECTED IN THE DETENTION BASIN SHOWN ON SHEET C.—3.

PERFORM THE NECESSARY CUTS AND FILLS TO CONSTRUCT THE DETENTION BASIN SHOWN ON SHEET C.—6.

CONSTRUCT THE DETENTION BASIN SEDWENT FOREBAY AND OUTLET PROTECTION. LOAM SEED AND MULL THE SIDE SIOPES OF THE BASIN AS DIRECTED IN THE DETENTION BASIN DETAILS.

ALL DITCHES/SWALLS/AND BASINS SHALL BE STABILIZED PRIOR TO DIRECTION BASIN SEED AND MULL THE SIDE SIOPES OF THE BASIN AS DIRECTED IN THE DETENTION BASIN DETAILS.

AND PARKING LOT ASSACL.

AND PARKING LOT ASSACL.

AND PARKING LOT ASSACL.

AND PARKING SOME AMAINUM PROTOTO DEBITY.

10. AS SUBGRADE IS ACHIEVED INSTALL REMAINING SEDIMENT CONTROL.

BARRIERS WITHIN THE SITE (LE. ADDITIONAL SILT FENCE, CHECK DAMS AND SEDIMENT CONTROL. AND CATCH BASINS. BTO.)

11. INSTALL ALL UTLITES AND CLOSED DRAINAGE SYSTEM COMPONENTS (LE. PIPE CULVERTS, CATCH BASINS AND WATER MAIN) PER THE CORRESPONDING DTEMPORARY SEDIMENT CONTROL SHOW ON SHEET C.—3. AS EACH STRUCTURE IS COMPLETED IN STALL THE CORRESPONDING DTEMPORARY SEDIMENT CONTROL SHARED PERFORMENT WEST AND SEPECH ON SHEET C.—3. AS EACH STRUCTURE IS COMPLETED IN STALL THE CORRESPONDING DTEMPORARY SEDIMENT CONTROL SHARED PERFORMENT WEST AND AND STABILIZATION AS DESCRIBED UNDER THE "PERMANENT WEST AND AND STABILIZATION AS DESCRIBED UNDER THE "PERMANENT WEST AND AND STABILIZATION AS DESCRIBED UNDER THE "PERMANENT WEST AND AND STABILIZATION AS DESCRIBED UNDER THE "PERMANENT WEST AND AND STABILIZATION AS DESCRIBED WITHIN 3 DAYS OF ACHIEVED FINANCE DEBASE. AFTER

BASE COURSE) WITHIN 3 DAYS OF ACHIEVING FINISHED SUBGRADE
ELEVATIONS.

51 INSTALL PAYMENT SURFACES AS SOON AS POSSIBLE AFTER THE
INSTALLATION OF THE GRAVEL BASE AND CRUSHED GRAVEL IN ORDER TO
LIMIT THE SOIL EROSION AND POLLUTION OF THE GRAVEL MATERIALS WITH
ORGANIC MATERIALS. IN NO CASE SHALL AREAS TO BE PAYED BE LEFT
UNPROTECTED THROUGH OUT THE WINTER MONTHS.

16. ALL DISTRIBED AREAS SHALL BE STRAIL AREAS TO BE PAYED BE LEFT
UNDROTTED THROUGH OUT THE WINTER MONTHS.

17. ALL DISTRIBED AREAS SHALL BE STRAIL AND SOON AS POSSIBLE. IN
NO CASE SHALL ANY DISTURBED AREA BE LEFT UN-STABILIZED FOR
LONGER THAN 21 DATS. F. NECESSARY TEMPORARY STABILIZED THO
MAINTELANCE AND INSURED AREA BE LEFT UN-STABILIZED FOR
MAINTELANCE AND HASHIM, OU. 3 SHOULD BE EMPLOYED.

18. ENGINE CONTELL AND STORMWARE MANAGEMENT PRACTICES SHOULD BE
INSPECTED WERKLY AFTER EVERY 1/2 RICH OF RAINFALL, AND ANNUALLY,
EROSION CONTELL AND STORMWARE MANAGEMENT PRACTICES WHEN IT
RECACHES PRESCRIBED THRESHOLDS BISCUSSED IN THE DETAILS FOR EACH
PRACTICE.

PRACTICE.

ALL DAMAGED TEMPORARY AND PERMANENT SEDMENT, EROSION CONTROL
AND STORMWATER MANAGEMENT PRACTICES SHOULD BE REPAIRED OR
REPLACED IMMEDIATELY UPON NOTICE.
SEDMENT SHALL BE DISPOSED OF PROPERLY EITHER ON SITE OR OFF SITE.

20. SEDIMENT SHALL BE DISPOSED OF PROPERLY EITHER ON SITE OR OFF SIT PROJECT COMPLETION, AND STABILIZATION.
21. UPON PROJECT COMPLETION, ONCE THE SITE IS DEEMED STABILIZED VICEGETATION IS GERMINATED. THE TEMPORARY SEDIMENT CONTROL BARRIERS AND EROSION CONTROL PRACTICES SHALL BE REVOYED. ANY DISTURBANCE CREATED URING REMOVAL SHALL BE REPARED IN AN APPROPRIATE MANNER.
22. ACCUMILATED SEDIMENT SHALL BE REMOVED FROM ALL ON SITE CATCH BASINS AND THE SEDIMENT FOREBAYS TO THE DETENTION BASIN.

PERMANENT EROSION AND SEDIMENTATION CONTROL DETAILS

> OAK STREET / ROUTE 125 ROCHESTER, NH

> > PREPARED FOR

COLBY FOOTWEAR, INC.

SCALE: AS SHOWN

MARCH 2012

DWG NO. 12009\SP-2 F.B. NO. SDR

FILE NO. 288 PLAN NO. PERLIM 22222

GEOTEXTILE FABRIC

SECTION A-A

(PIPE OUTLET TO FLAT AREA NO

RIP-RAP GRADATION

d50 = 3"7 OF WEIGHT SMALLER SIZE OF STONE THAN THE GIVEN SIZE (INCHES)

APRON DIMENSION TABLE CUTLET FROT. # PIPE CUTLET Wo W to T d50
#1 12" CPP INLET 3.00 13 9' 9" 3"

NOTES:

IPPE CLIMETS SHALL HAVE END SECTIONS OR HEADWALLS. END SECTION

I. MLTERIAL AND MANUFACTURER SHALL MATCH THAT OF THE PIPE CULVERT,

ITHE LARGEST RIP—RAP SIZE DETERMENTS DURING HYDROLOGIC ANALYSIS HAS BEEN

USED FOR ALL OUTLETS FOR ECONOMY AND SIMPLICITY.

3. APRON LENGTHS, WORTHS AND THICKNESSES HAVE BEEN ROUNDED UP TO WHOLE

NUMBERS FOR EASE OF CONSTRUCTION.

CONSTRUCTION SPECIFICATIONS:

1. PREPARE THE SISH-GRADE FOR THE FILTER MATERIAL, GEOTEXTILE FABRIC, AND RIP-RAP TO THE GRADES SHOWN ON THE PLANS.

2. MINIMUM 6° SAND/GRAVEL BEDDING OR GEOTEXTILE FABRIC REQUIRED UNDER ALL ROCK

E ROCK OR GRAVEL USED FOR FILTER OR RIP-RAP SHALL CONFORM TO THE ECIFIED GRADATION.

THE ROCK OR GRAVEL USED FOR FILTER OR RIP—RAP SHALL CONFORM TO THE SPECIFIED GRADATION.

GEOTEVILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF ROCK RIP—RAP. DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIREDED FOR REPAIRS OR JUNING TWO (2) PIECES OF FABRIC SHALL BE A MINIMAM OF 12 NOCHES.

STONE FOR THE RIP—RAP MY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE TULL LAYER TRICKNESS IN ONE CEPTATION AND IN SUCH A MANNER AS TO PREVENT ESCREGATION OF THE STONE SIZES.

RIP—RAP SIZE CHOSEN FOR THE WORST CASE OF ALL OUTLEND.

STORM EVENT. ANY ENUSING US UNMADE TO THE BUT HOST SHOULD BE CHECKED TO MEDIATELY DOWNSTREAM FROM THE OUTLET SHOULD BE CHECKED TO THE DOWNSTREAM CHANNEL SHOULD BE KEPT CLEAR OF OBSTRUCTIONS SUCH AS FALLEN TREES, DEERIS, AND SEDIMENT THAT COULD CHANCE FLOW PATTERNS AND/OR TALLWATER DEPTHS ON THE PIPES. REPRINS MUST BE CAMPRIED OUT IMMEDIATELY TO AVOID ADDITIONAL DAMAGE TO THE OUTLET PROTECTION APRON.

MAINTENANCE NOTES:
1. OUTLETS SHALL BE INSPECTED AND CLEANED ANNUALLY AND AFTER ANY MAJOR STORM EVENT. ANY EROSION OR DAMAGE TO THE RIP—RAP SHALL BE REPAIRED

DUST CONTROL PRACTICES:

. APPLY DUST CONTROL MEASURES AS NECESSARY TO MAINTAIN CONTROL OF DUST ON SITE. WALEK APPLICATION:

A) MOISTEN EXPOSED SOIL SURFACES PERIODICALLY WITH ADEQUATE WATER TO CONTROL DUST.


B) AVOID EXCESSIVE APPLICATION OF WATER THAT WOULD RESULT IN MOBILIZING SEDIMENT AND SUBSEQUENT DEPOSITION IN NATURAL


WASHED AGGREGATE,
REFER TO "NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME
3 CONSTRUCTION PHASE EROSION AND SEDWENT CONTROLS, DECEMBER
2008" FOR OTHER ALLOWABLE DUST CONTROL PRACTICES (I.E. COMMERCIAL
TACKHIERES OR CHEMICAL TREATMENTS SUCH AS CALCIUM CHLORDE, ETC.)

CULVERT


CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION. SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WITH IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS


ASSOCIATES, INC. (603)-335-3948.





2 EAST (ROUTE 125) ELEVATION
A2.0 Scale: 1/16" = 11





Associates, Inc. One Automin Street Portsmouth, NB 03801 Phone: (603) 433 - 8639 Fax: (603) 431 - 2811 www.jsneng.com

Client:

Knights Construction 303 Reservoir Road Farmington, NH

Addition to Colby Footwear, Inc. Oak Street Rochester, NH

Preliminary Not for Construction 03-26-12



Revisions

Elevations