RESTORATION OF TEMPORARY WETLAND IMPACT

THE SEQUENCE OF CONSTRUCTION IN THIS AREA SHALL BE AS FOLLOWS:

- SILT FENCE SHALL BE INSTALLED AT THE LIMIT OF DISTURBANCE.
- THE "A HORIZON" WITHIN THE WETLAND AREA SHALL BE REMOVED AND STOCKPILED IN AN ADJACENT AREA. CARE SHALL BE TAKEN TO ENSURE SEDIMENT FROM THE STOCKPILE DOES NOT ERODE INTO A WETLAND AREA.
- THE SEWER LINE SHALL BE INSTALLED PER THE ENGINEERING PLANS AND BACKFILLED ACCORDINGLY.
- THE STOCKPILE OF "A HORIZON" SHALL BE THEN SPREAD OVER THE AREA RESTORING THE AREA TO PREDISTURBANCE GRADES.
- ANNUAL RYE GRASS SHALL BE SPREAD OVER THE DISTURBED AREA AS STRAW MULCH.
- SILT FENCE SHALL NOT BE REMOVED UNTIL THE AREA HAS RESTABILIZED.
- IF AFTER THE FIRST GROWING SEASON THE VEGETATION HAS NOT ESTABLISHED ITSELF THE AREA SHALL BE OVERSEEDED.

FOR CONTINUATION OF 8" WATER SUPPLY SEE PLAN NO. C-04, PREPARED BY WRIGHT-PIERCE, REVISED JULY 2010 BY LEWIS ENGINEERING, PLLC. ENTITLED " PRESSURE ZONE WATER MAIN INTERCONNECTION, STA. +100.00 TO +119.00".
(PLAN LAST SAVED BY DKR 4/24/2008 1:20 PM)

PREPARED BY
ROBERT G. ROOK, P.E.
Consulting Engineer
72 Pleasant Street
Concord, N.H. 03301
RGRook@comcast.net
Voice (603) 223-0358
Fax (603) 715-2374

APPROVAL CERTIFIED BY _____ DATE _____

GENERAL PLAN

HIGHFIELD COMMONS

PREPARED FOR:
183 WASHINGTON STREET, LLC
501 DANIEL WEBSTER HIGHWAY
MERRIMACK, NH 03054

REVISIONS DURING CONSTRUCTION

No.	DESCRIPTION	DATE
1.	REVISED WATER SERVICE; REVISED SEWER CONNECTION	8/25/10
2.		
3.		
4.		
5.		
6.		
7.		

SCALE IN FEET: 40 0 40 80 120

PROJ. NO.	DATE:	DWG. NO.	DRAWN BY:	SHEET NO.
86.3	8-25-10	166.1-001	MDC	G-4