7.00	
	City of Rochester
	Gon: (P001
72.702.103.2	BiO # 14-37
	may 15,2014
	Perrock 338112,00 + 800.00 presure decinine
	Custom Pus 333720.00
	COLOLD AND PROVO
- 10	
- Parameter	
	Cope Shay
	( Of a Cay
	South min
	3-15-14
	5-15-11

## **Bid Specifications**

The following specifications are for the replastering of the Gonic Pool for the City of Rochester. All work must be completed by June 20, 2014.

# Requirements:

# Gonic Pool

•		•
1.	Drain	noot
	210111	Poor

- 2. Saw cut under tile
- Chip back existing finish under tile approx three inches down, to allow for a 3. smooth transition of new finish.
- 4. Saw cut around drains, returns, anchors, etc.
- 5. Chip back all areas where cut for a smooth transition.
- Saw out around all tiled racing lanes and chip back same as pool-tile. (addendum # 2)

  Check entire pool for hollowers. 6.
- 7. Check entire pool for hollow spots, remove all hollow spots and repair these areas.
- 8. Acid wash to etch finish, then neutralize.
- 9. Apply multicoat scratch kote 2000 bonding coating to pool.
- 10. Replaster pool in one day.

address: purchasing@rochesternh.net

- 11. Replaster pool with white marcite finish
- 12. Start up pool system

Ve	andor Name: BOYTOCK Pools L.L.C.
	Address: 1201 Washington RQ. Rye, N.H. 03870
	Phone: 706-0200 Fax# 603-964-3731 E-mail Boyrockpools @ G mail.com
	Print Name & Title: Michael A Oakos (owner)
	Authorized Signature: Nichael a Oabst
	Total Bid to Replaster The Gonic Pool
	s 35,112.00 (pressure test drain line add)
	Bid results will be posted after 48 hours on the City of Rochester's web site:  www.rochesternh.net or will be available by request via e-mail at the following

# **Proposal**

# **CUSTOM POOLS, INC**

373 Shattuck Way Newington, NH 03801 (603) 431-7800

Fax (603) 431-5109

May 15, 2014

City of Rochester NH 310 Wakefield St. Rochester, NH

Gonic Pool

#### Main Pool

- 1.) Drain Pool.
- 2.) Pressure test main drain line.
- 3.) Saw cut under tile.
- 4.) Chip back existing finish under tile approx three inches down, to allow for a smooth transition of new finish.
- 5.) Saw cut around drains, returns, anchors, etc.
- 6.) Remove existing lane marker anchors and fill in.
- 7.) Chip back all areas where cut for a smooth transition.
- 8.) Remove all tiled racing lanes and targets.
- 9.) Repair approximately 12ft tile.
- 10.) Acid wash to etch finish, then neutralize.
- 11.) Apply Multicoat Scratch Kote 2000 bonding coating to pool.
- 12.) Install two (2) main drain covers. To be VGB approved.
- 13.) Replaster pool in one day.
- 14.) Replaster pool with white marcite finish.
- 15.) Start up pool system.

#### Total \$33,720.00

The following are the responsibilities of the owner:

- 1.) Supply of water for construction and filling of the pool..
- 2.) Damage of pool due to hydrostatic water damages.
- 3.) Brushing of pool 2 times daily for 2 weeks.
- 4.) Continued water chemistry monitoring.
- 5.) Any and all electrical needs.
- 6.) Costs of any unforeseen repairs.

Please feel free to call me with any questions at 603-431-7800

Sinterely,

Sales Manager

# **Bid Specifications**

The following specifications are for the replastering of the Gonic Pool for the City of Rochester. All work must be completed by June 20, 2014.

## Requirements:

#### Gonic Pool

- 1. Drain pool
- 2. Saw cut under tile
- 3. Chip back existing finish under tile approx three inches down, to allow for a smooth transition of new finish.
- 4. Saw cut around drains, returns, anchors, etc.
- 5. Chip back all areas where cut for a smooth transition.
- 6. Saw cut around all tiled racing lanes and chip back same as pool tile.
- 7. Check entire pool for hollow spots, remove all hollow spots and repair these areas.
- 8. Acid wash to etch finish, then neutralize.
- 9. Apply multicoat scratch kote 2000 bonding coating to pool.
- 10. Replaster pool in one day.
- 11. Replaster pool with white marcite finish
- 12. Start up pool system

Vendor Name:	Cust	tom	Pools	INC			
Address:	373	ShA	Huck	WAY	Newny	BUNK	
					E-mail OCOr	Jy Q Custon	1
Print Name	& Title:	in	Landy	6.	M,		, con
Authorized	Signature:	L. 1	n	-			
Total Bid to	Replaster The	Gonic Po	ool				
\$	337	209	0				

Bid results will be posted after 48 hours on the City of Rochester's web site: <a href="https://www.rochesternh.net">www.rochesternh.net</a> or will be available by request via e-mail at the following address: <a href="mailto:purchasing@rochesternh.net">purchasing@rochesternh.net</a>