


## NOTICE TO BIDDERS

May 25, 2007

### ADDENDUM NO. 1

(Bid No. 07-60)

**Congress Street Improvements**  
Rochester, New Hampshire



A handwritten signature in black ink, appearing to read "David A. Lewis", written over the bottom right portion of the professional seal.

Bidders shall acknowledge receipt of this Addendum No. 1  
on the Bid Form, Page BF-1

#### Item 1: Bid Date/Time

Bidders are hereby notified that there has been no change in the bid due date or time.

#### Item 2: Bid Form

- Bidders are hereby notified that Item No. 202.5 should read: "Removal of Catch Basins, Drop Inlets, and Manholes."
- Bidders are hereby notified that Item No. 670.15 "Ornamental Street Lighting" is redundant and will be not be used. (Cost for street lighting should be entered under Item 625.551 "Ornamental Street Lighting, Type A.")

#### Item 3: Special Provision 606.10 - Parking Guardrail

The attached Special Provision 606.10 - Parking Guardrail describes requirements for this item.

**END OF ADDENDUM NO. 1**

**ROCHESTER  
CONGRESS STREET**

May 25, 2007

**SPECIAL PROVISION**

**PARKING GUARDRAIL**

**Description**

**1.1 General Description of Work.** This work shall consist of installing a new guardrail assembly to replace the existing damaged guardrail at the south parking lot.

**1.1.1** The CONTRACTOR shall furnish all materials, labor, tools and equipment, and perform all operations, testing, and incidentals necessary to install the new system, as outlined herein and on the plans.

**1.2 Submittal.** Supply sketch showing guardrail elements and spacing of posts.

**Materials**

**2.1 General** - The CONTRACTOR shall provide the following features.

**2.1.1** Guardrail – Galvanized W-beam.

**2.1.2** Wooden posts, offset blocks, and all hardware.

**2.1.3** Type G terminal units.

**Construction Requirements**

**3.1 Installation.** Coordinate installation with pavement limits and landscaping to prevent ponding.

**Method of Measurement**

**4.1** Parking Guardrail will be measured as a linear foot item between the terminal units.

**4.2** The ENGINEER must be involved in and approve the measurement of any pay item.

**Basis of Payment**

**5.1** The accepted work will be paid at the linear foot contract price complete in place, as shown on the plan and specified herein, and shall include designing, furnishing and installing, adjustments due to other work, and all other work required for or incidental to the completion of this item.

**Pay Item and Unit**

606.10	Parking Guardrail	Linear Foot
--------	-------------------	-------------