

ADDENDUM NO. 2

TO

**BIDDING AND CONTRACT REQUIREMENTS AND
SPECIFICATIONS FOR**

24-24 Gymnasium Bleacher Replacement

CITY OF ROCHESTER, NEW HAMPSHIRE

BID NO. 24-24

This Addendum amends and/or supplements the Bid Documents as indicated below. Only these items alter the Bid Documents; any conflicting oral discussions or responses are hereby declared null and void.

BID CLARIFICATIONS AS FOLLOWS:

Scope of Work Requirements Clarification:

- Complete removal and disposal of the north end **16** tier bank of retractable bleachers.

Current Bleacher Measurements:

- Court 3 (North End Set of Bleachers) has a total of 16 tiers of seating.
- Court 1 (South End Set of Bleachers) set has a total of 20 tiers of seating.

The following measurements apply to both sets of bleachers:

- Each set of bleachers are exactly 88' in width excluding side rails.
- Each set has a 3' wide stair section up the middle.
- All tiers, excluding the top of each set, has 85' of available seating area due to the stair sections.

Desired Bleacher Specifications:

The following apply to both sets of bleachers:

- The new bleachers will be 88' in length.
- Both wireless and manual controls are requested. A handheld pendent and wireless remote are requested.