


PROPOSED MANUFACTURING FACILITY

FOR

CITY OF ROCHESTER 145 AIRPORT DRIVE ROCHESTER, N.H. 03867 DECEMBER 2019

Not For Construction





CIVIL ENGINEERS

NORWAY PLAINS ASSOCIATES, INC. 2 CONTINENTAL BOULEVARD ROCHESTER, NEW HAMPSHIRE 03867 (603) 335-3948

CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION. SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WITH IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS ASSOCIATES, INC. (603)-335-3948.

OWNER OF RECORD


CITY OF ROCHESTER 31 WAKEFIELD STREET ROCHESTER, NEW HAMPSHIRE 03867 (603) 335-7500

LANDSCAPING ARCHITECTS

WOODBURN & COMPANY LANDSCAPE ARCHITECTURE, LLC 103 KENT PLACE NEWMARKET, NEW HAMPSHIRE 03857 (603) 659-5949

APPLICANT

CITY OF ROCHESTER 31 WAKEFIELD STREET ROCHESTER, NEW HAMPSHIRE 03867 (603) 335-7500



<u>STATE AND FEDERAL PERMITS:</u> STATE OF NEW HAMPSHIRE PERMIT NUMBERS: NHDES ALTERATION OF TERRAIN: NHDES WETLANDS PERMIT: NHDES DAM PERMIT: NHDES SUBDIVISION PERMIT: NHDES SUBSURFACE SYSTEMS PERMIT: NHDES WASTEWATER PERMIT: NHDOT DRIVEWAY/ENTRANCE PERMIT:

NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES):

NPDES PERMITS ARE ONLY REQUIRED FOR PROJECTS MEETING THE DISTURBED AREA CRITERIA BELOW AND HAVING A POINT SOURCE STORMWATER DISCHARGE FROM THE SITE TO AN ADJACENT WETLAND OR WATER BODY (I.E. CULVERT, SWALE, ETC. OUTLETING TO A WETLAND, CREEK, STREAM OR RIVER).

NPDES PERMIT:

CERTIFIED BY: _____


NPDES PERMITS CONSIST OF A NOTICE OF INTENT (NOI) FILED WITH THE ENVIRONMENTAL PROTECTION AGENCY AT LEAST 14 DAYS PRIOR TO CONSTRUCTION COMMENCING AND A STORMWATER POLLUTION PREVENTION PLAN (SWPPP) BEING PREPARED, KEPT ON SITE AND FOLLOWED BY THE CONTRACTOR.


FOR STATUS OF THIS PERMIT, CONTACT THE PROJECT GENERAL CONTRACTOR


FINAL APPROVAL BY ROCHESTER PLANNING BOARD


SHEET INDEX SHEET E-1 EXISTING FEATURES PLAN 1" = 40'SHEET C-1 OVERALL SITE PLAN 1" = 60'C-2SITE LAYOUT PLAN 1" = 40'SHEET C-3 GRADING AND DRAINAGE PLAN 1" = 40'1" = 40'SHEET C-4 UTILITY PLAN 1" = 40'EROSION AND SEDIMENTATION CONTROL PLAN CONSTRUCTION DETAILS AS SHOWN C-6 SHEET C-7 DRAINAGE DETAILS AS SHOWN GRAVEL WETLANDS BASIN DETAILS AS SHOWN TEMPORARY EROSION AND SEDIMENTATION AS SHOWN CONTROL DETAILS SHEET C-10 PERMANENT EROSION AND SEDIMENTATION AS SHOWN CONTROL DETAILS SHEET C-11 UTILITY DETAILS AS SHOWN SHEET C-12 SEWER DETAILS AS SHOWN SHEET C-13 GUARDRAIL DETAILS AS SHOWN SHEET L-1 LANDSCAPING PLAN AND DETAILS 1" = 40'1" = 40'SHEET L-2 LIGHTING PLAN AND DETAILS


FILE NO. 104 PLAN NO. C-3013 DWG NO. $19275 \SP-7$ F.B. NO. SDR-TJR






















ON ALL SIDES FOUNDATION (MIRAFI 140N OR EQUAL) 3" CRUSHED STONE 6" PERFORATED PVC DRAINAGE

FOUNDATION DRAIN DETAIL

NOT TO SCALE






SIDE VIEW

FRONT VIEW FLAIRED END SECTION DETAIL

NOT TO SCALE


FILE NO. 104 PLAN NO. C-3013 DWG NO. 19275\SP-F.B. NO. SDR-TJR

31 Mooney Street, Alton, N.H. 603-875-3948



CIVIL ENGINEERS TRANSPORTATION PLANNERS

CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WIT IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS ASSOCIATES, INC. (603)-335-3948.



INFILTRATION BASIN:

LIMITS OF THE INFILTRATION BASIN.

OR GREATER IN A 24-HOUR PERIOD.

AND CROSS-SECTION.

MAINTENANCE REQUIREMENTS:

SPECIFICATIONS:

1. DO NOT DISCHARGE SEDIMENT-LADEN WATERS FROM CONSTRUCTION
ACTIVITIES (RUNOFF, WATER FROM EXCAVATIONS) TO THE INFILTRATION BASIN.

AFTER THE BASIN IS EXCAVATED TO THE FINAL DESIGN ELEVATION, THE

4. VEGETATION SHALL BE ESTABLISHED IMMEDIATELY AFTER FINIAL GRADING IS

LOAM AND SEED ONLY THE SLOPES OF THE INFILTRATION BASIN AS

PRESCRIBED IN THE "PERMANENT VEGETATION" NOTES FOUND ON SHEET C-10. SEED MIXTURE = A
DO NOT PLACE INFILTRATION SYSTEMS INTO SERVICE UNTIL THE CONTRIBUTING AREAS HAVE BEEN FULLY STABILIZED.

1. INSPECT PRETREATMENT MEASURES (I.E. SEDIMENT FOREBAY(S), HOODED

GREATER THAN 2.5 INCHES OF RAIN OVER A 24-HOUR PERIOD.

CATCH BASINS, ETC.) AT LEAST TWICE A YEAR AND AFTER EVERY STORM

INSPECT INFILTRATION SURFACE BI-ANNUALLY. ONCE IN THE SPRING PRIOR TO MAY 15 AND ONCE IN THE FALL PRIOR TO OCTOBER 15.

INSPECT INFILTRATION SURFACE AFTER ANY RAINFALL EVENT OF 2.5-INCHES

EMBANKMENTS (MINIMUM TWICE A YEAR) TO ELIMINATE WOODY GROWTH FROM

REMOVE AND DISPOSE OF ACCUMULATED SEDIMENT BASED ON INSPECTION. REPAIR AREA OF REMOVAL AS NECESSARY TO RESTORE INFILTRATION

PERFORM MAINTENANCE AND REHABILITATION BASED ON INSPECTIONS.

REMOVE DEBRIS (IF ANY) FROM INFILTRATION BASIN INLET BASED ON

CONDUCT PERIODIC MOWING OF THE INFILTRATION BASIN SLOPES AND

THE EMBANKMENTS AND BOTTOM. MOWING THE INFILTRATION BASIN EMBANKMENTS WHEN MOWING THE REST OF THE SITE IS RECOMMENDED.

OF THE FACILITY TO DETERMINE MEASURES REQUIRED TO RESTORE

INFILTRATION FUNCTION, INCLUDING BUT NOT LIMITED TO REMOVAL OF ACCUMULATED SEDIMENTS OR RECONSTRUCTION OF THE INFILTRATION

8. IF THE INFILTRATION SYSTEM DOES NOT DRAIN WITHIN 72-HOURS FOLLOWING

A RAINFALL EVENT, THEN A QUALIFIED PROFESSIONAL (I.E. PROFESSIONAL ENGINEER, CERTIFIED SOILS SCIENTIST, ETC.) SHALL ASSESS THE CONDITION


DO NOT TRAFFIC EXPOSED SOIL SURFACE WITH CONSTRUCTION EQUIPMENT. IF

FLOOR SHALL BE DEEPLY TILLED WITH A ROTARY TILLER OR DISC HARROW

TO RESTORE INFILTRATION RATES, FOLLOWED BY A PASS WITH A LEVELING

CONSTRUCT THE INFILTRATION BASIN TO THE GRADES DEPICTED ON THE PLAN

FEASIBLE, PERFORM EXCAVATIONS WITH EQUIPMENT POSITIONED OUTSIDE THE



INFILTRATION BASIN #1 CROSS SECTION

INFITRATION BASIN -BERM= 276.0' 4" LOAM AND SEED MINIMUM 12" DRAIN TOP-(3:1 SLOPE) RIM = 275.0'INFITRATION BASIN EARTHEN BERM TO BE CLEAN SILTY OR CLAYEY MATERIAL UNIFIED SOIL CLASSIFICATION CH OR CL, SUBMIT SAMPLES TO ENGINEER FOR APPROVAL PRIOR TO CONSTRUCTION. BOTTOM = 274.0'INSTALL MATERIAL IN 6" LIFTS. — 12 x 12"
PVC SDR35 - FERNCO FLEXIBLE COUPLING (OR

INFILTRATION BASIN #1 **OUTLET STANDPIPE DETAIL** NOT TO SCALE


Not For Construction


DRAINAGE DETAILS TAX MAP 243, LOT 34 127 & 145 AIRPORT DRIVE ROCHESTER, NH PREPARED FOR:

OF ROCHESTER

SCALE: AS SHOWN

DECEMBER 2019





GRATE &

PLAN

SQUARE

OPENING

ELEVATION

SLAB TO BE PLACED IN LIEU OF TAPERED SECTION WHERE PIPE WOULD OTHERWISE ENTER INTO TAPERED SECTION OF THE STRUCTURE AND WHERE

SLAB TOP MAY BE CASTED WITH MINIMUM OR NO INTERLOCKING CHANNEL. HOWEVER, THE CONTRACTOR MUST ENSURE THE SLAB TOP IS FIRMLY

NOT TO SCALE

SECTION A-A

FRAME AND GRATE SHALL BE CAST IRON. FRAME AVAILABLE IN 4" OR 8" HEIGHTS.

NOT TO SCALE

ALL DIMENSIONS ARE NOMINAL.

ATTACHED TO THE STRUCTURE.

4', 5', OR 6' I.D.


NOTE: "THIS SIDE UP"

SHALL BE INDENTED ON

TOP SIDE OF PRECAST

SECTION


DIMENSIONS ARE FOR 12" DIAMETERS.
UNITS ARE AVAILABLE IN 8", 10", 12", 15" AND 18" DIAMETERS. ELIMINATOR CATCH BASIN OIL AND DEBRIS TRAP DETAIL NOT TO SCALE




PIPES MAY BE INSTALLED BY EXCAVATING AN OPEN TRENCH WITH SIDE SLOPES OF 1:1 MAXIMUM TO A DEPTH OF 4-FT. INTALLATIONS DEEPER THAN 4-FT REQUIRE THE USE OF A TRENCH BOX.
 PIPE MATERIALS SHALL BE AS SPECIFIED ON THE DESIGN PLAN.
 SAND BLANKET MAY BE OMITTED FOR REINFORCED CONCRETE PIPE.

DRAINAGE PIPE TRENCH INSTALLATION DETAIL NOT TO SCALE

NORWAY PLAINS ASSOCIATES, INC.





ALL BLANKET AND MATS SHALL BE INSPECTED WEEKLY DURING THE CONSTRUCTION PERIOD, AND AFTER ANY RAINFALL EVENT EXCEEDING 1/2 INCH IN A 24-HOUR PERIOD. ANY FAILURE SHALL BE REPAIRED IMMEDIATELY. IF WASHOUT OF THE SLOPE, DISPLACEMENT OF THE MAT, OR DAMAGE TO THE MAT OCCURS, THE AFFECTED SLOPE SHALL BE REPAIRED AND RESEEDED, AND THE AFFECTED AREA OF MAT SHALL BE RE-INSTALLED.

MANUFACTURE'S INSTALLATION INSTRUCTIONS: A. PREPARE SOIL BEFORE INSTALLING ROLLED EROSION CONTROL PRODUCTS (RECP's), INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED. NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED MUST BE INSTALLED WITH PAPER SIDE DOWN. B. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE RECP'S IN A 6" (15 CM) DEEP X 6" (15 CM) WIDE

CONSTRUCTION SPECIFICATIONS:

TRENCH WITH APPROXIMATELY 12" (30cm) OF RECP's EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE RECP'S WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" (30 CM) PORTION OF RECP'S BACK OVER SEED AND COMPACTED SOIL. SECURE RECP's OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" (30 CM) APART ACROSS THE WIDTH OF THE RECP's.

. ROLL THE RECP's (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE. RECP's WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL RECP'S MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING THE DOT SYSTEM, STAPLES/STAKES SHALL BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.

D. THE EDGES OF PARALLEL RECP'S MUST BE STAPLED WITH APPROXIMATELY 2" - 5" (5 CM - 12.5 CM) OVERLAP DEPENDING ON RECP'S TYPE.


CONSECUTIVE RECP'S SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" (7.5 CM) OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" (30 CM) APART ACROSS ENTIRE RECP's WIDTH. NOTE: IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" (15 CM) MAY


BE NECESSARY TO PROPERLY SECURE THE RECP's. SITE PREPARATION: PROPER SITE PREPARATION IS ESSENTIAL TO ENSURE COMPLETE CONTACT OF THE PROTECTION MATTING WITH THE SOIL. GRADE AND SHAPE AREA IF INSTALLATION. REMOVE ALL ROCKS, CLODS, TRASH, VEGETATIVE OR OTHER OBSTRUCTIONS SO THAT THE INSTALLED BLANKETS WILL

HAVE DIRECT CONTACT WITH THE SOIL. PREPARE SEEDBED BY LOOSENING 2-3 INCHES OF TOPSOIL ABOVE FINAL GRADE. INCORPORATE AMENDMENTS, SUCH AS LIME AND FERTILIZER, INTO SOIL ACCORDING TO SOIL TEST AND THE SEEDING

SFFDING: A. SEED AREA BEFORE BLANKET INSTALLATION FOR EROSION CONTROL AND REVEGETATION. SEEDING AFTER MAT INSTALLATION IS OFTEN SPECIFIED FOR THE AREAS DISTARDED DURING INSTALLATION MUST BE RESEEDED.

WHEN THE CONTROL AND PRIOR TO FEED TO SOIC ON TROLL AND PRIOR TO SOIC ON TROLL AND TROLL AND PRIOR TO SOIC ON TROLL AND PRIOR TO SOIC ON TROLL AND NOT TO SCALE





SPACING BETWEEN STONE CHECK DAMS

CONSTRUCTION SPECIFICATIONS:

1. STRUCTURES SHALL BE INSTALLED ACCORDING TO THE DIMENSIONS SHOWN ON THE PLANS AT THE

CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER SO THAT EROSION, AIR AND WATER POLLUTION WILL BE MINIMIZED.

STRUCTURES SHALL BE REMOVED FROM THE CHANNEL WHEN THEIR USEFUL LIFE HAS BEEN COMPLETED.

TEMPORARY GRADE STABILIZATION STRUCTURES SHALL BE INSPECTED AFTER EACH STORM AND DAILY DURING PROLONGED STORM EVENTS. ANY DAMAGE TO THE STRUCTURES SHALL BE REPAIRED PARTICULAR ATTENTION SHALL BE GIVEN TO END RUN AND EROSION AT THE DOWNSTREAM TOE OF THE

WHEN REMOVING THE STRUCTURES, THE DISTURBED AREAS SHALL BE BROUGHT UP TO EXISTING CHANNEL

GRADE AND THE AREAS PREPARED, SEEDED AND MULCHED.

SEDIMENT SHALL BE REMOVED FROM BEHIND THE STRUCTURES WHEN IT REACHES 1/2 THE ORIGINAL HEIGHT OF THE STRUCTURE.


STONE CHECK DAM **INSTALLATION DETAIL**

FILE NO. 104 *PLAN NO. C-3013* DWG NO. 19275\SP-F.B. NO. SDR-TJR

NOT TO SCALE

31 Mooney Street, Alton, N.H. 603-875-3948

FABRIC FENCE



CROSS-SECTION

FENCES SHALL BE INSPECTED AND MAINTAINED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALLS; 2. SEDIMENT DEPOSITION SHALL BE REMOVED, AT A MINIMUM, WHEN DEPOSITION ACCUMULATES TO ONE-HALF THE HEIGHT OF THE FENCE, AND MOVED TO AN APPROPRIATE LOCATION SO THE SEDIMENT IS NOT READILY TRANSPORTED BACK TOWARD THE SILT FENCE. SILT FENCES SHALL BE REPAIRED IMMEDIATELY IF THERE ARE ANY SIGNS OF EROSION OR SEDIMENTATION BELOW THEM. IF THERE ARE SIGNS OF UNDERCUTTING AT THE CENTER OR THE EDGES OF THE BARRIER, OR IMPOUNDING OF LARGE VOLUMES OF WATER BEHIND THEM, SEDIMENT BARRIERS SHALL BE REPLACED WITH A TEMPORARY CHECK DAM.

SHALL THE FABRIC ON A SILT FENCE DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL IS NECESSARY; THE FABRIC SHALL BE REPLACED PROMPTLY. 5. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM TO THE EXISTING

MEASURES, SUCH AS TEMPORARY DIVERSIONS AND SEDIMENT TRAPS. SILT FENCES HAVE A USEFUL LIFE OF ONE SEASON. ON LONGER CONSTRUCTION PROJECTS, SILT FENCE SHALL BE REPAIRED PERIODICALLY AS REQUIRED TO MAINTAIN EFFECTIVENESS.

IF THERE IS EVIDENCE OF END FLOW ON PROPERLY INSTALLED BARRIERS, EXTEND BARRIERS UPHILL OR CONSIDER REPLACING THEM WITH OTHER

FENCES SHALL BE USED IN AREAS WHERE EROSION WILL OCCUR ONLY IN THE FORM OF SHEET EROSION AND THERE IS NO CONCENTRATION OF WATER IN A CHANNEL OR DRAINAGE WAY ABOVE THE FENCE. SEDIMENT BARRIERS SHALL BE INSTALLED PRIOR TO ANY SOIL DISTURBANCE OF THE CONTRIBUTING DRAINAGE AREA ABOVE THEM.

THE MAXIMUM CONTRIBUTING DRAINAGE AREA ABOVE THE FENCE SHALL BE LESS THAN 1 ACRE PER 100 LINEAR FEET OF FENCE; THE MAXIMUM LENGTH OF SLOPE ABOVE THE FENCE SHALL BE 100 FEET;

THE MAXIMUM SLOPE ABOVE THE FENCE SHALL BE 2:1; FENCES SHALL BE INSTALLED FOLLOWING THE CONTOUR OF THE LAND AS CLOSELY AS POSSIBLE, AND

THE ENDS OF THE FENCE SHALL BE FLARED UPSLOPE; B. THE FABRIC SHALL BE EMBEDDED A MINIMUM OF 4 INCHES IN DEPTH AND INCHES IN WIDTH IN A TRENCH EXCAVATED INTO THE GROUND, OR IF SITE CONDITIONS INCLUDE FROZEN GROUND, LEDGE, OR THE PRESENCE OF HEAVY ROOTS, THE BASE OF THE FABRIC SHALL BE EMBEDDED WITH A MINIMUM THICKNESS OF 8 INCHES OF 3/4-INCH STONE;

THE SOIL SHALL BE COMPACTED OVER THE EMBEDDED FABRIC; D. SUPPORT POSTS SHALL BE SIZED AND ANCHORED ACCORDING TO THE MANUFACTURER'S INSTRUCTIONS WITH MAXIMUM POST SPACING OF 6 FEET; E. ADJOINING SECTIONS OF THE FENCE SHALL BE OVERLAPPED BY A MINIMUM OF 6 INCHES (24 INCHES IS PREFERRED), FOLDED AND STAPLED TO A SUPPORT POST. IF METAL POSTS ARE USED, FABRIC SHALL BE WIRE—TIED DIRECTLY TO THE POSTS WITH THREE DIAGONAL TIES. SILT FENCING SHALL NOT BE STAPLED OR NAILED TO TREES.

THE FILTER FABRIC SHALL BE A PERVIOUS SHEET OF PROPYLENE, NYLON, POLYESTER OR ETHYLENE YARN AND SHALL BE CERTIFIED BY THE MANUFACTURER OR SUPPLIER. THE FILTER FABRIC SHALL CONTAIN ULTRAVIOLET RAY INHIBITORS AND STABILIZERS TO PROVIDE A MINIMUM OF 6 MONTHS OF EXPECTED USABLE CONSTRUCTION LIFE AT A TEMPERATURE RANGE OF 0 DEGREES FAHRENHEIT TO 120 DEGREES FAHRENHEIT.

9. POSTS FOR SILT FENCES SHALL BE EITHER 4-INCH DIAMETER WOOD OR 1.33 POUNDS PER LINEAR FOOT STEEL WITH A MINIMUM LENGTH OF 5 FEET. STEEL POSTS SHALL HAVE, PROJECTIONS FOR FASTENING WIRE TO THEM. POSTS SHALL BE PLACED ON THE DOWN SLOPE SIDE OF THE 10. THE HEIGHT OF A SILT FENCE SHALL NOT EXCEED 36 INCHES AS HIGHER FENCES MAY IMPOUND VOLUMES OF WATER SUFFICIENT TO CAUSE FAILURE

11. THE FILTER FABRIC SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID THE USE OF JOINTS. WHEN JOINTS ARE NECESSARY; FILTER CLOTH SHALL BE SPLICED TOGETHER ONLY AT SUPPORT POST, WITH A MINIMUM 6-INCH OVERLAP, AND SECURELY

12. A MANUFACTURED SILT FENCE SYSTEM WITH INTEGRAL POSTS MAY BE USED.

13. POST SPACING SHALL NOT EXCEED 6 FEET. 14. A TRENCH SHALL BE EXCAVATED APPROXIMATELY 4 INCHES WIDE AND 4 INCHES DEEP ALONG THE LINE OF POSTS AND UP GRADIENT FROM THE 15. THE STANDARD STRENGTH OF FILTER FABRIC SHALL BE STAPLED OR WIRED TO THE POST, AND 8 INCHES OF THE FABRIC SHALL BE EXTENDED INTO

THE TRENCH. THE FABRIC SHALL NOT EXTEND MORE THAN 36 INCHES ABOVE THE ORIGINAL GROUND SURFACE. 16. THE TRENCH SHALL BE BACKFILLED AND THE SOIL COMPACTED OVER THE FILTER FABRIC. 17. SILT FENCE MAY BE INSTALLED BY "SLICING" USING MECHANICAL EQUIPMENT SPECIFICALLY DESIGNED FOR THIS PROCEDURE. THE SLICING METHOD USES AN IMPLEMENT TOWED BEHIND A TRACTOR TO "PLOW" OR SLICE THE SILT FENCE MATERIAL INTO THE SOIL. THE SLICING METHOD MINIMALLY

DISRUPTS THE SOIL UPWARD AND SLIGHTLY DISPLACES THE SOIL, MAINTAINING THE SOIL'S PROFILE AND CREATING AN OPTIMAL CONDITION FOR SUBSEQUENT MECHANICAL COMPACTION. 18. SILT FENCES SHALL BE INSTALLED WITH "SMILES" OR "J-HOOKS" TO REDUCE THE DRAINAGE AREA THAT ANY SEGMENT WILL IMPOUND. 19. THE ENDS OF THE FENCE SHALL BE TURNED UPHILL.

20. SILT FENCES PLACED AT THE TOE OF A SLOPE SHALL BE SET AT LEAST 6 FEET FROM THE TOE M ALLOW SPACE FOR SHALLOW PONDING AND TO ALLOW FOR MAINTENANCE ACCESS WITHOUT DISTURBING THE SLOPE. 21. SILT FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREAS HAVE BEEN PERMANENTLY STABILIZED.

SILTATION CONTROL FENCE DETAIL NOT TO SCALE

TEMPORARY VEGETATION SEEDING RECOMMENDATIONS

SPECIES	PER ACRE BUSHELS (BU) OR POUNDS (LBS.)	PER 1,000-SF	REMARKS		
WINTER RYE	2.5 BU OR 112 LBS.	2.5 LBS.	BEST FOR FALL SEEDING. SEED FROM AUGUST 15 TO SEPTEMBER 15 FOR BEST COVER. SEED TO A DEPTH OF 1 INCH.		
OATS	2.5 BU OR 80 LBS.	2.0 LBS.	BEST FOR SPRING SEEDING. SEED NO LATER THAN MAY 15 FOR SUMMER PROTECTION. SEED TO A DEPTH OF 1 INCH.		
ANNUAL RYE GRASS	40 LBS.	1.0 LB.	GROWS QUICKLY, BUT IS OF SHORT DURATION. USE WHERE APPEARANCES ARE IMPORTANT. SEED EARLY SPRING AND/OR BETWEEN AUGUST 15 AND SEPTEMBER 15. COVER THE SEED WITH NO MORE THAN 0.25 INCH OF SOIL.		
PERENNIAL RYE GRASS	30 LBS.	0.7 LBS.	BEST FOR FALL SEEDING. SEED FROM AUGUST 15 TO SEPTEMBER 15 FOR BEST COVER. SEED TO A DEPTH OF 1 INCH.		
SOURCES: 1. NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME 3, TABLE 4-1 2. MINNICK, E.L. AND H.T. MARSHALL, (AUGUST 1992)					

-WIRE SCREEN FLOW ___ CATCH BASIN

CIVIL ENGINEERS

-WIRE SCREEN

-CONCRETE BLOCK

(HOLLOW)

BLOCK AND GRAVEL DROP INLET SEDIMENT FILTER

SECTION

NOT TO SCALE

CONSTRUCTION SPECIFICATIONS

1. PLACE CONCRETE BLOCKS LENGTHWISE ON THEIR SIDE IN A SINGLE ROW AROUND THE PERIMETER OF THE INLET, WITH THE ENDS OF ADJACENT BLOCKS ABUTTING. THE HEIGHT OF THE BARRIER CAN BE VARIED, DEPENDING ON DESIGN NEEDS, BY STACKING COMBINATIONS OF 4-INCH, 8-INCH AND 12-INCH WIDE BLOCKS. THE BARRIER OF BLOCKS SHALL BE AT LEAST 12 INCHES HIGH AND NO GREATER THAN 24 INCHES HIGH.

WIRE MESH SHALL BE PLACED OVER THE OUTSIDE VERTICAL FACE (WEBBING) OF THE CONCRETE BLOCKS TO PREVENT STONE FROM BEING WASHED THROUGH THE HOLES IN THE BLOCKS. HARDWARE CLOTH OR COMPARABLE WIRE MESH WITH 1/2-INCH OPENINGS SHALL BE USED. STONE SHALL BE PILED AGAINST THE WIRE TO THE TOP OF THE BLOCK BARRIER, AS SHOWN IN FIGURE


16.7. STONE GRADATION SHALL BE WELL GRADED WITH THE MAXIMUM STONE SIZE OF 6 INCHES AND

4. IF THE STONE FILTER BECOMES CLOGGED WITH SEDIMENT SO THAT IT NO LONGER ADEQUATELY PERFORMS ITS FUNCTION, THE STONE MUST BE PULLED AWAY FROM THE BLOCKS, CLEANED AND REPLACED.

THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN AND REPAIRS MADE AS NEEDED. SEDIMENT SHALL BE REMOVED AND THE TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE

SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF THE TRAP. REMOVED SEDIMENT SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.

STRUCTURES SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.



THE DE-WATERING AREA WILL BE CONSTRUCTED BEFORE ANY PUMPING OCCURS AT

TEMPORARY DE-WATERING AREA TYPE, <u>ABOVE GRADE</u>, WILL BE CONSTRUCTED AS SHOWN ABOVE, WITH A RECOMMENDED MINIMUM LENGTH AND MINIMUM WIDTH OF

 $\frac{20-F1}{1}$.
THE DE-WATERING AREA WILL BE LOCATED AS SHOWN OR AS DIRECTED BY TEH ENVIRONMENTAL CONSULTANT.

GEOTEXTILE LINING WILL BE FREE OFTEARS, OR OTHER DEFECTS THAT COMPROMISE HE DURABILITY OF THE MATERIAL

THE DE-WATERING AREAS(S) WILL BE INSPECTED DAILY TO ENSURE THAT ALL SEDIMENT IS BEING DISCHARGED INTO THE HAYBALE DAM AREA, NO TEARS ARE

PRESENT AND TO IDENTIFY WHEN SEDIMENT NEED OT BE REMOVED. THE DE-WATERING AREA(S) WILL BE CLEANED OUT ONCE THE AREA IS FILLED TO 75 PERCENT OF ITS HOLDING CAPACITY.


3. ONCE THE HOLDING CAPACITY HAS BEEN REACHED THE SEDIMENT SHALL BE REMOVED AND DISPOSED OF OFF-SITE IN ACCORDANCE WITH LOCAL, STATE AND

THE GEOTEXTILE LINING WILL BE REPLACED IF TEARS OCCUR DURING REMOVAL OF SEDIMENT FROM THE DE-WATERING AREA.

DE-WATERING AREA DETAIL NOT TO SCALE

CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION. SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WITH IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS ASSOCIATES, INC. (603)-335-3948.

TRANSPORTATION PLANNERS



TEMPORARY VEGETATION:

INSTALL NEEDED EROSION AND SEDIMENT CONTROL MEASURES SUCH AS SILTATION BARRIERS, DIVERSIONS, AND

2. GRADE AS NEEDED FOR THE ACCESS OF EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH

APPLICATION, AND MULCH ANCHORING. RUNOFF SHALL BE DIVERTED FROM THE SEEDBED AREA.

SPECIFICATIONS:

4. ON SLOPES 4:1 OR STEEPER, THE FINAL PREPARATION SHALL INCLUDE CREATING HORIZONTAL GROOVES PERPENDICULAR O THE DIRECTION OF THE SLOPE TO CATCH SEED AND REDUCE RUNOFF.

STONES AND TRASH SHALL BE REMOVED SO AS NOT TO INTERFERE WITH THE SEEDING AREA.

TIMING IS CRITICAL FERTILIZER AND LIMESTONE MAY BE APPLIED AT THE FOLLOWING RATES:

WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOOSEN SOIL TO A DEPTH OF 2 INCHES BEFORE APPLYING FERTILIZER, LIME AND SEED. IF APPLICABLE, FERTILIZER AND ORGANIC SOIL AMENDMENTS SHALL BE APPLIED DURING THE GROWING SEASON. APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TEST RECOMMENDATIONS. FERTILIZER SHALL BE RESTRICTED TO LIME, WOOD ASH OR LOW PHOSPHATE AND SLOW RELEASE NITROGEN VARIETIES, UNLESS A

SOIL TEST WARRANTS OTHERWISE. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES, OR WHERE

LIMESTONE APPLICATION RATE = 3 TONS/ACRE (138 LB./1,000-SF)* *EQUIVALENT TO 50% CALCIUM PLUS MAGNESIUM OXIDE

FERTILIZER APPLICATION RATE = 870 LB./ACRE (20 LB./1,000-SF)* *LOW PHOSPHATE FERTILIZER (6-0-4) OR EQUIVALENT

I. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL CULTIPACKER TYPE SEEDER OR HYDRO SEEDER (SLURRY INCLUDING SEED AND FERTILIZER). NORMAL SEEDING DEPTH IS FROM 1/4 TO 1/2 INCH. HYDROSEEDING THAT INCLUDES MULCH MAY BE LEFT ON SOIL SURFACE. SEEDING RATES MUST BE INCREASED BY 10% WHEN HYDROSEEDING.


TEMPORARY SEED SHALL TYPICALLY OCCUR PRIOR TO SEPTEMBER 15. AREAS SEEDED BETWEEN MAY 15 AND AUGUST 15 SHALL BE COVERED WITH HAY OR STRAW MULCH,

ACCORDING TO THE "TEMPORARY AND PERMANENT MULCHING" PRACTICE DESCRIBED IN THE NHSSM, VOL 3. VEGETATED GROWTH COVERING AT LEAST 85% OF THE DISTURBED AREA SHALL BE ACHIEVED PRIOR TO OCTOBER 15. IF THIS CONDITION IS NOT ACHIEVED, IMPLEMENT OTHER TEMPORARY STABILIZATION MEASURES FOR OVER WINTER PROTECTION.

TEMPORARY SEEDING SHALL BE INSPECTED WEEKLY AFTER ANY RAINFALL EXCEEDING 1/2 INCH IN 24 HOURS ON ACTIVE CONSTRUCTION SITES. TEMPORARY SEEDING SHALL BE INSPECTED JUST PRIOR TO SEPTEMBER 15, TO ASCERTAIN WHETHER ADDITIONAL SEEDING IS REQUIRED TO PROVIDE STABILIZATION OVER THE WINTER

BASED ON INSPECTION, AREAS SHALL BE RESEEDED TO ACHIEVE FULL STABILIZATION OF EXPOSED SOILS. IF IT IS TOO LATE IN THE PLANTING SEASON TO APPLY ADDITIONAL SEED, THEN OTHER TEMPORARY STABILIZATION MEASURES SHALL BE IMPLEMENTED.

3. IF ANY EVIDENCE OF EROSION OR SEDIMENTATION IS APPARENT, REPAIRS SHALL BE MADE AND AREAS SHALL BE RESEEDED, WITH OTHER TEMPORARY MEASURES (I.E. MULCH, ETC.) USED TO PROVIDE EROSION PROTECTION DURING THE PERIOD OF VEGETATION ESTABLISHMENT.



TEMPORARY CONSTRUCTION EXIT

NOT TO SCALE

MAINTENANCE REQUIREMENTS:
1. WHEN THE CONTROL PAD BECOMES INEFFECTIVE, THE STONE SHALL BE REMOVED ALONG WITH THE

COLLECTED SOIL MATERIAL, REGRADED ON SITE, AND STABILIZED. THE ENTRANCE SHALL TEN BE RECONSTRUCTED. THE CONTRACTOR SHALL SWEEP THE PAVEMENT AT EXITS WHENEVER SOIL MATERIALS ARE TRACKED

ONTO THE ADJACENT PAVEMENT OR TRAVELED WAY. WHEN WHEEL WASHING IS REQUIRED, IT SHALL BE CONDUCTED ON AN AREA STABILIZED WITH

AGGREGATE, WHICH DRAINS INTO AN APPROVED SEDIMENT-TRAPPING DEVICE. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING STORM DRAINS, DITCHES, OR WATERWAYS.

CONSTRUCTION SPECIFICATIONS:

I. THE MINIMUM STONE USED SHALL BE 3—INCH CRUSHED STONE

THE MINIMUM LENGTH OF THE PAD SHALL BE 75 FEET, EXCEPT THAT THE MINIMUM LENGTH MAY BE REDUCED TO 50 FEET IF A 3-INCH TO 6-INCH BERM IS INSTALLED AT THE ENTRANCE OF THE

THE PAD SHALL BE THE FULL WIDTH OF CONSTRUCTION ACCESS ROAD OR 10 FEET, WHICHEVER IS

GREATER. THE PAD SHALL SLOPE AWAY FROM THE EXISTING ROADWAY

THE PAD SHALL BE AT LEAST 6 INCHES THICK. THE GEOTEXTILE FILTER FABRIC SHALL BE PLACED BETWEEN THE STONE PAD AND THE EARTH SURFACE

THE PAD SHALL BE MAINTAINED OR REPLACED WHEN MUD AND SOIL PARTICLES CLOG THE VOIDS IN THE STONE SUCH THAT MUD AND SOIL PARTICLES ARE TRACKED OFF-SITE.

NATURAL DRAINAGE THAT CROSSES THE LOCATION OF THE STONE PAD SHALL BE INTERCEPTED AND PIPED BENEATH THE PAD, AS NECESSARY, WITH SUITABLE OUTLET PROTECTION.

Not For Construction

TEMPORARY EROSION AND SEDIMENTATION CONTROL **DETAILS**

TAX MAP 243, LOT 34 145 AIRPORT DRIVE ROCHESTER, NH PREPARED FOR:

OF ROCHESTER

SCALE: AS SHOWN

DECEMBER 2019

NORWAY PLAINS ASSOCIATES, INC.


CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION. CONTACT

GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WIT

IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN

BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE

THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS




END SECTION CULVERT EXISTING SUB-GRADE GEOTEXTILE FABRIC SECTION A-A

RIP-RAP GRADATION

d50 = 3"							
% OF WEIGHT SMALLER THAN THE GIVEN SIZE	SIZE OF STONE (INCHES)						
100	5	TO	6				
85	4	TO	5				
50	3	TO	5				
15	1	TO	2				
d50 = 4"							

d50 = 4"						
% OF WEIGHT SMALLER THAN THE GIVEN SIZE	SIZE OF STONE (INCHES)					
100	6	TO	8			
85	5	TO	7			
50	4	ТО	6			
15	1	TO	2			




(PIPE OUTLET TO WELL DEFINED CHANNEL)

APRON DIMENSION TABLE 8' 8.5' 22' 12" 4" 18" CPP INLET 6' 6' 9" 3" 14'

4.5' 22'

12" CPP OUTLET

INTO BASIN 2



NOTES:
1. ALL PIPE CULVERTS SHALL HAVE END SECTIONS OR HEADWALLS. END SECTION MATERIAL AND MANUFACTURER SHALL MATCH THAT OF THE PIPE CULVERT.

- 2. THE LARGEST RIP-RAP SIZE DETERMINED DURING HYDROLOGIC ANALYSIS HAS BEEN USED FOR ALL OUTLETS FOR ECONOMY AND 3. APRON LENGTHS, WIDTHS AND THICKNESSES HAVE BEEN ROUNDED UP TO WHOLE NUMBERS FOR EASE OF CONSTRUCTION.
- PREPARE THE SUB-GRADE FOR THE FILTER MATERIAL, GEOTEXTILE FABRIC, AND RIP-RAP TO THE GRADES SHOWN ON THE PLANS.
- MINIMUM 6" SAND/GRAVEL BEDDING OR GEOTEXTILE FABRIC REQUIRED UNDER ALL ROCK RIP-RAP. THE ROCK OR GRAVEL USED FOR FILTER OR RIP-RAP SHALL CONFORM TO THE SPECIFIED GRADATION.
- GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF ROCK RIP-RAP. DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO (2) PIECES OF FABRIC SHALL BE A MINIMUM OF 12 INCHES.
- STONE FOR THE RIP-RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.
- 6. RIP-RAP SIZE CHOSEN FOR THE WORST CASE OF ALL OUTLETS. ALL RIP-RAP USED FOR PIPE OUTLET PROTECTION WILL HAVE THE SAME GRADATION AND THICKNESS.

MAINTENANCE NOTES: OUTLETS SHALL BE INSPECTED AND CLEANED ANNUALLY AND AFTER ANY MAJOR STORM EVENT. ANY EROSION OR DAMAGE TO THE RIP-RAP SHALL BE REPAIRED IMMEDIATELY.

THE CHANNEL IMMEDIATELY DOWNSTREAM FROM THE OUTLET SHOULD BE CHECKED TO SEE THAT NO EROSION IS OCCURRING. THE DOWNSTREAM CHANNEL SHOULD BE KEPT CLEAR OF OBSTRUCTIONS SUCH AS FALLEN TREES, DEBRIS, AND SEDIMENT THAT COULD CHANGE FLOW PATTERNS AND/OR TAILWATER DEPTHS ON THE PIPES. REPAIRS MUST BE CARRIED OUT IMMEDIATELY TO AVOID ADDITIONAL DAMAGE TO THE OUTLET PROTECTION APRON.

PIPE OUTLET PROTECTION DETAIL

DUST CONTROL PRACTICES:

- APPLY DUST CONTROL MEASURES AS NECESSARY TO MAINTAIN CONTROL OF DUST ON SITE.
- A) MOISTEN EXPOSED SOIL SURFACES PERIODICALLY WITH ADEQUATE WATER TO CONTROL DUST. B) AVOID EXCESSIVE APPLICATION OF WATER THAT WOULD RESULT IN MOBILIZING SEDIMENT AND SUBSEQUENT DEPOSITION IN NATURAL WATERBODIES.
- STONE APPLICATION: A) COVER SURFACE WITH CRUSHED OR COARSE GRAVEL.
- B) IN AREAS NEAR WATERWAYS USE ONLY CHEMICALLY STABILIZED OR WASHED AGGREGATE. REFER TO "NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME 3 CONSTRUCTION PHASE EROSION AND SEDIMENT CONTROLS, DECEMBER 2008" FOR OTHER ALLOWABLE DUST CONTROL PRACTICES (I.E. COMMERCIAL TACKIFIERS OR CHEMICAL TREATMENTS SUCH AS CALCIUM CHLORIDE, ETC.)

STOCKPILE PRACTICES:

- LOCATE STOCKPILES A MINIMUM OF 50-FT. AWAY FROM CONCENTRATED FLOWS OF STORMWATER, DRAINAGE
- PROTECT ALL STOCKPILES FROM STORMWATER RUN-ON USING TEMPORARY PERIMETER MEASURES SUCH AS DIVERSIONS, BERMS, SANDBAGS OR OTHER APPROVED PRACTICES.
- STOCKPILES SHALL BE SURROUNDED BY SEDIMENT BARRIERS AS DESCRIBED ON THE PLANS AND IN NHSMM VOL. 3. TO PREVENT MIGRATION OF MATERIAL BEYOND THE IMMEDIATE CONFINES OF THE STOCKPILE.
- IMPLEMENT WIND EROSION CONTROL PRACTICES AS APPROPRIATE ON ALL STOCKPILED MATERIAL.
- 5. PLACE BAGGED MATERIALS ON PALLETS OR UNDERCOVER.

PROTECTION OF INACTIVE STOCKPILES:
6. INACTIVE SOIL STOCKPILES SHALL BE COVERED WITH ANCHORED TARPS OR PROTECTED WITH SOIL STABILIZATION MEASURES (TEMPORARY SEED AND MULCH OR OTHER TEMPORARY STABILIZATION PRACTICE) AND TEMPORARY PERIMETER SEDIMENT BARRIERS (I.E. SILT FENCE, ETC.) AT ALL TIMES.

INACTIVE STOCKPILES OF CONCRÈTE RUBBLE, ASPHALT CONCRETE RUBBLE, AGGREGATE MATERIALS, AND SIMILAR MATERIALS SHALL BE PROTECTED WITH TEMPORARY SEDIMENT PERIMETER BARRIERS (I.E. SILT FENCE, ETC.) AT ALL TIMES. IF THE MATERIALS ARE A SOURCE OF DUST, THEY SHALL ALSO BE COVERED.

PROTECTION OF ACTIVE STOCKPILES:

- 8. ALL STOCKPILES SHALL BE SURROUNDED WITH TEMPORARY LINEAR SEDIMENT BARRIERS (I.E. SILT FENCE, ETC.) PRIOR TO THE ONSET OF PRECIPITATION. PERIMETER BARRIERS SHALL BE MAINTAINED AT ALL TIMES, AND ADJUSTED AS NEEDED TO ACCOMMODATE THE DELIVERY AND REMOVAL OF MATERIAL FROM THE STOCKPILE. THE INTEGRITY OF THE BARRIER SHALL BE INSPECTED AT THE END OF EACH WORKING DAY.
- WHEN A STORM IS PREDICTED, STOCKPILES SHALL BE PROTECTED WITH AN ANCHORED PROTECTIVE COVERING.

PERMANENT VEGETATION:

- SITE PREPARATION:
 1. INSTALL NEEDED EROSION AND SEDIMENT CONTROL MEASURES SUCH AS SILTATION BARRIERS, DIVERSIONS, AND SEDIMENT TRAPS 2. GRADE AS NEEDED FOR THE ACCESS OF EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH APPLICATION, AND MULCH ANCHORING.
- RUNOFF SHALL BE DIVERTED FROM THE SEEDBED AREA. 4. ON SLOPES 4:1 OR STEEPER, THE FINAL PREPARATION SHALL INCLUDE CREATING HORIZONTAL GROOVES PERPENDICULAR TO THE DIRECTION OF THE SLOPE TO CATCH SEED AND REDUCE
- WORK LIME AND FERTILIZER INTO THE SOIL AS NEARLY AS PRACTICAL TO A DEPTH OF 4 INCHES WITH A DISC, SPRING TOOTH HARROW OR OTHER SUITABLE EQUIPMENT. THE FINAL HARROWING OPERATION SHALL BE ON THE GENERAL CONTOUR. CONTINUE TILLAGE UNTIL A REASONABLY UNIFORM, FINE SEEDBED IS PREPARED. ALL BUT CLAY AND SILT SOILS SHALL
- BE ROLLED TO FIRM THE SEEDBED WHEREVER FEASIBLE. REMOVE FROM THE SURFACE ALL STONES 2INCHES OR LARGER IN ANY DIMENSION. REMOVE ALL OTHER DEBRIS, SUCH AS WIRE, CABLE, TREE ROOTS, CONCRETE CLODS, LUMPS, TRASH
- OTHER UNSUITABLE MATERIAL. INSPECT SEEDBED JUST BEFORE SEEDING. IF TRAFFIC HAS LEFT THE SOIL COMPACTED: THE AREA MUST BE TILLED AND FIRMED AS ABOVE.
- WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOOSEN SOIL TO A DEPTH OF 2 INCHES BEFORE APPLYING FERTILIZER, LIME AND SEED. IF APPLICABLE, FERTILIZER AND ORGANIC SOIL AMENDMENTS SHALL BE APPLIED DURING THE
- APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TEST RECOMMENDATIONS. FERTILIZER SHALL BE RESTRICTED TO LIME, WOOD ASH OR LOW PHOSPHATE AND SLOW RELEASE NITROGEN VARIETIES, UNLESS A SOIL TEST WARRANTS OTHERWISE. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES, OR WHERE TIMING IS CRITICAL FERTILIZER AND LIMESTONE MAY BE APPLIED AT THE FOLLOWING RATES:

LIMESTONE APPLICATION RATE = 3 TONS/ACRE (138 LB./1,000-SF)* *EQUIVALENT TO 50% CALCIUM PLUS MAGNÉSIUM OXIDE

FERTILIZER APPLICATION RATE = 870 LB./ACRE (20 LB./1,000-SF)* *LOW PHOSPHATE FERTILIZER (6-0-4) OR EQUIVALENT

12" 4"

18

- INOCULATE ALL LEGUME SEED WITH THE CORRECT TYPE OF INOCULANT. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL CULTIPACKER TYPE SEEDER OR HYDROSEEDER (SLURRY INCLUDING SEED AND FERTILIZER). NORMAL SEEDING DEPTH IS FROM 1/4 TO 1/2 INCH. HYDROSEEDING THAT INCLUDES MULCH MAY BE LEFT ON SOIL SURFACE.
- 3. WHERE FEASIBLE EXCEPT WHERE EITHER CULTIPACKER TYPE SEEDER OR HYDROSEEDER IS USED, THE SEEDBED SHALL BE FIRMED FOLLOWING SEEDING OPERATIONS WITH A ROLLER, OR 4. SPRING SEEDING USUALLY GIVES THE BEST RESULTS FOR ALL SEED MIXES OR WITH LEGUMES.
- PERMANENT SEEDING SHALL BE COMPLETED 45 DAYS PRIOR TO FIRST KILLING FROST. WHEN CROWN VETCH IS SEEDED IN LATE SUMMER AT LEAST 35% OF THE SEED SHALL BE HARD SEED (UNSCARIFIED). IF SEEDING CANNOT BE DONE WITHIN THE SPECIFIED SEEDING DATES, MULCH ACCORDING TO THE "TEMPORARY AND PERMANENT MULCHING" PRACTICE DESCRIBED IN THE NHSSM, VOL 3. AND DELAY SEEDING UNTIL THE NEXT RECOMMENDED SEEDING PERIOD.
- AREAS SEEDED BETWEEN MAY 15 AND AUGUST 15 SHALL BE COVERED WITH HAY OR STRAW MULCH, ACCORDING TO THE "TEMPORARY AND PERMANENT MULCHING" PRACTICE DESCRIBED IN
- THE NHSSM, VOL 3. VEGETATED GROWTH COVERING AT LEAST 85% OF THE DISTURBED AREA SHALL BE ACHIEVED PRIOR TO OCTOBER 15. IF THIS CONDITION IS NOT ACHIEVED, IMPLEMENT OTHER TEMPORARY STABILIZATION MEASURES FOR OVER WINTER PROTECTION.

- 1. WHEN HYDROSEEDING (HYDRAULIC APPLICATION), PREPARE THE SEEDBED AS SPECIFIED ABOVE OR BY HAND RAKING TO LOOSEN AND SMOOTH THE SOIL AND REMOVE SURFACE STONES LARGER THAN 2 INCHES IN DIAMETER.
- SLOPES BUST BE NO STEEPER THAN 2:1 (2 FEET HORIZONTALLY BY 1 FOOT VERTICALLY. LIME AND FERTILIZER MAY BE APPLIED SIMULTANEOUSLY WITH THE SEED. THE USE OF FIBER MULCH ON CRITICAL AREAS IS NOT RECOMMENDED (UNLESS IT IS USED TO HOLD STRAW OR HAY). BETTER PROTECTION IS GAINED BY USING STRAW MULCH AND HOLDING IT WITH ADHESIVE MATERIALS OR 500 POUNDS PER ACRE OF WOOD FIBER MULCH.

SEEDING RATES MUST BE INCREASED BY 10% WHEN HYDROSEEDING.

- PERMANENT SEEDED AREAS SHALL BE INSPECTED AT LEAST MONTHLY DURING THE COURSE OF CONSTRUCTION. INSPECTION, MAINTENANCE AND CORRECTIVE ACTIONS SHALL CONTINUE UNTIL THE OWNER ASSUMES PERMANENT OPERATION OF THE SITE. SEEDED AREAS SHALL BE MOWED AS REQUIRED TO MAINTAIN A HEALTHY STAND OF VEGETATION. MOWING HEIGHT AND FREQUENCY DEPEND OF TYPE OF GRASS COVER.
- BASED ON INSPECTION, AREAS SHALL BE RESEEDED TO ACHIEVE FULL STABILIZATION OF
- EXPOSED SOILS. 4. AT A MINIMUM 85% OF THE SOIL SURFACE SHALL BE COVERED BY VEGETATION. 5. IF ANY EVIDENCE OF EROSION OR SEDIMENTATION IS APPARENT, REPAIRS SHALL BE MADE AND AREAS SHALL BE RESEEDED. WITH OTHER TEMPORARY MEASURES (I.E. MULCH, ETC.) USED TO PROVIDE EROSION PROTECTION DURING THE PERIOD OF VEGETATION ESTABLISHMENT.

PERMANENT VEGETATION SEEDING RECOMMENDATIONS

USE	MIXTURE	SPECIES	LBS./ACRE	LBS./ 1,000-SF
STEEP CUTS AND FILLS, BORROW AND DISPOSAL AREAS	A	TALL FESCUE CREEPING RED FESCUE REDTOP TOTAL	20 20 2 42	0.45 0.45 0.05 0.95
WATERWAYS, EMERGENCY SPILLWAYS, AND OTHER CHANNELS WITH FLOWING WATER	A	TALL FESCUE CREEPING RED FESCUE REDTOP TOTAL	20 20 2 42	0.45 0.45 0.05 0.95
LIGHTLY USED PARKING LOTS, ODD AREAS, UNUSED LANDS, AND LOW INTENSITY RECREATION SITES	A	TALL FESCUE CREEPING RED FESCUE REDTOP TOTAL	20 20 2 42	0.45 0.45 0.05 0.95
PLAY AREAS AND ATHLETIC FIELDS (TOPSOIL ESSENTIAL FOR GOOD TURF)	F	CREEPING RED FESCUE KENTUCKY BLUEGRASS TOTAL	50 50 100	1.15 1.15 2.30

SOURCES:
1. NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME 3, TABLES 4-2 AND 4-3 MINNICK, E.L. AND H.T. MARSHALL, (AUGUST 1992)

GENERAL CONSTRUCTION PHASING:

- STABILIZATION:
 A SITE IS DEEMED STABILIZED WHEN IT IS IN A CONDITION IN WHICH THE SOIL ON SITE WILL NOT EXPERIENCE ACCELERATED OR UNNATURAL EROSION UNDER THE CONDITIONS OF A 10-YEAR STORM EVENT, SUCH AS BUT NOT LIMITED TO: A) IN AREAS THAT WILL NOT BE PAVED:
 - i) A MINIMUM OF 85% VEGETATIVE COVER HAS BEEN ESTABLISHED; ii) A MINIMUM OF 3-INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR A CERTIFIED COMPOST BLANKET HAS BEEN INSTALLED, OR; iii) EROSION CONTROL BLANKETS HAVE BEEN INSTALLED.
- B) IN AREAS TO BE PAVED: i) BASE COURSE GRAVELS HAVE BEEN INSTALLED.
- TEMPORARY STABILIZATION:
 ALL AREAS OF EXPOSED OR DISTURBED SOIL SHALL BE TEMPORARILY STABILIZED AS SOON AS PRACTICABLE BUT NO LATER THAN 45 DAYS FROM THE TIME OF INITIAL DISTURBANCE, UNLESS A SHORTER TIME IS SPECIFIED BY LOCAL AUTHORITIES, THE ONSTRUCTION SEQUENCE APPROVED AS PART OF THE ISSUED PERMIT OR AN INDEPENDENT MONITOR.
- 3. <u>PERMANENT STABILIZATION:</u>
 ALL AREAS OF EXPOSED OR DISTURBED SOIL SHALL BE PERMANENTLY STABILIZED AS 5. SOON AS PRACTICABLE BUT NO LATER THAN 3 DAYS FOLLOWING FINAL GRADING.
- MAXIMUM AREA OF DISTURBANCE:
 THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT IN NO CASE EXCEED 5 ACRES AT ANY ONE TIME BEFORE DISTURBED AREA ARE 5. ONLY DISTURB, CLEAR, OR GRADE AREAS NECESSARY FOR CONSTRUCTION
- A) FLAG OR OTHERWISE DELINEATE AREAS NOT TO BE DISTURBED.) EXCLUDE VEHICLES AND CONSTRUCTION EQUIPMENT FROM THESE AREAS TO PRESERVE NATURAL VEGETATION. 6. ALL GRADED OR DISTURBED AREAS INCLUDING SLOPES SHALL BE PROTECTED DURING
- CLEARING AND CONSTRUCTION IN ACCORDANCE WITH THE APPROVED GRADING AND DRAINAGE PLAN DEPICTED ON <u>SHEET C-3</u>.

 7. ALL EROSION AND SEDIMENT CONTROL PRACTICES AND MEASURES SHALL BE
- CONSTRUCTED, APPLIED AND MAINTAINED IN ACCORDANCE WITH THE APPROVED EROSION AND SEDIMENT CONTROL PLAN DEPICTED ON SHEET C-5.
 TOPSOIL REQUIRED FOR THE ESTABLISHMENT OF VEGETATION SHALL BE STOCKPILED IN THE AMOUNT NECESSARY TO COMPLETE FINISHED GRADING AND BE PROTECTED
- FROM EROSION. STOCKPILES, BORROW AREAS AND SPOILS SHALL BE STABILIZED AS DESCRIBED UNDER "SOIL STOCKPILE PRACTICES".
- 10. SLOPES SHALL NOT BE CREATED SO CLOSE TO PROPERTY LINES AS TO ENDANGER ADJOINING PROPERTIES WITHOUT ADEQUATE PROTECTION AGAINST SEDIMENTATION, EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER RELATED DAMAGE. 11. AREAS TO BE FILLED SHALL BE CLEARED, GRUBBED AND STRIPPED OF TOPSOIL TO
- REMOVE TREES, VEGETATION, ROOTS AND/OR OTHER OBJECTIONABLE MATERIALS. 12. AREAS SHALL BE SCARIFIED TO A MINIMUM DEPTH OF 3-INCHES PRIOR TO PLACEMENT OF TOPSOIL. TOPSOIL SHALL BE PLACED WITHOUT SIGNIFICANT
- COMPACTION TO PROVIDE A LOOSE BEDDING FOR PLACEMENT OF SEED. 13. ALL FILLS SHALL BE COMPACTED IN ACCORDANCE WITH PROJECT SPECIFICATIONS TO REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER RELATED PROBLEMS. FILL INTENDED TO SUPPORT BUILDINGS, STRUCTURES, SITE UTILITIES, CONDUITS AND OTHER FACILITIES, SHALL BE COMPACTED IN ACCORDANCE WITH LOCAL
- REQUIREMENTS OR CODES. 14. IN GENERAL, FILLS SHALL BE COMPACTED IN LAYERS RANGING FROM 6 TO 24 INCHES IN THICKNESS. THE CONTRACTOR SHALL REVIEW THE PROJECT GEOTECHNICAL REPORT AND/OR THE "PROJECT SPECIFIC PHASING NOTES" FOR SPECIFIC GUIDANCE.
- 15. ANY AND ALL FILL MATERIAL SHALL BE FREE OF BRUSH. RUBBISH. ROCKS (LARGER THAN 3/4 THE DEPTH OF THE LIFT BEING INSTALLED), LOGS, STUMPS, BUILDING DEBRIS, FROZEN MATERIAL AND OTHER OBJECTIONABLE MATERIALS THAT WOULD INTERFERE WITH OR PREVENT CONSTRUCTION OF SATISFACTORY LIFTS. 16. FROZEN MATERIAL OR SOFT, MUCKY OR HIGHLY COMPRESSIBLE (I.E. CLAY, SILT)
- MATERIALS ARE SUSCEPTIBLE TO ACCELERATED SETTLEMENT AND POTENTIAL ACCELERATED EROSION. WORK IN AREAS OF THESE MATERIALS SHALL BE PERFORMED UNDER THE DIRECTION OF A PROFESSIONAL ENGINEER. 17. THE OUTER FACE OF THE FILL SLOPE SHALL BE ALLOWED TO STAY LOOSE, NOT ROLLED OR COMPACTED, OR BLADE SMOOTHED. A BULLDOZER MAY RUN UP AND
- DOWN THE FILL SLOPE SO THE DOZER TREADS (CLEAT TRACKS) CREATE GROOVES PERPENDICULAR TO THE SLOPE. IF THE SOIL IS NOT TOO MOIST, EXCESSIVE COMPACTION WILL NOT OCCUR. SEE "SURFACE ROUGHENING" IN THE NHSMM, VOL.3. 18. ROUGHEN THE SURFACE OF ALL SLOPES DURING THE CONSTRUCTION OPERATION TO RETAIN WATER INCREASE INFILTRATION AND FACILITATE VEGETATION ESTABLISHMENT
- APPROPRIATE TO REDUCE THE LENGTH OF CUT-FILL SLOPES TO LIMIT SHEET AND RILL EROSION AND PREVENT GULLY EROSION. ALL BENCHES SHALL BE KEPT FREE OF SEDIMENT DURING ALL PHASES OF CONSTRUCTION. 20. SEEPS OR SPRINGS ENCOUNTERED DURING CONSTRUCTION SHALL BE EVALUATED BY A PROFESSIONAL ENGINEER (PREFERABLY THE DESIGN ENGINEER) TO DETERMINE IF

19. USE SLOPE BREAKS, SUCH AS DIVERSIONS, BENCHES, OR CONTOUR FURROWS AS

- THE PROPOSED DESIGN SHALL BE REVISED TO PROPERLY MANAGE THE CONDITION. 21. STABILIZE ALL GRADED AREAS (AS ABOVE) WITH VEGETATION, CRUSHED STONE, COMPOST BLANKET, OR OTHER GROUND COVER AS SOON AS GRADING IS COMPLETE OR IF WORK IS INTERRUPTED FOR 21 WORKING DAYS OR MORE. USE MULCH OR
- OTHER APPROVED METHODS TO STABILIZE AREAS TEMPORARILY WHERE FINAL GRADING MUST BE DELAYED. 22. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY FOLLOWING FINISHED GRADING. 23. THE PROJECT SHALL BE CONSTRUCTED TO MEET ALL REQUIREMENTS AND INTENT OF

RSA 430:53 AND CHAPTER ARG 3800 RELATIVE TO INVASIVE SPECIES.

ABOVE NOTES EXCERPTED, ADAPTED AND REFERENCED FROM "NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL, VOLUME 3 CONSTRUCTION PHASE EROSION AND SEDIMENT CONTROLS, DECEMBER 2008" (NHSMM, VOL. 3)

PROJECT SPECIFIC CONSTRUCTION PHASINGS

CIVIL ENGINEERS

. REFER TO THE "GENERAL CONSTRUCTION PHASING" NOTES PRIOR TO COMMENCING CONSTRUCTION IN ACCORDANCE WITH THE FOLLOWING PHASING. THE "GENERAL CONSTRUCTION PHASING" NOTES APPLY TO THE OVERALL CONSTRUCTION AND SHALL BE ADHERED TO

ASSOCIATES, INC. (603)-335-3948.

- 2. INSTALL ALL TEMPORARY SEDIMENT CONTROL BARRIERS (I.E. SILT FENCE, EROSION CONTROL MIX BERM, STONE CHECK DAMS, ETC.) AROUND THE OUTER PERIMETER OF THE CONSTRUCTION SITE AS DEPICTED ON SHEET
- C-5 PRIOR TO EARTH MOVING OPERATIONS. INSTALL ORANGE SNOW FENCE AROUND THE PEREMITER OF THE INFILTATION BASINS AND THE FENCE SHALL REMAIN IN PLACE UNTIL CONSTRUCTION OF
- THE BASINS HAS STARTED. 4. CLEAR, GRUB AND STRIP THE SITE. STUMPS, BRUSH AND OTHER ORGANIC WASTE SHALL BE DISPOSED OF OFF-SITE IN ACCORDANCE WITH STATE AND
- LOCAL REGULATIONS. INSTALL A TEMPORARY CONSTRUCTION EXIT AT THE LOCATION OF THE PROPOSED DRIVEWAY CONNECTION TO AIRPORT DRIVE. MAINTAIN AS
- DIRECTED BY THE TEMPORARY CONSTRUCTION EXIT DETAIL. STOCKPILE STRIPPED TOPSOIL AND CUT MATERIAL TO BE REUSED ON SITE IN AN APPROPRIATE LOCATION IN ACCORDANCE WITH THE "SOIL STOCKPILES PRACTICES". MAINTAIN THE STOCKPILES AS DIRECTED IN THE "SOIL STOCKPILE PRACTICES".
- PERFORM THE NECESSARY CUTS AND FILLS TO CONSTRUCT THE GRAVEL WETLANDS BASIN AS DEPICTED ON <u>SHEET C-3</u> AND IN ACCORDANCE WITH THE GRAVEL WETLAND BASIN DETAILS SHOWN ON <u>SHEET C-8</u>.

 PERFORM THE NECESSARY CUTS AND FILLS TO CONSTRUCT THE
- INFILTRATION BASIN AS DEPICTED ON SHEET C-3 AND IN ACCORDANCE WITH THE INFILTRATION BASIN DETAILS SHOWN ON <u>SHEET C-7</u>.

 CONSTRUCT THE GRAVEL WETLANDS BASIN, SEDIMENT FOREBAY AND OUTLET
- PROTECTION. LOAM SEED AND MULCH THE SIDE SLOPES OF THE BASIN AS DIRECTED IN THE INFILTRATION BASIN DETAILS. 10. ALL DITCHES/SWALES/AND BASINS SHALL BE STABILIZED PRIOR TO
- DIRECTING RÚNOFF TÓ THEM. 11. PERFORM THE NECESSARY CUTS AND FILLS TO SUBGRADE IN THE BUILDING AND PARKING LOT AREAS.
- A) INSTALL REQUIRED FILLS IN MAXIMUM 8-INCH LIFTS AND COMPACT EACH LIFT TO 95% MAXIMUM PROCTOR DENSITY. 12. AS SUBGRADE IS ACHIEVED INSTALL REMAINING SEDIMENT CONTROL BARRIERS WITHIN THE SITE (I.E. ADDITIONAL SILT FENCE, CHECK DAMS AND
- SEDIMENT CONTROLS AND CATCH BASINS, ETC.) 13. INSTALL ALL UTILITIES AND CLOSED DRAINAGE SYSTEM COMPONENTS (I.E. PIPE CULVERTS, CATCH BASINS AND REMAINING WATER MAIN) PER THE CORRESPONDING DETAILS AND AS SHOWN ON SHEET C-3 AND C-4. AS EACH STRUCTURE IS COMPLETED INSTALL THE CORRESPONDING

 14. CONSTRUCT THE INFILTRATION BASINS AND OUTLET PROTECTION. LOAM
- SEED AND MULCH THE SIDE SLOPES OF THE BASIN AS DIRECTED IN THE INFILTRATION BASIN DETAILS AND TEMPORARY SEDIMENT CONTROL BARRIER DEPICTED ON SHEET C-7.

 15. ALL CUT AND FILL SLOPES AND LAWN AREAS NOT TO BE PAVED SHALL BE
- LOAMED AND SEEDED FOR PERMANENT VEGETATION AND STABILIZATION AS DESCRIBED UNDER THE "PERMANENT VEGETATION PRACTICES" WITHIN 3 DAYS OF ACHIEVING FINAL GRADE
- 16. INSTALL ALL GRAVEL BASE AND CRUSHED GRAVEL MATERIALS FOR THE PARKING AREA AS SPECIFIED IN THE CORRESPONDING DETAILS.
- 17. THE PARKING AREAS SHALL BE STABILIZED (CONSTRUCTED TO GRAVEL BASE COURSE) WITHIN 3 DAYS OF ACHIEVING FINISHED SUBGRADE ELEVATIONS. 18. INSTALL PAVEMENT SURFACES AS SOON AS POSSIBLE AFTER THE INSTALLATION OF THE GRAVEL BASE AND CRUSHED GRAVEL, IN ORDER TO LIMIT THE SOIL EROSION AND POLLUTION OF THE GRAVEL MATERIALS WITH
- ORGANIC MATERIALS. IN NO CASE SHALL AREAS TO BE PAVED BE LEFT UNPROTECTED THROUGH OUT THE WINTER MONTHS. 19. ALL DISTURBED AREAS SHALL BE STABILIZED AS SOON AS POSSIBLE. IN NO CASE SHALL ANY DISTURBED AREA BE LEFT UN-STABILIZED FOR LONGER THAN 21 DAYS. IF NECESSARY TEMPORARY STABILIZATION MEASURES AS DISCUSSED IN THE "GENERAL CONSTRUCTION PHASING NOTES" AND NHSMM, VOL. 3 SHOULD BE EMPLOYED.
- <u>MAINTENANCE AND INSPECTION:</u> 20. DURING CONSTRUCTION ALL TEMPORARY AND PERMANENT SEDIMENT, EROSION CONTROL AND STORMWATER MANAGEMENT PRACTICES SHOULD BE
- INSPECTED WEEKLY, AFTER EVERY 1/2 INCH OF RAINFALL, AND ANNUALLY. 21. EXCESS SEDIMENT SHOULD BE REMOVED FROM TEMPORARY SEDIMENT, EROSION CONTROL AND STORMWATER MANAGEMENT PRACTICES WHEN IT REACHES PRESCRIBED THRESHOLDS DISCUSSED IN THE DETAILS FOR EACH PRACTICE.
- 22. ALL DAMAGED TEMPORARY AND PERMANENT SEDIMENT, EROSION CONTROL AND STORMWATER MANAGEMENT PRACTICES SHOULD BE REPAIRED OR REPLACED IMMEDIATELY UPON NOTICE. 23. SEDIMENT SHALL BE DISPOSED OF PROPERLY EITHER ON SITE OR OFF SITE. PROJECT COMPLETION AND STABILIZATION:
 24. UPON PROJECT COMPLETION, ONCE THE SITE IS DEEMED STABILIZED
- (VEGETATION IS GERMINATED). THE TEMPORARY SEDIMENT CONTROL BARRIERS AND EROSION CONTROL PRACTICES SHALL BE REMOVED. ANY DISTURBANCE CREATED DURING REMOVAL SHALL BE REPAIRED IN AN APPROPRIATE MANNER. 25. ACCUMULATED SEDIMENT SHALL BE REMOVED FROM ALL ON SITE CATCH

BASINS AND THE SEDIMENT FOREBAYS TO THE GRAVEL WETLANDS BASIN.

WINTER STABILIZATION & **CONSTRUCTION PRACTICES:**

- MAINTENANCE REQUIREMENTS: MAINTENANCE MEASURES SHALL BE PERFORMED THROUGHOUT CONSTRUCTION, INCLUDING OVER THE WINTER PERIOD. AFTER EACH RAINFALL, SNOWSTORM, OR PERIOD OF THAWING AND RUNOFF, THE SITE CONTRACTOR SHALL CONDUCT INSPECTION OF ALL INSTALLED EROSION CONTROL PRACTICES AND PERFORM REPAIRS AS NEEDED TO INSURE THEIR
- CONTINUED FUNCTION. 2. FOR ANY AREA STABILIZED BY TEMPORARY OR PERMANENT SEEDING PRIOR TO THE ONSET OF THE WINTER SEASON, THE CONTRACTOR SHALL CONDUCT AN INSPECTION IN THE SPRING TO ASCERTAIN THE CONDITION OF THE VEGETATION AND REPAIR ANY DAMAGED AREAS OR BARE SPOTS AND RESEED AS REQUIRED TO ACHIEVE AN ESTABLISHED VEGETATIVE COVER (AT LEAST 85% OF AREA VEGETATED WITH HEALTHY, VIGOROUS GROWTH.)

THE FOLLOWING STABILIZATION TECHNIQUES SHALL BE EMPLOYED DURING THE PERIOD FROM OCTOBER 15 THROUGH MAY 15. 1. THE AREA OF EXPOSED, UNSTABILIZED SOIL SHALL BE LIMITED TO 1-ACRE AND SHALL BE PROTECTED AGAINST EROSION BY THE METHODS DISCUSSE IN NHSMM, VOL. 3 AND ELSEWHERE IN THIS PLAN SET, PRIOR TO ANY

- THAW OR SPRING MELT EVENT. 2. STABILIZATION AS FOLLOWS SHALL BE COMPLETED WITHIN A DAY OF ESTABLISHING THE GRADE THAT IS FINAL OR THAT OTHERWISE WILL EXIST
- FOR MORE THAN 5 DAYS. A. ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF LESS THAN 15% WHICH DO NOT EXHIBIT A MINIMUM 85% VEGETATIVE GROWTH BY OR ARE DISTURBED AFTER OCTOBER 15, SHALL BE SEEDED AND COVERED WITH 3 TO 4 TONS OF HAY OR STRAW MULCH PER ACRE SECURED WITH ANCHORED NETTING, OR 2 INCHES OF EROSION CONTROL MIX (REFER TO NHSMM, VOL. 3 FOR SPECIFICATION).
- B. ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF GREATER THAN 15% WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OR ARE DISTURBED AFTER OCTOBER 15 SHALL BE SEEDED AND COVERED WITH A PROPERLY INSTALLED EROSION CONTROL BLANKET OR WITH A MINIMUM OF 4 INCHES OF EROSION CONTROL MIX, UNLESS OTHERWISE SPECIFIED BY THE MANUFACTURER. NOTE THAT COMPOST BLANKETS SHALL NOT EXCEED 2 INCHES IN THICKNESS OR THEY MAY
- OVERHEAT 3. ALL STONE COVERED SLOPES MUST BE CONSTRUCTED AND STABILIZED BY
- 4. INSTALLATION OF ANCHORED HAY MULCH OR EROSION CONTROL MIX SHALL
- NOT OCCUR OVER SNOW OF GREATER THAN 1 INCH IN DEPTH. 5. ALL MULCH APPLIED DURING WINTER SHALL BE ANCHORED (I.E. BY NETTING, TRACKING, WOOD CELLULOSE FIBER).
- 6. WITHIN 24 HOURS OF STOCKPILING SOIL MATERIALS SHALL BE MULCHED FOR OVER WINTER PROTECTION WITH HAY OR STRAW AT TWICE THE NORMAL RATE OR WITH A 4 INCH LAYER OF EROSION CONTROL MIX. MULCH SHALL BE REESTABLISHED PRIOR TO ANY RAIN OR SNOWFALL. NO SOIL STOCKPILE SHALL BE PLACED (EVEN COVERED WITH MULCH) WITHIN 100-FT
- OF ANY WETLAND OR OTHER WATER RESOURCE AREA. 7. FROZEN MATERIAL (I.E. FROST LAYER REMOVED DURING WINTER CONSTRUCTION) SHALL BE STOCKPILED SEPARATELY AND IN A LOCATION AWAY FROM ANY AREA NEEDING PROTECTION. FROZEN MATERIAL STOCKPILES CAN MELT IN SPRING AND BECOME UNWORKABLE AND
- DIFFICULT TO TRANSPORT DUE TO HIGH SOIL MOISTURE CONTEN 8. INSTALLATION OF EROSION CONTROL BLANKETS SHALL NOT OCCUR OVER SNOW OF GREATER THAN 1 INCH IN DEPTH OR ON FROZEN GROUND. 9. ALL GRASS-LINED DITCHES AND CHANNELS SHALL BE CONSTRUCTED BY SEPTEMBER 1. ALL DITCHES AND SWALES WHICH DO NOT EXHIBIT 85% VEGETATIVE GROWTH BY OR ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS AS DETERMINED BY A PROFESSIONAL ENGINEER. IF STONE LINING IS NECESSARY, THE
- PROVIDE ADEQUATE CROSS-SECTION AFTER ALLOWING FOR PLACEMENT OF 10. ALL STONE LINED DITCHES AND CHANNELS MUST BE CONSTRUCTED AND

CONTRACTOR MAY NEED TO RE-GRADE THE DITCH AS REQUIRED TO

- STABILIZED BY OCTOBER 15. 11. AFTER NOVEMBER 15, INCOMPLETE ROAD OR PARKING AREAS WHERE ACTIVE CONSTRUCTION HAS STOPPED FOR THE WINTER SHALL BE PROTECTED WITH A MINIMUM 3 INCH LAYER OF SAND AND GRAVEL WITH A GRADATION THAT IS LESS THAN 12% OF THE SAND PORTION. OR MATERIAL PASSING THE
- NUMBER 4 SIEVE, BY WEIGHT, PASSES THE NUMBER 200 SIEVE. 12. SEDIMENT BARRIERS THAT ARE INSTALLED DURING FROZEN CONDITIONS SHALL CONSIST OF EROSION CONTROL MIX BERMS, OR CONTINUOUS CONTAINED BERMS. SILT FENCES AND HAY BALES SHALL NOT BE INSTALLED WHEN FROZEN CONDITIONS PREVENT PROPER EMBEDMENT OF THESE BARRIERS.

Not For Construction

PERMANENT EROSION AND SEDIMENTATION CONTROL **DETAILS** TAX MAP 243, LOT 34 145 AIRPORT DRIVE ROCHESTER, NH

OF ROCHESTER

2 Continental Blvd., Rochester, N.H. 603-335-3948

PREPARED FOR:

SCALE: AS SHOWN


DECEMBER 2019

PLAN NO. C-3013 DWG NO. $19275 \SP$ F.B. NO. SDR-TJR

FILE NO. 104

CAREFULLY REVIEW ALL SHEETS OF THIS PACKAGE TO INSURE PROPER CONSTRUCTION. SPECIFIC SITE CONDITIONS SHOULD BE EXPLORED PRIOR TO CONSTRUCTION, CONTACT BOTH THE DESIGN ENGINEER AND THE PROJECT OWNER FOR ANY AVAILABLE GEOTECHNICAL OR HYDROGEOLOGICAL INFORMATION AVAILABLE BUT NOT CONTAINED WIT IN THE PLAN SET. IF THERE ARE ANY QUESTIONS WITH THE DESIGN PRESENTED IN THIS PLAN SET PLEASE CONTACT THE ENGINEERING STAFF AT NORWAY PLAINS ASSOCIATES, INC. (603)-335-3948.





WATER PIPE TRENCH INSTALLATION DETAIL


NOT TO SCALE

PAYMENT PAYMENT LIMIT 2" COPPER TUBING TYPE K 2" CORP. COPPER GOOSENECK CURB STOP & BOX LOCATION AS DIRECTED 2" TEE — BUILDING SERVICE PROPOSED WATER--BALL VALVE CURB STOP 2" COPPER SERVICE COMPRESSION (NO DRAIN) WATER SERVICE BRONZE FLARED TYPE COMPRESSION FITTINGS


NOTE: SERVICE LINE SHALL BE TYPE K COPPER CONFORMING TO ASTM-D88

TYPICAL DOMESTIC SERVICE CONNECTION

NOT TO SCALE



NOT TO SCALE



NOTES:

1. ALL NON-METALLIC CONDUIT AND FITTINGS SHALL BE ELECTRICAL GRADE, SCHEDULE 40 PVC, AND SHALL CONFORM TO THE APPLICABLE SECTIONS OF NEMA TC2-1990 AND BE UL LISTED. ONLY GRAY-COLORED CONDUIT WILL BE ACCEPTED. ANY PVC CONDUIT NOT HAVING THE PROPER NEMA AND UL MARKINGS WILL NOT BE ACCEPTED. ALL STEEL CONDUITS SHALL CONFORM TO ASTM A120 AND BE RIGID GALVANIZED STEEL. ALL PVC JOINTS MUST BE CEMENTED. STEEL FITTINGS SHALL BE SEALED WITH COMPOUND. 2. ALL 90 DEGREE SWEEPS WILL BE MADE USING RIGID GALVANIZED STEEL WITH A MINIMUM RADIUS OF 36 INCHES FOR PRIMARY CABLES AND 24 INCHES

- FOR SECONDARY CABLES. ALL STEEL SWEEPS WITHIN 18" OF THE SURFACE SHALL BE PROPERLY GROUNDED.

 3. A 10-FOOT HORIZONTAL SECTION OF RIGID GALVANIZED STEEL CONDUIT WILL BE REQUIRED AT EACH SWEEP, UNLESS IN THE OPINION OF THE PSNH DESIGNER. THE SWEEP-PVC JOINT IS NOT SUBJECT TO FAILURE DURING CABLE PULLING. THE CONDUIT SHALL CROSS PAVED AREAS AT APPROXIMATELY 90 DEGREES.
- 5. BACKFILL MAY BE MADE WITH EXCAVATED MATERIAL OR COMPARABLE, UNLESS MATERIAL IS DEEMED UNSUITABLE BY PSNH. BACKFILL SHALL BE FREE OF FROZEN LUMPS, ROCKS, DEBRIS, AND RUBBISH. ORGANIC MATERIAL SHALL NOT BE USED AS BACKFILL. BACKFILL SHALL BE THOROUGHLY 6. A SUITABLE PULL STRING, CAPABLE OF 200 POUNDS OF PULL, MUST BE INSTALLED IN THE CONDUIT BEFORE PSNH IS NOTIFIED TO INSTALL CABLE. THE STRING SHOULD BE BLOWN INTO THE CONDUIT AFTER THE RUN IS ASSEMBLED TO AVOID BONDING THE STRING TO THE CONDUIT. ROUTING OF THE CONDUIT AND INSPECTION PRIOR TO BACKFILL WILL BE PROVIDED BY PSNH. INSTALLATION OF THE CONDUIT WILL BE DONE BY THE CONTRACTOR. THE PSNH SUPERVISOR MUST BE NOTIFIED 2 BUSINESS DAYS PRIOR TO BACKFILLING THE TRENCH. IN THE EVENT THAT A CABLE CANNOT BE SUCCESSFULLY PULLED THROUGH THE COMPLETED CONDUIT SYSTEM DUE TO A CONSTRUCTION ERROR, IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO LOCATE AND REPAIR THE INVOLVED CONDUIT. THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL RESULTING EXPENSES. 8. NORMAL CONDUIT SIZES FOR PSNH ARE 3-INCH FOR SINGLE PHASE PRIMARY AND SECONDARY VOLTAGE CABLES, 4-INCH FOR THREE PHASE
- SECONDARY, AND 5-INCH FOR THREE PHASE PRIMARY. 9. ALL CONDUIT INSTALLATIONS MUST CONFORM TO THE CURRENT EDITION OF THE NATIONAL ELECTRIC SAFETY CODE, STATE AND LOCAL CODES AND ORDINANCES, AND WHERE APPLICABLE THE NATIONAL ELECTRIC CODE.


 10. CONDUIT MAY BE INSTALLED BY EXCAVATING AN OPEN TRENCH WITH SIDE SLOPES OF 1:1 MAXIMUM TO A DEPTH OF 4-FT. INSTALLATIONS DEEPER THAN 4-FT REQUIRE THE USE OF A TRENCH BOX.

ELECTRICAL & UNDERGROUND UTILITY TRENCH INSTALLATION DETAIL

NOT TO SCALE

GENERAL UTILITY NOTES

- 1.) CONTRACTOR SHALL NOTIFY DIG-SAFE (1-888 344-7233) 72 HOURS PRIOR TO THE START OF CONSTRUCTION.
- ALL EXISTING UTILITY LOCATIONS ARE APPROXIMATE AS SHOWN. THE CONTRACTOR SHALL VERIFY THEIR LOCATIONS AND ELEVATIONS.
- THESE PLAN SHOWS ONLY THOSE FEATURES THAT WERE VISUALLY APPARENT ON THE DATE OF THE SURVEY. THE ABSENCE OF SUBSURFACE STRUCTURES, UTILITIES, ETC. FROM THIS PLAN, BUT IN EXISTENCE IS NOT
- 4.) ANY UTILITY POLES THAT NEED TO BE RELOCATED SHALL BE COORDINATED WITH PSNH OR VERIZON, WHOM
- EVER HAS CONTROL OVER THEM. PROPOSED UTILITIES ARE TO BE UNDERGROUND. COORDINATE LOCATION OF UNDERGROUND UTILITIES AND TRANSFORMER PADS WITH PSNH AND OTHER PERTINENT UTILITY COMPANIES.
- WATER AND SEWER LINES SHALL BE INSTALLED A MINIMUM OF 10-FT APART HORIZONTALLY.
- WHERE SEWER AND WATER LINES MUST CROSS, SEWER PIPE JOINTS SHALL BE LOCATED A MINIMUM 9-FT HORIZONTALLY FROM THE WATER LINE AND A VERTICAL SEPARATION OF 18-INCHES SHALL BE MAINTAINED. SEWER PIPE JOINTS SHALL BE TESTED WITH ZERO LEAKAGE AT 25 POUNDS PER SQUARE INCH FOR GRAVITY
- SEWER AND AT 1-1/2 TIMES WORKING PRESSURE FOR ALL FORCE MAINS. WATERLINE CONSTRUCTION: A.) ALL PROPOSED WATER LINE MATERIAL USED SHALL MEET ROCHESTER WATER DEPARTMENT AND ROCHESTER
- ENGINEERING DEPARTMENT SPECIFICATIONS. WATER LINES SHALL BE A.W.W.A C 151, CLASS 52, CEMENT LINED, DUCTILE IRON PIPE. B.) PROPOSED WATER GATE VALVES SHALL BE MANUFACTURED BY KENNEDY OF AMERICAN FLOW CONTROL, RÉSILIENT SEAT TYPE.
- C.) ALL WATER LINES SHALL BE BURIED A MINIMUM OF 5'. D.) IF 5' OF COVER IS NOT AVAILABLE WATER LINE SHALL BE INSULATED AS SHOWN IN THE "SHALLOW COVER TRENCH DETAIL FOR INSULATED WATER PIPE".
- E.) ALL WATER FITTINGS SHALL BE CLASS 350. F.) PROPOSED WATER GATE VALVE SHALL OPEN CLOCKWISE (RIGHT).
- 10.) WORK TO CONNECT INTO THE WATER OR SEWER MAINS REQUIRES A PERMIT FROM THE ROCHESTER PUBLIC WORKS DEPARTMENT. CONTRACTORS ARE TO BE PRE-QUALIFIED.



POLE MOUNTED LIGHT DETAIL

NOT TO SCALE

LIGTH POLE BASE SHALL BE 18" ABOVE FINISH GRADE FOR NON VEHICLE IMPACT AREAS AND 30" FOR VEHICLE IMPACT AREAS. THE LIGTH POLE BASES CAN BE PRECAST, WITH COORDINATION WITH

Not For Construction

TAX MAP 243, LOTS 34 145 AIRPORT DRIVE ROCHESTER, NH PREPARED FOR: CITY OF ROCHESTER


SCALE: AS SHOWN

DECEMBER 2019

FILE NO. 104 PLAN NO. C-3013 DWG NO. 19275\SP-F.B. NO. SDR-TJR

NORWAY PLAINS ASSOCIATES, INC.


2 Continental Blvd., Rochester, N.H. 603-335-3948



TRANSPORTATION PLANNERS

MORTAR USED IN MANHOLE CONSTRUCTION SHALL COMPLY WITH THE FOLLOWING:
MORTAR SHALL BE COMPOSED OF TYPE II PORTLAND CEMENT AND SAND WITH OR WITHOUT HYDRATED LIME

THE ASTM C150/C150M STANDARD IN EFFECT AT THE TIME THE CEMENT WAS MANUFACTURED. HYDRATED LIME SHALL BE TYPE S THAT IS CERTIFIED BY ITS MANUFACTURER AS CONFORMING TO THE ASTM C207 STANDARD IN EFFECT AT THE TIME THE HYDRATED LIME WAS PROCESSED.



Not For Construction

IT IS INTENTION OF THE CITY OF ROCHESTER PUBLIC WORKS DEPARTMENT THAT THE MANHOLE, INCLUDING ALL COMPONENT PARTS HAVE ADEQUATE SPACE, STRENGTH AND LEAK PROOF QUALITIES CONSIDERED NECESSARY BY THE PUBLIC WORKS DEPARTMENT FOR THE INTENDED SERVICE. SPACE REQUIREMENTS AND CONFIGURATIONS, SHALL BE AS SHOWN ON THE DRAWING. MANHOLES MAY BE AN ASSEMBLY OF PRECAST SECTIONS, WITH OR WITHOUT STEEL REINFORCEMENT, WITH ADEQUATE JOINTING, OR CONCRETE CAST MONOLITHICALLY IN PLACE WITH OR WITHOUT REINFORCEMENT. IN ANY APPROVED MANHOLE, THE COMPLETE STRUCTURE SHALL BE OF SUCH MATERIAL AND QUALITY AS TO WITHSTAND LOADS OF 8 TONS (H-20 LOADING) WITHOUT FAILURE AND PREVENT LEAKAGE IN EXCESS OF ONE GALLON PER DAY PER VERTICAL FOOT OF MANHOLE, CONTINUOUSLY FOR THE LIFE OF THE STRUCTURE. A PERIOD GENERALLY IN EXCESS OF 25 YEARS IS TO BE UNDERSTOOD IN BOTH CASES.

BARRELS AND CONE SECTIONS SHALL BE PRECAST REINFORCED CONCRETE, OR POURED IN PLACE REINFORCED CONCRETE. PRECAST CONCRETE BARREL SECTIONS, CONES AND BASES SHALL CONFORM TO ASTM C478. ALL PRECAST SECTIONS AND BASES SHALL HAVE THE DATE OF MANUFACTURE AND THE NAME OR TRADEMARK OF THE MANUFACTURER IMPRESSED OR INDELIBLY MARKED ON THE INSIDE WALL.

VACUUM LEAKAGE TESTING (ASTM C1244) SHALL BE PERFORMED FOR ALL MANHOLES, LOW-PRESSURE AIR TESTING (ASTM F1417) AND DEFELECTION TRETING USING A 'GO/NO GO' MANDREL FOR ALL SANITARY SEWERS, IN ACCORDANCE WITH THE NHDES SEWER REGULATIONS AND THE CITY OF ROCHESTER DEPARTMENT OF PUBLIC WORKS REQUIREMENTS.

INVERTS AND SHELVES: MANHOLES SHALL HAVE A BRICK PAVED SHELF AND INVERT, CONSTRUCTED TO CONFORM TO THE SIZE OF PIPE AND FLOW. AT CHANGES IN DIRECTION, THE INVERTS SHALL BE LAID OUT IN CURVES OF THE LONGEST RADIUS POSSIBLE TANGENT TO THE CENTER LINE OF THE SEWER PIPES. SHELVES SHALL BE CONSTRUCTED TO THE ELEVATION OF THE HIGHEST PIPE CROWN AND SLOPE TO DRAIN TOWARD THE FLOWING THROUGH CHANNEL. UNDERLAYMENT OF INVERT AND SHELF SHALL CONSIST OF BRICK MASONRY. BRICK MASONRY CONFORM WITH ASTM C32. INVERTS AND SHELVES SHALL NOT BE INSTALLED UNTIL AFTER

FRAMES AND COVERS: MANHOLE FRAMES AND COVERS SHALL BE OF HEAVY DUTY DESIGN AND PROVIDE A 30-INCH CLEAR OPENING. A 3-INCH (MINIMUM HEIGHT) LETTER "SEWER" FOR SEWERS OR "DRAIN" FOR DRAINS SHALL BE PLAINLY CAST. INTO THE CENTER SEWER MANHOLE FRAME AND COVER: PAMREX 32" D.I. MANHOLE FRAME AND COVER SEWER — E.J.PRESCOTT PRODUCT# 62113-32-S. IMMEDIATELY FOLLOWING COMPLETION OF THE LEAKAGE TEST, THE FRAME AND COVER SHALL BE PLACED ON THE TOP OF THE MANHOLE OR SOME OTHER MEANS USED TO PREVENT ACCIDENTAL ENTRY BY UNAUTHORIZED PERSONS, CHILDREN, OR

ANIMALS, UNTIL THE CONTRACTOR IS READY TO MAKE FINAL ADJUSTMENT TO GRADE. BEDDING: MIN. 6" OF 3/4" CRUSHED STONE (12" IN LEDGE) FREE FROM CLAY, LOAM, ORGANIC MATTER AND MEETING ASTM C33: 100% PASSING 1 INCH SCREEN

90-100% PASSING 3/4 INCH SCREEN 20-55% PASSING 3/8 INCH SCREEN 0-10% PASSING #4 SIEVE

0-5% PASSING #8 SIEVE

WHERE ORDERED BY THE ENGINEER TO STABILIZE THE BASE, CRUSHED STONE MIN. 3/4" SHALL BE USED. CONCRETE FOR DROP SUPPORT SHALL CONFORM TO THE REQUIREMENT FOR CLASS A (3000#) CONCRETE OF THE NEW HAMPSHIRE DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS STANDARD SPECIFICATIONS AS FOLLOWS: CEMENT: 6.0 BAGS PER CUBIC YARD WATER: 5.75 GALLONS PER BAG CEMENT

MAXIMUM SIZE OF AGGREGATE: 1 INCH. 9. FLEXIBLE JOINT: A FLEXIBLE JOINT SHALL BE PROVIDED WITHIN THE FOLLOWING DISTANCES:

RCP & CI PIPE - ALL SIZES - 48" AC & VC PIPE - UP THROUGH 12" DIA. - 18" SEE NOTE 9.A.

AC & VC PIPE - LARGER THAN 12" DIA. - 36" DI PIPE- NONE REQUIRED

PVC (ASTM 3034) - UP THROUGH 15" DIA. - NONE REQUIRED PVC (ASTM F 679) -LARGER THAN 15" DIA. - 48" TO 60"

PVC (ASTM F 789) - ALL SIZES - 48" TO 60" 9.A. ÙNDER SEVEŔE CONDITIONS WHEN DIFFERENTIAL SETTING CANNOT BE CONTROLLED WITHIN NORMAL LIMITS, VARIATIONS IN HE STUB LENGTH MAY BE NECESSARY. OTHER PLASTIC PIPES SHALL BE REVIEWED ON A CASE BY CASE BASIS. SHALLOW MANHOLE: IN LIEU OF A CONE SECTION, WHEN MANHOLE DEPTH IS LESS THAN 6 FEET, A REINFORCED CONCRETE SLAB

COVER MAY BE USED HAVING AN ECCENTRIC ENTRANCE OPENING AND CAPABLE OF SUPPORTING H-20 LOADS. MANHOLE STEPS SHALL NOT BE PROVIDED WITHIN THE MANHOLES AS DIRECTED BY THE CITY OF ROCHESTER. MINIMUM SIZE PIPE FOR HOUSE SERVICE SHALL BE 4 INCHES.

13. PIPE AND JOINT MATERIALS P.V.C. (POLY VINYL CHLORIDE) PIPE: ALL P.V.C. PIPE AND FITTINGS SHALL CONFORM TO THE MOST RECENT REQUIREMENTS OF ASTM SPECIFICATIONS FOR TYPE PSM POLY VINYL CHLORIDE (P.V.C.) SEWER PIPE AND FITTINGS, DESIGNATION D-3034 AND ASTM SPECIFICATIONS FOR SEWER PIPE, JOINTS USING ELASTOMERIC SEALS, DESIGNATION D-3212 MANUFACTURER'S CERTIFICATE OF COMPLIANCE SHALL BE FURNISHED TO THE ENGINEER. PRIOR TO INSTALLATION METHODS OF HIPPING AND STORAGE ON SITE SHALL BE SUCH AS TO AVOID INJURY TO THE PIPE. DAMAGED PIPE SHALL BE REJECTED AND REMOVED FROM THE JOB. MINIMUM "PIPE STIFFNESS" (F/Y) AT 7 1/2° DEFLECTION SHALL BE 45 PSI FOR SIZE WHEN TESTED IN ACCORDANCE WITH ASTM METHODS OF TEST D-2412, "EXTERNAL LOADING PROPERTIES OF PLASTIC PIPE BY PARALLEL - PLATE LOADING." ALL P.V.C. PIPE SHALL BE TYPE SDR-35 (A MEASURE OF THICKNESS AND RIGIDITY) AND SHALL HAVE ELASTOMERIC D-2241 AND D-1784 (CLASS 1254-B). A SAFETY FACTOR OF 2.5 SHALL BE USED FOR PRESSURE RATING DETERMINATION WITH A STANDARD DIMENSION RATIO (SDR) NO HIGHER THAN 21.

DAMAGED PIPE SHALL BE REJECTED AND REMOVED FROM THE JOB SITE 15. JOINTS SHALL BE DEPENDENT UPON A NEOPRENE OR ELASTOMERIC GASKET FOR WATER TIGHTNESS. ALL JOINTS SHALL BE

PROPERLY MATCHED WITH THE PIPE MATERIAL USED. WHERE DIFFERING MATERIALS ARE TO BE CONNECTED, AS AT THE STREET SEWER WYE OR AT THE FOUNDATION WALL, APPROPRIATE MANUFACTURED ADAPTERS SHALL BE USED. 16. TEES OR WYES: WHERE A TEE OR WYE IS NOT AVAILABLE IN THE EXISTING STREET SEWER, AN APPROPRIATE CONNECTION SHALL BE MADE, FOLLOWING MANUFACTURERS INSTRUCTIONS USING A BOLTED, CLAMPED, OR EPOXY—CEMENTED SADDLE TAPPED INTO A SMOOTHLY DRILLED OR SAWN OPENING IN THE SEWER. THE PRACTICE OF BREAKING AN OPENING WITH A SLEDGE HAMMER, STUFFING CLOTH OR OTHER SUCH MATERIAL AROUND THE JOINT, OR APPLYING MORTAR TO HOLD THE CONNECTION, AND ANY OTHER SIMILAR CRUDE PRACTICES OR INEPT OR HASTY IMPROVISATIONS WILL NOT BE PERMITTED. THE CONNECTION SHALL BE CONCRETE ENCASED AS SHOWN IN THE DETAIL UP TO AND INCLUDING 15" DIAMETER. DOES (NOT APPLY TO INSTALLATIONS WHERE TEES & WYES ARE

PIPE INSTALLATION: THE PIPE SHALL BE HANDLED, PLACED, AND JOINTED IN ACCORDANCE WITH INSTALLATION GUIDES OF THE APPROPRIATE MANUFACTURER IT SHALL BE CAREFULLY BEDDED ON A 4 INCH LAYER OF CRUSHED STONE AS SPECIFIED IN NOTE 10. BEDDING AND RE-FILL FOR A DEPTH OF 12 INCHES ABOVE THE TOP OF THE PIPE SHALL BE CAREFULLY AND THOROUGHLY TAMPED BY HAND OR WITH THE APPROPRIATE MECHANICAL DEVICES. THE PIPE SHALL BE LAID AT A CONTINUOUS AND CONSTANT GRADE FROM THE STREET SEWER CONNECTION TO THE HOUSE FOUNDATION AT A GRADE OF NOT LESS THAN 1/8 INCH PER FOOT PIPE

JOINTS MUST BE MADE UNDER DRY CONDITIONS. IF WATER IS PRESENT, ALL NECESSARY STEPS SHALL BE TAKEN TO DEWATER THE 18. TESTING. THE COMPLETED HOUSE SEWER SHALL BE SUBJECTED TO A LEAKAGE TEST IN ANY OF THE FOLLOWING MANNERS (PRIOR A. AN OBSERVATION TEE SHALL BE INSTALLED AS SHOWN AND, WHEN READY FOR TESTING, AN INFLATABLE BLADDER OR PLUG

SHALL BE INSERTED JUST UPSTREAM FROM THE OPENING IN THE TEE AFTER INFLATION, WATER SHALL BE INTRODUCED INTO THE SYSTEM ABOVE THE PLUG TO A HEIGHT OF 5 FEET ABOVE THE LEVEL OF THE PLUG.

B. THE PIPE SHALL BE LEFT EXPOSED AND LIBERALLY HOSED WITH WATER, TO SIMULATE, AS NEARLY AS POSSIBLE, WET TRENCH CONDITIONS OR, IF THE TRENCH IS WET, THE GROUND WATER SHALL BE PERMITTED TO RISE IN THE TRENCH OVER THE PIPE INSPECTIONS FOR LEAKS SHALL BE MADE THROUGH THE CLEANOUT WITH A FLASHLIGHT.

C. DRY FLUORESCENCE DYE SHALL BE SPRINKLED INTO THE TRENCH OVER THE PIPE. IF THE TRENCH IS DRY, THE PIPE SHALL BE LIBERALLY HOSED WITH WATER, OR IF THE TRENCH IS WET, GROUND WATER SHALL BE PERMITTED TO RISE IN THE TRENCH OVER THE PIPE ORSERVATION FOR LEAKS SHALL BE MADE IN THE FIRST DOWNSTPFAM MANHOLE LEAKAGE ORSERVED. TRENCH OVER THE PIPE. OBSERVATION FOR LEAKS SHALL BE MADE IN THE FIRST DOWNSTREAM MANHOLE. LEAKAGE OBSERVED IN ANY OF THE ABOVE ALTERNATE TESTS SHALL BE CAUSE FOR NON-ACCEPTANCE AND THE PIPE SHALL BE DUG-UP IF

NECESSARY AND RE-LAID SO AS TO ASSURE WATER-TIGHTNESS. 19. ILLEGAL CONNECTION: NOTHING BUT SANITARY WASTE FLOW FROM THE HOUSE TOILETS, SINKS, LAUNDRY ETC. SHALL BE PERMITTED. ROOF LEADERS, FOOTING DRAINS OR SUMP PUMPS OR ANY OTHER SIMILAR CONNECTION CARRYING RAIN WATER, DRAINAGE, OR GROUND WATER, SHALL NOT BE PERMITTED.

20. HOUSE AND WATER SERVICE SHOULD NOT BE LAID IN THE SAME TRENCH AS SEWER SERVICE, BUT WHEN NECESSARY, SHALL BE PLACED ABOVE AND TO THE SIDE OF THE HOUSE SEWER AS SHOWN.

21. BEDDING: MIN. 3/4" CRUSHED STONE FREE FROM CLAY, LOAM, ORGANIC MATERIAL AND MEETING ASTM C33.6

100% PASSING 1 INCH SCREEN

90-100% PASSING 3/4 INCH SCREEN 20-55% PASSING 3/8 INCH SCREEN 0-10% PASSING #4 SIEVE 0-5% PASSING #8 SIEVE

WHERE ORDERED BY THE ENGINEER TO STABILIZE THE TRENCH BASE, MIN. 3/4" CRUSHED STONE SHALL BE USED. 22. LOCATION: THE LOCATION OF THE TEE OR WYE SHALL BE RECORDED AND FILED IN THE MUNICIPAL RECORDS. IN ADDITION, A FERROUS METAL ROD OR PIPE SHALL BE PLACED OVER THE TEE OR WYE AS DESCRIBED IN THE TYPICAL "CHIMNEY": DETAIL, TO AID IN LOCATING THE BURIED PIPE WITH A DIP NEEDLE OR PIPEFINDER.

23. CONCRETE: CONCRETE SHALL CONFORM TO THE REQUIREMENTS FOR CLASS A (3000 PSI.) CONCRETE OF THE NEW HAMPSHIRI DEPARTMENT OF PUBLIC WATER WORKS AND HIGHWAYS STANDARD SPECIFICATIONS AS FOLLOWS: CEMENT: 6.0 BAGS/C.Y.

WATER: 5.75 GALLONS/BAG OF CEMENT AGGREGATE: 11/2" MAX.

CHIMNEYS: IF VERTICAL DROP INTO SEWER IS GREATER THAN 4', A CHIMNEY SHALL BE CONSTRUCTED FOR THE HOUSE CONNECTION. 25- ALL DRAINAGE AND SEWER STRUCTURES INCLUDING FRAMES AND GRATES SHALL BE H-20 LOADING. 26- ALL SEWER CONSTRUCTION SHALL BE CONSTRUCTED TO NHDES AND THE CITY OF ROCHESTER STANDARDS & SPECIFICATIONS


27. HORIZONTAL JOINTS: BETWEEN SECTIONS OF PRECAST CONCRETE BARRELS SHALL BE OF A TYPE APPROVED BY THE COMMISSION, WHICH TYPE SHALL, IN GENERAL, DEPEND FOR WATER TIGHTNESS UPON AN ELASTOMERIC OR MASTIC—LIKE GASKET.

28. PIPE TO MANHOLE JOINTS: SHALL BE ONLY AS APPROVED BY THE COMMISSION AND IN GENERAL, WILL DEPEND FOR WATER TIGHTNESS UPON EITHER AN APPROVED NON-SHRINKING MORTAR OR ELASTOMERIC SEALANT.
 29. FOR BITUMASTIC TYPE JOINTS: THE AMOUNT OF SEALANT SHALL BE SUFFICIENT TO FILL AT LEAST 75% OF THE JOINT CAVITY

APPROVED BITUMASTIC SEALANTS: RAM-NEK KENT SEAL NO.2 EZ
30. THE CONTRACTOR SHALL NOTIFY DIG-SAFE 1-888-344-7233 PRIOR TO CONSTRUCTION.

SANITARY SEWER DETAILS TAX MAP 243, LOT 34 145 AIRPORT DRIVE ROCHESTER, NH PREPARED FOR:

OF ROCHESTER SCALE: AS SHOWN DECEMBER 2019





NORWAY PLAINS ASSOCIATES, INC.


C-13

2 Continental Blvd., Rochester, N.H. 603-335-3948

31 Mooney Street, Alton, N.H. 603-875-3948







Associates, LLC Consulting Structural Engineers
One Autumn Street Portsmouth, NH 03801

Phone: (603) 433 - 8639 www.jsneng.com City of Rochester Rochester, NH

New Industrial/Office Building


Airport Drive, Rochester, NH

-Preliminary-Not for Construction 10-10-19 Date: Scale: As Noted
Design By: RB
Approved By: -

noted

Floor Plan
A1.0

Project No: 191002



Associates, LLC
Consulting Structural Engineers

One Autumn Street
Portsmouth, NH 03801
Phone: (603) 433 - 8639
www.jsneng.com

City of Rochester Rochester, NH

New Industrial/Office Building

Airport Drive, Rochester, NH

-Preliminary-Not for Construction 10-10-19 Date: Scale: As Noted
Design By: RB
Approved By: -

Revisions

Elevations
A2.0

Project No: 191002