

City of Rochester
8/30/2018

Concrete Sidewalk Replacement Bid # 19-14
2:30 PM

Item #	Item	Northeast Earth Mechanics, Inc.	SUR Construction, Inc.
1	Removal and Disposal of Existing Sidewalk and Driveway Aprons (includes all asphalt concrete, and subbase material to depth)	\$6,600.00	\$35,200.00
2	Installation of cementitious Concrete Sidewalk (includes 4" concrete, fiber mesh, and 9" crushed gravel base)	\$115,200.00	\$147,840.00
3	Bituminous Concrete driveway aprons (includes 1.5" wearing course, 1.5" base course, and 10" crushed gravel base)	\$12,320.00	\$13,440.00
4	ADA accessible tip downs (includes installation)	\$38,700.00	\$27,450.00
5	Detectable warning panels (includes installation)	\$10,220.00	\$9,324.00
6	Remove and Reset Existing Granite Curb	\$28,800.00	\$63,000.00
7	Installation of New Granite Curb	\$5,400.00	\$7,200.00
8	Loam and Hydroseed	\$8,000.00	\$22,000.00
9	Maintenance of Traffic	\$168,000.00	\$61,500.00
	Total Bid Amount	\$393,240.00	\$386,954.00
Alternate			
2A	Installation of bituminous Concrete Sidewalk (includes 3" bituminous concrete and 10" crushed gravel base)	\$80,640.00	\$105,600.00