

**RIVER STREET PUMP STATION UPGRADE
ROCHESTER, NH**

ADDENDUM NO. 4

To be considered as part of the contract drawings and specification for the River Street Pump Station Upgrade, Bid No. 20-14.

SPECIFICATIONS

1. In Specification Section 15065, **DELETE** all references to cement mortar lining. All ductile iron pipe shall be ceramic epoxy lined.

QUESTIONS

The response to Question No. 24 provided in Addendum No. 3 has been modified. The Owner has elected to only allow ceramic epoxy lined ductile iron pipe. The revised response is as follows:

Q-24. Spec 15065 provides multiple options for ductile iron lining and external coatings. Please confirm which internal lining and which external coating systems are required for the site piping, the piping inside the wet wells, and piping inside the pump station.

A-24. *ONLY ceramic epoxy as specified, are acceptable lining systems. External coatings shall be as specified in Specification Section 09900, paragraph 2.02.C. and 2.02.D.*

END OF ADDENDUM 4

BY ORDER CITY OF ROCHESTER, NH